



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar



BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

Govt. of Bihar

EMERGENT REPAIR OF ROAD FROM SARVODAY CITY ADAMPUR TO LAKHANI BIGHA TAK



Name of the Road :-

EMERGENT REPAIR OF ROAD FROM SARVODAY CITY ADAMPUR TO LAKHANI BIGHA TAK

DISTRICT	:	Patna	
DIVISION	:	DANAPUR	
BLOCK	:	DANAPUR	
Total Length Of Road		0.600	km
Total Damaged Length Of Road	:	0.450	km
TOTAL COST OF CONSTRUCTION	:	11.694	Lacs
TOTAL COST OF PROJECT	:	11.694	Lacs

Executive Engineer
Rural Works Division, DANAPUR

प्रतिवेदन


कार्य का नाम : सर्वोदय सिटी आदमपुर से लखनी बिगहा पथ की
आपातकालीन मरम्मति ।

पथ की लम्बाई : 0.600 कि०मी०

प्राक्कलित राशि: मो० 11.694 लाख

मद : एफ०डी०आर०

प्रस्तुत प्राक्कलन दानापुर प्रखण्ड अन्तर्गत सर्वोदय सिटी आदमपुर से लखनी बिगहा पथ की आपातकालीन मरम्मति का वर्तमान अनुसूचित दर पर मो० 11.694 लाख (ग्यारह लाख उनहतर हजार चार सौ) रुपये मात्र का तैयार किया गया है । इस माह में लगातार अतिवृष्टि से पथ काफी क्षतिग्रस्त हो गया है । आवागमन बन्द है । विभागीय निर्देशानुसार पथ को मोटरेबूल करने हेतु ब्रीक्स वैट भरने का प्रावधान प्राक्कलन में किया गया है । जनहित में पथ को मोटरेबूल करना अति आवश्यक है । अतः प्राक्कलन की स्वीकृति जनहित में अतिआवश्यक है । पत्रिका में आशुतोष शर्मा जी की ओर से लिखी धारणाएँ स्वीकृति के लिए भेजी गई हैं ।


कनीय अभियंता
दानापुर

सहायक अभियंता
दानापुर


कार्यपालक अभियंता
(ग्रामीण कार्य विभाग)
कार्यप्रमंडल, दानापुर
01/09/2020

Details of Road & Bridge

Bill No.	Wing	Circle	District	Division	Road/Bridge Name	Scheme Name	Status (Comp./On Going)	Is Maintenance (Y/N)	Length (In Km)	Damage Part Length During Flood	Restoration Amount (in Lakh)	Remarks	FDR Fin Year	Type R/B	Start Point		Intermediate Point		End Point	
															Latitude	Longitude	Latitude	Longitude	Latitude	Longitude
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
1	CE-1, Patna	Patna	Patna	Danapur	Mukhya Khagaul Road Bataia to Adampur Mushari Tak ki one Jane Wall Road	FDR	On Going	No	1.100	0.900	21.439	Badly Damaged & Traffic Closed	2020-21	Road	25.59148	85.04251	25.59303	85.04251	25.5941	85.04251
2	CE-1, Patna	Patna	Patna	Danapur	Sarvodaya City Adampur to Lakhan Bigha Tak	FDR	On Going	No	0.600	0.450	11.694	Badly Damaged & Traffic Closed	2020-21	Road	25.59567	85.03197	25.59408	85.03197	25.5943	85.03197


 Mr. K. S. Singh
 01/09/2020

20/07/20
 HE

20/07/20
 HE

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

EMERGENT REPAIR OF ROAD FROM SARVODAY
CITY ADAMPUR TO LAKHANI BIGHA TAK

DISTRICT

PATNA


BLOCK

DANAPUR


DIVISION

DANAPUR

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	BRICK BATS	1029712.500
	TOTAL COST IN LACS =	10.297
	GST @ 12 % ON (PART A)	1.236
	LABOUR CESS GST @ 1 % ON (PART A)	0.103
	SUB TOTAL WITH GST & Labour cess	11.636
	CNC @0.5%	0.058
	TOTAL	11.694
	TOTAL COST OF PROJECT IN LACS =	11.694


20/07/20
JE
RWD


20/07/20
AE
RWD


11/9/20
EE
RWD

01/09/2024

पत्रांक:- 964/3132

मसौदी/दिनांक:- 16.10.2020

प्रेषक :

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल मसौदी।

सेवा में,

अधीक्षक अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, पटना।

विषय:-वर्ष-2019 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल करने हेतु किये गये कार्य की जाँच के संबंध में।

प्रसंग:-विभागीय पत्रांक-मु0अ0-4 (मु0) विविध (कार्य)-23-291/2019-3976 दिनांक-11.09.2019
एवं भवदीय पत्रांक-1481 दिनांक-15.09.2020

महाशय,

उपर्युक्त विषयक प्रासंगिक पत्र के निर्देश के आलोक में ग्रामीण कार्य विभाग, कार्य प्रमंडल दानापुर का निम्नलिखित दो पथों का दिनांक-13.10.2020 को बाढ़ क्षतिग्रस्त मरम्मत कार्य का जाँच किया गया एवं किया गया कार्य संतोषप्रद पाया गया।

सूचनार्थ समर्पित।

क्रमांक	पथ का नाम	पथ की लम्बाई	क्षतिग्रस्त पथ की लम्बाई
1	सर्वोदय सिटी आदमपुर से लखनी बिगहा पथ	0.600	0.450
2	मुख्य खगौल रोड बटाला से आदमपुर मुशहरी तक जाने वाली सड़क	1.100	0.900

अनु0:- निरीक्षण प्रतिवेदन प्रपत्र संलग्न।
(दो प्रतियों में)

विश्वासभाजन

16/10/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल मसौदी।

Inspection Report for Flood Damage Work

Date: 13/10/2020

- Executive
1. Name of PIU:- ~~En~~ Engineer R.W.D (W) Div. - Dhanapur.
2. Name of Block/Road:- Dhanapur / Sarvodaya City Aclampur to
3. For Road:- Laxmi Bigha Road.
4. Damage Location/Chainage:- Ch. 0 m to 350 m and 400 m to 500 m
5. Damage Length:- 450 m
6. Nature of Damage:- Damage due to heavy Rain.
I. Material being used in Restoration Works:- Brick bats
II. Equipments/Tools being used in Restoration Works:- J.C.B, Tractor, Roller
III. Procedure taken up in Restoration Works:- Brick bats spreading, laying and compacting
IV. Restored Length:- 450 m

B. For Bridge

1. Damage Location/Chainage:-
2. Damage Length:-
3. Nature of Damage:-
4. Details of Restoration Works:-
I. Material being used in Restoration Works:-
II. Equipments/Tools being used in Restoration Works:-
III. Procedure taken up in Restoration Works:-
IV. Restored Length
- NA
N.H.

Asst
Name of Inspector
Executive Engineer
R.W.D Works Division
Masaurhi