



लखीसराय समाहरणालय (जिला गोपनीय शाखा)



पत्रांक 2252 / गो0

लखीसराय, दिनांक- 30.09.2020

प्रेषक,

जिलाधिकारी,
लखीसराय।

सेवा में,

कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय।
विद्युत कार्यपालक अभियंता, विद्युत आपूर्ति प्रमंडल, लखीसराय।
कार्यपालक अभियंता, लोक स्वास्थ्य प्रमंडल, लखीसराय।

विषय :- 167-सूर्यगढ़ा विधान सभा अन्तर्गत सी०पी०एम०एफ के ठहराव हेतु आवश्यक व्यवस्था करने के संबंध में।

प्रसंग :- कार्यपालक दण्डाधिकारी, अनुमंडल, लखीसराय के पत्रांक-833 दिनांक-29.09.2020

महाशय,

उपर्युक्त विषयक एवं प्रासंगिक पत्र के द्वारा 167-सूर्यगढ़ा विधान सभा अन्तर्गत सी०पी०एम०एफ के ठहराव हेतु चयनित स्थलों का निरीक्षण प्रतिवेदन प्राप्त हुआ है। उक्त निरीक्षण के क्रम में कतिपय त्रुटियाँ पायी गयी, जो निम्न है :-

1. मध्य विद्यालय नवकाडीह, उरैन में पहुँच पथ नहीं पाया गया। विद्यालय जाने के रास्ते में अगल-बगल धान का खेत है। 200 मीटर रास्ता का निर्माण कराना आवश्यक है। कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय स्वयं निरीक्षण कर पहुँच पथ का निर्माण करायेंगे।
2. उत्क्रमित मध्य विद्यालय लहसोरवा, पीरी बाजार में रास्ते में बिजली का तार कम उँचाई पर पाया गया, जिससे बड़े वाहनों को आने-जाने में काफी परेशानी होगी। विद्युत कार्यपालक अभियंता, विद्युत आपूर्ति प्रमंडल, लखीसराय विद्युत तार के उँचाई की समस्या का निराकरण कर लेंगे।
3. मध्य विद्यालय अभयपुर, +2 उच्च विद्यालय, घोसैठ एवं मध्य विद्यालय माधोपुर, कजरा में चापाकल खराब पाया गया। कार्यपालक अभियंता, लोक स्वास्थ्य प्रमंडल, लखीसराय उक्त तीनों विद्यालयों में चापाकल मरम्मत कराना सुनिश्चित करायेंगे।

निदेश है कि तत्संबंधी समस्या का निराकरण 01 (एक) सप्ताह के अन्दर पूर्ण कराकर प्रतिवेदन उपलब्ध कराना सुनिश्चित करेंगे।

विश्वासभाजन


जिलाधिकारी,
लखीसराय।

बहार विधान सभा निर्वाचन-2020

167-सूर्यगढ़ा विधान सभा अन्तर्गत सी0पी0एम0एफ0 के ठहराव हेतु चयनित स्थलों की अध्ययन स्थिति

क्रमांक	स्थल का नाम	कमरों की संख्या	पेयजल की स्थिति		बिजली की व्यवस्था	शौचालय की संख्या	पहुँच पथ की स्थिति	अभ्युक्ति
			वोरिंग	चापाकल				
1	2	3		4	5	6	7	8
1	मध्य विधालय, अभयपुर।	11	वोरिंग है।	चापाकल खराब है। मरम्मती कराना अनिवार्य है।	हाँ	6	ठीक है।	
2	मध्य विधालय, नवकाडीह, उरैन।	30	वोरिंग है।	—	हाँ	8	नहीं है।	200 मीटर रास्ता का निर्माण कराना होगा। अगल-बगल धान का खेत है।
3	+2 उच्च विधालय, धोसैठ।	10+ (2 बड़ा हॉल)	वोरिंग है।	चापाकल खराब है। मरम्मती कराना अनिवार्य है।	हाँ	10	ठीक है।	
4	उत्कर्मित मध्य विधालय, लहसोरवा, पीरीबाजार।	20	वोरिंग है।	—	हाँ	6	ठीक है।	रास्ते में बिजली का तार नीचे है। बड़ी वाहन को जाने में कठिनाई होगी विद्युत विभाग को निदेश दिया जा सकता है।
5	मध्य विधालय माधोपुर, कजरा।	8	—	चापाकल खराब है। मरम्मती कराना अनिवार्य है।	हाँ	3	ठीक है।	
6	उत्कर्मित मध्य विधालय, पोखराना (पुराना भवन एवं नया भवन)	13	वोरिंग खराब है।	चापाकल है। (पुराना भवन)	हाँ	8	ठीक है।	पूर्व में यहाँ सी0पी0एम0एफ0 का ठहराव हो चुका है।

(रजिव मोहम्मद सहाय)

कार्यपालक दण्डाधिकारी
अनुमंडल, लखीसराय।

Original Copy



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

F.D.R

STATE :- BIHAR
DISTRICT :- Lakhisarai
BLOCK :- Surajgraha

NAUKA DIH TO MIDDLE SCHOOL URAIN

DETAILED PROJECT REPORT

LENGTH OF ROAD	0.300 KM
COST OF CONSTRUCTION INCLUDING 1% LABOUR CESS & 12% GST)	(Rs. 3.19 Lacs
TOTAL COST OF CONSTRUCTION	Rs. 3.19 Lacs

Submitted By:
Executive Engineer
RWD WORKS DIV -
Lakhisarai



PREPARED BY:
Shambhavi Techno Solutions Pvt. Ltd.
E/82, Rajesh Kumar Path
S.k. Puri, Boring Road, Patna - 1 (Bihar)

GENERAL ABSTRACT OF COST

NAME OF ROAD :- Nauka Dih to Middle School Urain

DISTRICT :- Lakhisarai

BLOCK :- Surajgraha

LENGTH OF ROAD :- 0.300 KM

LENGTH OF CONSTRUCTION :- 0.300 KM

LENGTH OF BT PAVEMENT :- 0.300 KM

LENGTH OF CC PAVEMENT :- 0.000 KM

NEW CD STRUCTURES


HUME PIPE :- 0 NOS.

RCC SLAB CULVERT :- 0 NOS.

Sl. No.	DESCRIPTION	AMOUNT (IN Rs.)
1	CONSTRUCTION COST	274616.00
	ADD 12% GST	32953.92
	ADD 1% LABOUR CESS	2746.16
	ADD 10% SEIGNIORAGE FEE ON BASIC RATE OF MINES MATERIAL	8582.00
	COST OF CONSTRUCTION (A)	318898.00

Sam B. 3-19-2020



24.11.2020
J.E.


23/11/2020
A.E.


24.11.2020
E.E.
RWD (W) Division
Lakhisarai

S.E.
RWD (W) Circle
Munger

Ref. E.E. Letter No.....1281.....dt.....24.11.2020
Technically Approved for Rs.....3.19 lakh
(Rupees.....Three lakh
nineteen thousand.....)Only,
for construction work & 5 Years Maintenance.


25/11/2020
SuperIntending Engineer
Rural Works Department
Works Circle, Munger


25.11.2020

COST ESTIMATE FOR ROAD CONSTRUCTION

Road: Nauka Dih to Middle School Urahi

Block: Surajgraha

District: Lakhisarai Length:

305 m

BSR Item No.	Description	No.	Length (M)	Width (M)	H/D (M)	Qty.	Unit	Rate (Rs.)	Amount
11.2	Sand Filling								
	Filling in foundation trenches as per drawing and technical specification Clause 305.3.9								
	Quantity As Per Pot Mesuarment	10	30	3.75	0.1	112.50	Cum	522.35	59155.50
4.1	Granular Sub-base with Well Graded Material (Table 400.1)								
	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with Vibrator Roller 8 Tonne capacity to achieve the desired density, complete as per Technical Specification Clause 401								
	Quantity As Per Pot Mesuarment	10	30	3.75	0.1	112.50	Cum	1918.57	215875.13
	Total Road work								274610.63
	Say Rs. (Lac)								2.75

[Signature]
24/11/2020
J.E.

[Signature]
23/11/2020
A.E.

[Signature]
24/11/2020
E.E.

RWD (W) Division
Lakhisarai

Nauka Dih To Middle School Urain



0.00 km.jpeg



0.050 km...jpeg



0.100 km.jpeg



0.150 km.jpeg