

3

Abstract of cost

Sch. XLV-Form No. 134

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
1) const. of reference pillar					
& working do				all	
QVTMBP ① = 0.92 km					
@ Rs 10315.56/km					Rs 9490.00
2) const. of reference pillar					
do				all comp	
QVTMBP ② = 0.92 km					
@ Rs 10549.45/km					Rs 9705.00
3) cleaning & grubbing road					
do				all	
QVTMBP ③ = 0.08 Hect					
@ Rs 51133.76/Hect					Rs 14317.00
4) const. of Embankment					
1000m lead do				all	
QVTMBP ④ = 270 m ³					
@ Rs 174.94/m ³					Rs 47234.00
5) const. of Embankment					
100m lead do				all	
QVTMBP ⑤ = 630 m ³					
@ Rs 58.70/m ³					Rs 36981.00
6) const. of subgrade					
fl shoulder do				all	
QVTMBP ⑥ = 1080 m ³					
@ Rs 176.58/m ³					Rs 190706.00

Continuation

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
7) const. of excavation for road weary do all comp					
QVMTMBP(2) = 25.11 m ³					
@ RS 74.16/m ³					RS 1862.00
8) const. of GSB grade					
do all comp					
QVMTMBP(3) = 21.225 m ³					
@ RS 2882.77/m ³					RS 61187.00
9) const. of PCC					
grade all					
QVMTMBP(4) = 79.57 m ³					
@ RS 3589.91/m ³					RS 285721.00
10) const. of PCC					
grade all					
QVMTMBP(5) = 168 m ³					
@ RS 7060.87/m ³					RS 1186226.00
11) PVC forming mmbg					
8mm board do all					
QVMTMBP(6) = 2 M					
QVMTMBP(7) = 2 M					
@ RS 11449.43/each					RS 22899.00
					1866328.00

Continuation

Sch. XLV-Form No. 134

6

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
		BA	18663	28.00	
Add 1st GST		(+)	223959.00		
Add 1st L. 0.04		(+)	18663.00		
			2108950.00		
Less 0.05% below		(-)	1054.00		
			Net	2107896.00	
				Limit 126473	
1899200		1899200	AB		
material statement					
E/w - 1920					

stone metal - 114.733m³
 stone chips - 151.20m³
 C. sand - 83.24m³
 cement - 1176 Bag.
 stone screening - 19.10m³

1899200
 1899200

Continuation

Rs 12,64,738 =