



लखीसराय समाहरणालय (जिला गोपनीय शाखा)



पत्रांक-2376/गो

लखीसराय, दिनांक- 16.10.2020

प्रेषक,

जिलाधिकारी
लखीसराय।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग, कार्य प्रमंडल,
लखीसराय।

विषय :-

बिहार विधान सभा आम निर्वाचन, 2020 के मददेनजर ग्रामीण क्षेत्र के सड़कों को वाहन परिचालन योग्य बनाने के संबंध में।

महाशय,


उपर्युक्त विषय के संबंध में कहना है कि बिहार विधान सभा आम निर्वाचन, 2020 को लेकर सभी प्रखंडों में मतदान केन्द्र बनाये गये हैं। मतदाताओं एवं मतदान कर्मियों/सुरक्षा बलों के मतदान केन्द्र तक सुगम पहुँच हेतु सम्पर्क पथ का वाहन परिचालन योग्य (Motorable) होना आवश्यक है। इस निमित्त जिला अन्तर्गत मरम्मत किये जाने वाले सड़क का विवरण इस प्रकार है :-

क्र०	पथ का नाम	सड़क की लम्बाई
01	रेहुआ रोड से बालिका विद्यापीठ के पीछे गेट नं०-02 (एन०एच०-80) तक सड़क	0.600 कि०मी०
02	रेहुआ रोड से आई०टी०आई० कैम्पस तक सड़क	0.300 कि०मी०
03	मध्य विद्यालय नवकाडीह से मध्य विद्यालय तक सड़क	0.60 कि०मी०
04	श्रृंगारपुर मोड़ से रामेश्वर धाम तक सड़क	1.10 कि०मी०
05	पचौता ग्राम से पतनेर मोड़ तक सड़क की मरम्मत	1.60 कि०मी०
06	दैताबोध रोड से पवैय हॉल्ट तक	1.2 कि०मी०
07	पचना सड़क से अमहरा तक	06 कि०मी०
08	गिरधरपुर पंचायत से सदायविगहा	
09	ऐजनीघाट से रेपुरा ग्राम तक	

ज्ञातव्य है कि लखीसराय जिले में दिनांक-28.10.2020 को प्रथम चरण में मतदान निर्धारित है। उक्त आलोक में उपरोक्त पथांशों को कार्य हित में मोटरेबुल करना आवश्यक है।

अतः अनुरोध है कि उक्त वर्णित सभी पथांशों का युद्धस्तर पर निर्वाचन तिथि के पूर्व मरम्मत/मोटरेबुल कराना सुनिश्चित करेंगे।

विश्वासभाजन


जिलाधिकारी,
लखीसराय।



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR(2245)

YEAR (2020 - 2021)

District Map



DISTRICT	:-	LAKHISARAI	
BLOCK	:-	SURAJGARHA	
NAME OF ROAD	:-	RESTORATION OF WORK FROM SRINGARPUR MORE SE RAMESHWAR DHAM TAK SADAK	
TOTAL LENGTH OF ROAD	:-	1.100	KM
TOTAL COST OF CONSTRUCTION INCLUDING 12% GST & 1% LABOUR CESS	:-	3.60	LAKH
COST OF ROAD CONSTRUCTION PER KM	:-	3.27	LAKH
5 YEAR MAINTENANCE COST INCLUDING 12% GST & 1% LABOUR CESS	:-	0.00	LAKH
Contingency 2.25% On Construction Cost	:-	0.00	LAKH
TOTAL COST OF PROJECT	:-	3.60	LAKH
TOTAL PROJECT COST PER KM	:-	3.270	LAKH

SUBMITTED BY:
EXECUTIVE ENGINEER
RWD (W) DIVISION, LAKHISARAI
LAKHISARAI

TA COPY
WITH S.F.



SHOT ON REDMI 7
AI DUAL CAMERA

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : RESTORATION OF WORK FROM SRINGARPUR MORE SE
RAMESHWAR DHAM TAK SADAK

DISTRICT LAKHISARAI
BLOCK SURAJGARHA

LENGTH OF ROAD (in Km) 1.100
LENGTH OF BT PAVEMENT 0.000
LENGTH OF CC PAVEMENT 0.000

CD STRUCTURES
HUME PIPE 0
RCC CULVERT 0

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL	
1	PREPARATORY WORKS ,SITE CLEARANCE , DISMANTLING	0.09
2	EARTHWORK	0.00
3	GSB	3.01
4	BRICK BATS	0.00
5	CC PAVEMENT	0.00
6	HARD SHOULDERING	0.00
7	ROAD FURNITURES , KM STONES , TRAFFIC & DIRECTION SIGN, PMGSY LOGO	0.00
8	CROSS DRAINAGE STRUCTURES	
I	HUME PIPE	0.00
II	RCC	0.00
III	BOX	0.00
IV	Utility Pipe (300 mm Dia)	0.00
V	DISMANTLING OF CD	0.00
VI	REPAIR OF CD WORK	0.00
	SUB TOTAL OF INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL	3.10
	AVERAGE COST PER KM (IN LACS)=	2.82
	TOTAL COST OF PROJECT IN LACS =	3.10


Junior Engineer

Assistant Engineer

Executive Engineer

RWD (w) Division, Lakhisarai

RWD (w) Division, Lakhisarai

RWD (w) Division,
Lakhisarai

Estimated Cost

Construction Cost : Rs. 3.60 Lakh

Ref. E.E. Letter No.....dt.....

Technically Approved for Rs. 3.60 Lakh

(Rupees Three lakh sixty

thousand) Only.

for construction work & 5 Years Maintenance.

✓

12/12/2020

Superintending Engineer

Rural Works Department

Works Circle, Munger

Cost Estimate for Road Work

FORMAT F6

Sl. No.	SDB Sl. No	MORD Ref. No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
SUB HEAD : PREPARATORY WORKS, SITE CLEARANCE, DISMANTLING											
1	2.2	201 (I-A)	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation , grass , bushes ,shrubs , saplings and trees of girth upto 300mm , removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification - clause 201.1 and direction of E/I								
				Ha	2	1,100.00	0.75		1,650.00 0.17	52,970.33	8,740.00
Sub Head : PAVEMENT LAYERS - GSB & WBM ITEMS											
2	4.1	401 (i)	Granular Sub-base with Well Graded Material (Table 400.1) (By mix in place method) For Grading II Material Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	Cum					220.52 220.52	1,364.88	3,00,987.00
			Net GSB Qty. Required form Grading I Material								
3		401	Supplying & filling of brick bats as per technical specification clause 401								
			Net GSB Qty. Required form Grading II Material								
			GSB in Widening Portion	Cum	0.00	550.00	4.050	0.600	0.00	1,526.65	0.00
			Net GSB Qty. Required form Grading II Material								
TOTAL COST OF PAVEMENT IN RS. =											3,09,727.00

[Signature]
Junior Engineer

Assistant Engineer

Executive Engineer

Name of work :- RESTORATION OF WORK FROM SRINGARPUR
MORE SE RAMESHWAR DHAM TAK SADAK
Annexure I

G.S.B

S.NO.	K.M.	N0	Length	Width	Depth	Quan.
1	Q	1	2.60	4.00	0.15	1.56
2		1	1.85	3.00	0.15	0.83
3		1	0.80	2.00	0.15	0.24
4		1	1.20	2.50	0.15	0.45
5		1	1.50	3.85	0.15	0.87
6		1	1.35	3.80	0.15	0.77
7		1	2.65	2.95	0.15	1.17
8		1	2.40	2.80	0.15	1.01
9		1	2.75	3.50	0.15	1.44
10		1	1.50	1.00	0.15	0.23
11		1	2.00	1.75	0.15	0.53
12		1	2.75	2.00	0.15	0.83
13		1	2.70	1.90	0.15	0.77
14		1	2.25	1.90	0.15	0.64
15		1	6.20	2.10	0.15	1.95
16		1	18.50	2.50	0.15	6.94
17		1	8.00	2.30	0.15	2.76
18		1	12.00	2.20	0.15	3.96
19		1	15.00	2.00	0.15	4.50
20		1	13.50	2.70	0.15	5.47
21		1	18.90	3.20	0.15	9.07
22		1	21.60	3.50	0.15	11.34
23		1	27.50	2.90	0.15	11.96
24		4	15.00	3.00	0.15	27.00
25		3	20.00	2.80	0.15	25.20
26		1	25.40	3.10	0.15	11.81
27		1	28.40	2.80	0.15	11.93
28		1	22.50	1.90	0.15	6.41
29		1	26.30	2.44	0.15	9.63
30		1	15.90	3.50	0.15	8.35
31		1	9.80	3.75	0.15	5.51
32		2	2.95	2.40	0.15	2.12
33		1	14.65	0.85	0.15	1.87
34		1	13.25	0.70	0.15	1.39
35		1	17.85	1.95	0.15	5.22
36		1	4.80	2.00	0.15	1.44
37		1	7.25	2.50	0.15	2.72
38		1	5.50	1.00	0.15	0.83
39		1	19.90	2.00	0.15	5.97
40		1	20.50	2.40	0.15	7.38
41		1	7.23	3.00	0.15	3.25
42		1	5.22	3.39	0.15	2.65
43		1	6.55	2.87	0.15	2.82
44		1	8.09	2.90	0.15	3.52
45		1	10.00	2.98	0.15	4.47
			392.03	Total		220.52

Handwritten signature and date:
20.10.2020
J.B