

NAME OF WORK : Detailed Estimate of traffic (Emergent Repair) in T047-T046 to Tarajliwar Road, due to heavy flood on dated. 12/07/2019 Block Aurai, for

the year 2019-20

Abstract				
Sl.No.	Description of Work	Unit	Qty.	Rate per Unit
1	Providing Supplying, laying & spreading of Brick bats to Cut fill all complete job	M ³	143.85	1527.85 1785.11
2	Providing supplying Laying & Spreading rubbish including the cost of carriage with cost all labour and materials complete job.	M ³	39.05	361.19 133.76
Sub total				28544.1
Labour cess 1%				2854.41
GST 12%				34252.97
Grand Total				322548.78
Say				322549.00

22/8/2019

JE(RWD) Muz. East-2


AE(RWD) Muz. East-2

प्रमाणित करे होरा स्वयं एवम अधिकारी द्वारा किया गया है।


Executive Engineer
RWD, WD, Muz. East-2

EE(RWD) Muz. East-2

Technically approved for Rs. 2.64 lac
(Rupees Two lac sixty four thousand) only.


18.08.19
WORKS CIRCLE
MUZAFFARPUR

अंत्राल कागजालत्र के आर्येडा आपाके 1230 दिनांक 26-8-19 एवं 1325 दिनांक 12-09-19
द्वारा गठित जांच दल से प्राक्कलन का जांच नहीं हो सका है/ जांचोपरान्त
प्राक्कलन के राशि में परिवर्तन हो सकता है/


18/9
WORKS CIRCLE
MUZAFFARPUR

R.W.D.(W) Sub Division, Aurai (Muzaffarpur)
NAME OF WORK : Detailed Estimate for Restoration of traffic in T047-T046 to Tarejiwar Road, due to heavy flood Damaged In Aurai Block for the year 2019-20

1 Supplying, laying & spreading of Brick bats by tractor etc. complete job as per specification and direction of E/I.								
SL NO		Nos	No./sides	Length (m)	Breadth (m)	Depth (m)	Total Qty.(m3)	Unit
1		1	1	20.00	6.850	0.600	82.20	
2		1	1	18.0	6.85	0.500	61.65	
				38.0				
Total							143.85	CUM
2 Providing Quarry material rubbish for filling the voids in brick bats including the cost of carriage with cost all labour and materials complete job as per specification and direction of E/I.								
SL NO		Nos	No./sides	Length (m)	Breadth (m)	Depth (m)	Total Qty.(m3)	Unit
1		1	1	20.0	6.85	0.150	20.55	
2		1	1	18.0	6.85	0.150	18.50	
Total							39.05	CUM

Scrp
 22/8/19
 J.E.

Scrp
 22/8/19
 A.E.

Scrp
 23/9/19
 E.E.

Measurement Verified and found Satisfactory

Scrp
 20/03/20
 A.E.

Scrp
 20/3/20
 T.A.