

① pre-filling the bricks-bats including the cost of bricks bats & labour all complete jobs as per specification & direction of E,

$$\begin{aligned}
 \text{ch. 50 to 75 M} & 2 \times 25.0 \times 1.00 \times \frac{1.00 + 0.30}{2} = 32.50 \text{ m}^3 \\
 \text{ch. - 75 to 100 M} & 1 \times 25.0 \times \frac{1.50 + 1.00}{2} \times \frac{0.60 + 0.90}{2} = 23.438 \text{ m}^3 \\
 \text{ch. - 100 to 200 M} & 1 \times 10.0 \times \frac{1.20 + 1.00}{2} \times \frac{0.60 + 0.80}{2} = 7.70 \text{ m}^3 \\
 & 1 \times 5.0 \times \frac{1.00 + 0.60}{2} \times \frac{0.60 + 0.40}{2} = 2.0 \text{ m}^3 \\
 & 1 \times 8.0 \times \frac{1.00 + 0.40}{2} \times \frac{0.60 + 0.30}{2} = 2.52 \text{ m}^3 \\
 & \underline{68.158 \text{ m}^3} \\
 & 63.638 \text{ m}^3
 \end{aligned}$$

$$\text{@ Rs } 1735.09/\text{m}^3 \text{ --- Rs } 110418.0$$

$$\text{Add 12% GST (+) Rs } 13250.0$$

$$\text{Add 5% L/C (+) Rs } 14191.31$$

$$\text{Rs } 1104.00 \text{ --- Rs } 1182.60$$

$$\text{Rs } 133634.31$$

$$\text{1,24,772.00}$$

$$\text{1,24,772.00}$$

कार्यालय अभियंता, आर आर वि, अरुणचम-गुवाहाटी
 - पत्रांक: - 284 अड्डा दिनांक: - 06/02/2020 से-आर वि अभियंता-अ-गुवाहाटी-
 - के आचार्य १२।

Post-Facto T/A for Rs 1,24,772.00 (Rupees one lac -
 twenty four thousand seven hundred seventy two only)

Superintending Engineer
 of RWD, Works Circle, Darbhanga
 07/02/2020

30.10.19
 J.E
 RWD

30/10/19
 A.E
 RWD

30/10/19
 E.E
 RWD