



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2020-21

Detailed Project Report

Division : Rosera

District :	Samastipur	Block :	Shivajinagar Rosera
------------	------------	---------	---------------------

Name of
Road :

REO Road to Bhirha

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

FDR

Detailed Estimate for

REO Road to Bhirha

Block : Shivajinagar Rosara
District : Samastipur

ABSTRACT OF COST FOR ROAD

Sl No	Item of Work	Amount (In Rs)	
		As per Estimate	
- 1	Total Cost for Pavement Works		262041.12
	Total Cost of Project :	Rs -	262041.12
	Total Cost Including (GST + L.Cess) 13% :	Rs -	34065.35
	Total :	Rs -	296106.47
	Say (Lakh) :	Rs -	2.96

Junior Engineer

RWD (W) Section, Shivajinagar
Rosa

Asstt. Engineer

RWD (W) S. Div. Shivajinagar
Rosenq

Executive Engineer

RWD (W) Div, Rosera

Technical Comy Approved for Rs 2.96 lac say Two lac
ninety six thousand and only.

6
 80
 19.1.24

FDR

REO Road to Bhirha

District : Samastipur

Block : Shivajinagar

Total Length (Km): 0.20

SI No	Reference To Mord Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
				L (m)	B (m)	D (m)				
1	401	Supply filling brick bat compacted manually								
			4	22.00	2.75	0.30	cum	72.60		
			6	15.00	2.25	0.35	cum	70.88		
			2	20.00	1.25	0.25	cum	12.50		
		Total Quantity :					cum	155.98	1680.02	262041.12
		Total Cost of Pavement in Rs :								2.62

24/12/20
 Junior Engineer
 RWD (W) Section, Shivajinagar

29/12/20
 Asst. Engineer
 RWD (W) S. Div. Shivajinagar
Rosera.

4-11-20
 Executive Engineer
 RWD (W) Div, Rosera

प्रतिवेदन

योजना का नाम :

REO Road to Bhirha


प्रस्तावित प्राक्कलन ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक-2789 दिनांक-21/08/2020 एवं समस्तीपुर जिलाधिकारी, समस्तीपुर के आदेश के अनुपालन के अलोक में मैं कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसड़ा के निदेशन में तैयार किया गया है। यह पथ विगत बाढ़ में डूबने एवं पानी के Over Lapping होने के कारण काफी क्षतिग्रस्त हो चुका है। इस पथ में क्षतिग्रस्त मर्दों का आवश्यकतानुसार दिनांक-1/7/20 से प्रभावी वर्तमान अनुसूचित दर पर प्रावधान किया गया है, जो जनहित में आवश्यक है। प्राक्कलन आवश्यक कार्रवाई हेतु समर्पित।


24/12/20

कनीय अभियंता

ग्रामीण कार्य विभाग


कार्य प्रशाखा, Shivajinagar


24/12/20

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल- Shivajinagar



कार्यपालक अभियंता

ग्रामीण कार्य विभाग,

कार्य प्रमंडल-रोसड़ा

ANALYSIS OF RATES.

BRICK BAT FILLING.

1. General sub

providing brick bats including spreading, laying stand packing with C.I. Hammer in layers not exceeding 75MM thick including cost of eight barriers, dangles, signal, chowkidar, taxes, Royalty, etc, all complete job, as per specifications and directions of S/O including cost of bricks, - - - all complete job.

Unit - cum.

assuming - 2.892 M³

Cost of Brick bats - 2.892 M³ @ 1096 = 00 - Rs 3169 = 87
 Maxdara Unskilled Labour 0.692 M³ @ 141 = 95/M³ Rs 89 = 65

Labour (unskilled)

1. Carrying, spreading, laying and packing unskilled labour 1.5 NO @ 287 = 00 - Rs 430 = 50
 Compaction of brick bats with C.I. Hammer, 0.670 NO @ 287 = 00 - Rs 192 = 29.
 Over Head Charge @ 6% on (a+b) - Rs 228 = 99.
 Total - 4045 = 29
 Rate / M³ - Rs 1428 = 42 / M³.

Carrriage cost

Carrriage for Bricks (1 M³ @ 100 NO @ 669 = 50/M³ - Rs 199 = 06
 Local Sand 0.320 M³ @ 97 = 00 / M³ - Rs 21 = 34.
 Total Rs 1648 = 81.
 31 = 24
 Rs 1680 = 02

2. Granular sub. base, with well Graded Material, Tack Coat by Mix and Place Method, for Grading

II Material all complete job.
 300.0 M³

Labour - Note - 0.48 NO @ 305 = 00 - Rs 146 = 40
 Maxdara Unskilled - 2.0 NO @ 364 = 00 - Rs 728 = 00
 Maxdara Unskilled - 10.0 NO @ 287 = 00 - Rs 2870 = 00

Material

Tractor Motor Grader 6.0 Hour @ 573 = 20 Rs 3439 = 20
 Three wheel 80-100 KN 30.0 Hour @ 803 = 00 / Hr - Rs 24090 = 00
 10 M³ / Hour
 Tractor with vibrator 12.0 Hour @ 573 = 20 - Rs 6878 = 40
 25 M³ / Hour
 Water Tanker 6kg Capacity 5.0 H @ 184 = 00 - Rs 920 = 00
 Total 39072 = 00

Material

Course Graded Granular sub base
 53MM to 9.5MM, 95% - 134.40 M³ @ 604 = 91/M³ - Rs 80695 = 00
 9.5MM to 2.36MM 25% 96.00 M³ @ 514 = 58/M³ - Rs 49400 = 00
 2.36MM below Local Sand 153.60 M³ @ 141 = 85/M³ - Rs 21788 = 00
 Total - 1,92,155 = 00
 Add over Head Charge 6% - Rs 11529 = 00
 Total - 2,03,684 = 00

कार्यपालक अभियंता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, समस्तीपुर।

पत्रांक..... १५०१ २०१५/१६

दिनांक 24.12.20

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, रोसड़ा।

विषय:- FDR अन्तर्गत पथों को जाँच करने के संबंध में।


प्रसंग:- आपका पत्रांक 22.12. दिनांक 22.12.20

महाशय,

उपर्युक्त प्रासंगिक विषयक के संबंध में कहना है कि आपके द्वारा निम्न पथों की सूची जाँच करने हेतु समर्पित किया गया था। पथों की जाँच की गई एवं जाँचोपरान्त सभी पथ पूर्ण पाया गया। प्रतिवेदन के साथ आवश्यक कार्रवाई हेतु समर्पित।

अनु०:- यथोक्त।


विश्वासभाजन



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसड़ा अंतर्गत FDR के तहत मरम्मत कराए गए पथों की सूची एवं जांच से संबंधित प्रतिवेदन

क्रम	प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए गए पथ की लंबाई	प्राक्कलित राशि	अभ्युक्ति
1	Rosera	Mabbi Halt to Hanuman Nagar Path	Brick Bat Filling.	1.83	9.79	पूर्ण
2	Rosera	Udaipur Gaddi to Chakki Dhab	Brick Bat Filling	0.60	8.76	पूर्ण
3	Rosera	Sonupur Panchgama Motipur Path	Brick Bat Filling	2.00	7.91	पूर्ण
4	Rosera	Sonupur Paswan Tola	Brick Bat Filling	0.60	3.38	पूर्ण
5	Rosera	Rosera Purab gumti to Batha	Brick Bat Filling	1.00	9.95	पूर्ण
6	Rosera	Rosera Pachim Gumti se Sahiyar Dih	Brick Bat Filling	1.50	8.98	पूर्ण
7	Rosera	Panchwati chowk se bandh	Brick Bat Filling	1.20	4.98	पूर्ण
8	Rosera	Jahangir Se lalpur sthan tak	Brick Bat Filling	0.50	2.42	पूर्ण
9	Rosera	Rosera Station Road to UR College	Brick Bat Filling	1.00	7.84	पूर्ण
10	Rosera	L058-T01 Vishwakarma chowk to Dhattha purbi (VR40)	Brick Bat Filling	1.50	9.78	पूर्ण
11	Rosera	Utkarmit Madhya Vidhyalay Makhtab Motipur	Brick Bat Filling	0.01	0.64	पूर्ण
12	Rosera	Bharwari se Tekunamath	Brick Bat Filling	0.25	1.67	पूर्ण
13	Rosera	REO Road to Bhirha	Brick Bat Filling	0.20	2.96	पूर्ण
14	Rosera	SDO office se UR College	Brick Bat Filling	0.90	2.92	पूर्ण
15	Rosera	Mabbi Govindpur Daxin Tola	Brick Bat Filling	5.00	6.94	पूर्ण
16	Rosera	PWD Road to Thatiya	Brick Bat Filling	0.15	2.94	पूर्ण
17	Rosera	Railway Line to Dargah	Brick Bat Filling	0.20	3.92	पूर्ण


 24.12.20
 कार्यपालक अभियंता
 ग्रामीण कार्य विभाग, कार्य प्रमंडल-समस्तीपुर