

GOVERNMENT OF BIHAR

UNDER FLOOD DAMAGE REPAIR

Estimate for Restoration of Traffic

DISTRICT :	WEST CHAMPARAN	BLOCK :	NARKATIAGANJ
------------	----------------	---------	--------------

YEAR(2020-2021)

NAME OF ROAD :	KOIRGANMA TO RAJPUR
----------------	---------------------

TOTAL LENGTH	:	0.076	KMS	
--------------	---	-------	-----	--

COST OF PAVEMENT (RS.)	:	1593505.08		
------------------------	---	------------	--	--

TOTAL COST OF ROAD (RS.)	:	1593505.08		
--------------------------	---	------------	--	--

SUBMITTED BY

Executive Engineer RWD

Works Division, Narkatiaganj

TECHNICAL REPORT

Name of Road :- Koingamara to Rajpur

Name of Block :- Narkatiyaganj

Name of Division :- Narkatiyaganj

Name of District :- West Champaran

Estimated Cost :- 15.93505 lakh

Restoration Length :- 0.076 KM

This Estimate is prepared for Restoration of Koingamara to Rajpur

.....road under FDR as per the instruction of Secretary, Rural Works Department, Patna vide,
ज्ञापक:- मु0अ0 -4 (मु0) विविध (कार्य) 23 -40 /16-2254 पटना, दिनांक 30.06.2020. Road remains effected
from flooded about 01 to 02 weeks and heavy amount of water passed through it.

Honorable Chief Minister/Secretary, Rural Works Department, Bihar, Patna/D.M., West Champaran
Bettiah/Concerned MP/MLA has instructed to maintain the traffic and movement of public etc. at the
earliest so that public of this area may get connected and for the same Departmental instruction has also
been issued to fill the gap made by flooded immediately.

The area surrounding is submerged in water and hence provision of Brick bat
Thana brick.....has been made to
maintain the road damage due to flood/heavy rainfall as per availability of material from available place by
tractor. Presently there is no Contractor is employed for Construction and Maintenance of this road hence
the work has been carried out Departmentally and due to this, provision of Contractor profit is not
mentioned in the estimate.

In view of above, it is requested to approve the estimate amounting to Rs. 15.93505 lakh please.

Submitted for Technical Approval please.

B. Kumar
23/12/2020
Junior Engineer,
Narkatiyaganj

[Signature]
23/12/2020
Assistant Engineer,
Narkatiyaganj

[Signature]
23/12/20
Executive Engineer
R.W.D.(W) Division, Narkatiyaganj

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

पत्रांक-.....954...../ बगहा-2, दिनांक-.....24.1.12/2020/

प्रेषक:-

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बगहा-2।

सेवा में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

विषय:- वर्ष 2020 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जॉच के संबंध में।

प्रसंग:- भवदीय पत्रांक-1312/बेतिया, दिनांक-26.08.2020।
महाशय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, नरकटियागंज द्वारा उपलब्ध कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी द्वारा सहायक अभियन्ता श्री दिगम्बर झा एवम् श्री नन्द किशोर साह के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, नरकटियागंज द्वारा प्रतिवेदित सभी पथों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।

अनु0:- निरीक्षण किये गये पथों की सूची।

विश्वासभाजन,


24/12/20

(दिगम्बर झा)
सहायक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बगहा-2

(नन्द किशोर साह)
सहायक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बगहा-2


24/12/20
(आनन्द बिहारी झा)
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बगहा-2

ज्ञापांक-.....954...../ बगहा-2, दिनांक-.....24.1.12/2020/

प्रतिलिपि:- कार्यपालक अभियन्ता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, नरकटियागंज को सूचनार्थ सम्प्रेषित।


24/12/20
कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बगहा-2

71	Narkatiaganj	L022 to Rakhahi	0.302	4,15,914.00
72	Narkatiaganj	Belwa to Sirisiya	0.446	12,52,033.00
73	Narkatiaganj	Pokhariya to Trilokwa	0.315	9,10,369.00
74	Narkatiaganj	REO Road to Bargajwa	0.24	5,73,469.00
75	Narkatiaganj	Koirgaun to Rampur	0.076	15,53,505.00
76	Narkatiaganj	Bargajwa me transformar Kabristan to Manjhi Sha ke Dukan tak	0.28	6,74,805.00
77	Narkatiaganj	Sathi to Bhashurari (Hichhopal)	0.68	15,44,539.00
78	Narkatiaganj	Semra Mandir to Pipra me Ramprawesh Ke ghar tak	0.22	3,10,358.00
79	Narkatiaganj	Sikarpur to Malda	0.21	16,57,218.00
Total			15.664	7,47,61,792.00

24/11/2020
OE

24/11/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल नरफटियागंज

24/11/2020
Executive Engineer
RWD (W) Div., Bagaha-2

COST ESTIMATE FOR traffic Restoration

Name of Road: KOIRGANMA TO RAJPUR
District: WEST CHAMPARAN

Block: NARKATIAGANJ Length: 76.000 m
Cutting length 76 M

S. No.	SOR Item No.	Description	No	Length (M)	Width (M)	H/D (M)	Qty.	Unit	Rates (in Rs.)	Amount
1	RCD	Laying brick bats on prepared soil surface as per Specification & direction of Engineer Incharge								
		As per measurement					684.68	cum	1703.77	1166545.40
2	RCD	Laying Jhama metal on prepared soil surface as per Specification & direction of Engineer Incharge								
		As per measurement					91.75	cum	2106.67	193286.78
		Total Road work								1359832.18
		Say Rs. (Lac)								1359832.18
		Add GST @12%								163179.86
		Add Labour Cess @1%								13598.32
		Add Seignrage Fee@10% of basic material rate								56894.72
		Total Cost of work								1593505.08

23/12/2020
E.E.

23/12/2020
E.E.

Technically approved for Amount ₹ 15,93,505-00 (Fifteen
lacs ninety three thousand five hundred five/only.


31.12.20
Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar

Detailed Measurement(BRICKBAT)				
No	L(m)	W(m)	D(m)	Qty(cum)
2	8	$(8+10)/2$	$(2.0+2.5+3.0)/3$	336.000
2	10	$(3.6+2.5)/2$	$(1.0+1.5)/2$	76.250
4	8	$(2.0+3.0)/2$	$(0.6+0.8)/2$	56.000
TOTAL	76			468.25

Detailed Measurement(JHAMA BRICK)				
No	L(m)	W(m)	D(m)	Qty(cum)
1	10	$(8+12)/2$	$(0.2+0.25+0.3)/3$	25.000
2	10	$(3.6+2.5)/2$	$(0.5+1.0)/2$	45.750
2	6	$(1.5+2.0)/2$	$(0.80+1.20)/2$	21.000
TOTAL				91.75

RE DAMAGED(MEASUREMENT)

Detailed Measurement(BRICKBAT)				
No	L(m)	W(m)	D(m)	Qty(cum)
1	8	$(6+8)/2$	$(1.5+2.0+3.0)/3$	121.333
1	10	$(3.6+2.5)/2$	$(1.0+1.2)/2$	67.100
5	8	$(2.0+3.0)/2$	$(0.6+0.9)/2$	28.000
TOTAL				216.43

B. Kumar.
23/12/2020
J.E.

J.B.
23/12/2020
A.R.

R.
23/12/2020
E.E.



R.R.
 23/12/20
 J.R.

R.R.
 23/12/20
 J.R.