

10

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- SIDHKI CHAUK TO LILAH PASWAN TO BHUSLI TOLA

DIVISION:- R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:- R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:- CHHATAPUR

ESTIMATED COST - 2572900.00

प्रतिवेदन

पथ का नाम :-

कार्य का नाम :-

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs 28,84,000/- है।
उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।
प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

24/11/20
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।

24/11/20
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।

24/11/20
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

Inspection Report for Flood Damage Work

Date:.....

1. Name of PIUs:-

ER R.V. Wark Ditt. Tribenpur

2. Name of Block:-

Chhatapur

3. Name of Road:-

Sidki Chaur to Lilahi Panna to
Bhusli Tola

4. For Road

3.2 km

1. Damage Location/Chainage:-

100m

2. Damage Length:-

0.500 km

3. Nature of Damage:-

w/cut of road

4. Details of Restoration Works:-

HP, Brick Bat, Local sand

(i.) Material being used in Restoration Works:-

HP, Brick Bat, Local sand

(ii.) Equipments/Tools being used in Restoration works:-

JCB, Tractor, etc.

(iii.) Procedure taken up in Restoration works:-

completed

(iv.) Restored Length:-

400m

For Bridge

1. Damage Location/Chainage:-

2. Damage Length:-

3. Nature of Damage:-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

Local Sand, Brick Bat
Hume pipe 1000 mm Ø

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length:-

86m

Signature of JE/AE/EE

26/10/20

Signature

(Name of Inspector)

**DETAILS OF ESTIMATE FOR RESTORATION OF
Abstract of Cost**

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Name of Road : **SIDHKI CHAUK TO LILAH PASWAN TO BHUSLI TOLA**

Sub division:-Chhatapur

PANCHAYAT :-

Length of Breach

Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of local sand obtained from river bed Watering & ramming all com.job	260.42	per cum	522.67	136113.72
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I	1092.36	per cum	1751.13	1912864.37
3	laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry 1000MM Dia Pipe	67.50	per cum	3377	227947.50
					2276925.59
					2276925.59

Add 12% GST

Add 1% Labour cess total item

Total

273231.07

22769.26

2572925.91

SAY RS

2572900.00

Junior Engine
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj

25,72,900/-
T.A. for Rs. Twenty five lacs, seventy two thousand
nine hundred) only.

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

DETAILS OF ESTIMATE FOR RESTORATION OF SIDHAI CHAUK TO LILAH PASWAN TO BHUSLI TOLA

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur


Yr. 2020-21

Length of Breach

Sl. No./ item	Item of works	L	B	H	Quantity
1	Filling of local sand obtained from river bed Watering & ramming all com.job	25.0	$(7.5+5)/2$	$(1+2.5+1.5)3$	260.42
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I	16.0 m	$(7.5+3.5)/2$	1.50m	132.0 cum
		86.0m	$(4+8)/2$	$(1+1.5+2.55+3.5+2.55+1.0)/6$	1040.6 cum
					1172.6 cum
	Less quantity for HP $=22/28 \times 1.23 \times 1.23 \times 9 \times 7.5 = 80.24$				80.2 cum
	Net Qty				1092.36
3	Providing and laying reinforced cement concrete pipe NP3 1000mm dia	9	3.00	2.50	67.50

Junior Engin

S D O
Rural Works Sub division
Chhatapur


Executive Engineer
Rural Works division
Triveniganj