


30

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

ESTIMATED COST	Rs	1558233.00
----------------	----	------------

NAME OF ROAD :-	Bhimpur kewla middle school W/N 3, 5 & 7
-----------------	--

DIVISION :-	RWD ,WORKS DIVISION , TRIVENIGANJ
-------------	-----------------------------------

CIRCLE :-	RWD , WORKS CIRCLE MADHEPURA
-----------	------------------------------

Block :-	CHHATAPUR	SUPAUL
----------	-----------	--------

REPORT

An estimate amounting 1558233.00 has been framed to meet the actual cost of expenditure towards motarable work of Bhimpur kewla middle school WN 3, 5 & 7 in between In between 0 Km to 1 ST KM & 2nd km Bhimpur of Chhatapur Block to resume normal traffic facilities for the year 2020-21.

This year's unpredictable rain fall in the Kosi basin broke the rural roads, which increased the problems of the villagers. In this rain, the life of people who were in trouble, were surrounded by water from all sides, it was necessary to resume normal traffic facilities. So that the voters and officials reach their respective booth smoothly As directed by SDO, Triveniganj vide his letter no. 271 dt 14.10. 2020

Measurement of the work had been recorded duly and attached along with the estimate. Local sand, brick bats, hume pipe and bamboos has been used to restore the traffic and accordingly estimate has been framed on basis of up-to-date SOR.

Hence requested for technical approval of the estimate.



Junior Engineer



SDO

Rural Works Sub division
Chhatapur



Executive Engineer

Rural Works division

Triveniganj

Executive Engineer
Rural Works Department
Work Division, Triveniganj

सेवा में

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग कार्य प्रमंडल, त्रिवेणीगंज।

त्रिवेणीगंज, दिनांक- 14.10. 2020

विषय : बिहार विधान सभा आम निर्वाचन 2020 के महेनजर मतदान केन्द्र तक पहुँच पथ के निर्माण के संबंध में।

महाराज,

उपर्युक्त विषयक संदर्भ में कहना है कि बिहार विधान सभा आम निर्वाचन 2020 के महेनजर कुल चार श्रोतों से मतदान केन्द्र तक पहुँच पथ के निर्माण एवं मरम्मति से जुड़े जन शिकायत आवेदन पत्र प्राप्त हुआ है, जिसका विवरण इस प्रकार है -

क्र०	आवेदक का नाम व पता	शिकायत का विषय वस्तु	अभ्युक्ति
1	2	3	4
1	अशीषकान्त झा व 10 अन्य ग्रामीण जनता ग्राम-पंचायत-मधुबनी, प्रखंड- छातापुर	मधुबनी पंचायत अंतर्गत मेहता टीला प्रा० कि० मधुबनी में वार्ड न०-9,11,12 एवं संवि० मधुबनी में वार्ड न०-13 एवं संवि०डोंहरा में वार्ड न०-3,4,5 में मतदाता के आवागमन हेतु कटावप्रस्त सड़क को जोड़ने के संबंध में।	
2	जयकृष्ण साह एवं 06 अन्य ग्राम पंचायत बलुआ प्रखंड-छातापुर	बलुआ पंचायत अंतर्गत मठवि० बलुआ में वार्ड न०-4 एवं 8 को जोड़ने वाली सड़क की मरम्मति के संबंध में।	
3	रजित कुमार सिंह एवं 10 अन्य, प्रा० पंचायत-भीमपुर प्रखंड-छातापुर	उ०मठवि० भीमपुर एवं मठवि० भीमपुर मतदान केन्द्र पर जाने हेतु भीमपुर में वार्ड न०-3,5,9,10,11,12,13 से जुड़े सड़क की मरम्मति के संबंध में।	
4	ललन कुमार मंडल एवं 07 अन्य, ग्राम पंचायत- लक्ष्मीनियों प्रखंड-छातापुर	रघुनंदन मठवि० एवं उर्दू मठवि० लक्ष्मीनियों मतदान केन्द्र पर जाने जाने हेतु वार्ड न०-07, 11, 12 मंडल टीला एवं लक्ष्मीनियों वार्ड न०-01,02 से जुड़े सड़क की मरम्मति एवं निर्माण के संबंध में।	

क्रम सं०- 01 से 04 पर अंकित परिवाद पत्र का विषय-वस्तु मतदान केन्द्रों पर पहुँच पथ एवं आवागमन की असुविधा के दृष्टिगत चुनाव बहिष्कार करने के विरुद्ध वर्णित स्थलों पर मतदाताओं के आवागमन हेतु सड़क निर्माण एवं मरम्मति कार्य कराने व मतदाता को सुविधा मुहैया कराये जाने से संबंधित है। आवेदन पत्र की छायाप्रति संलग्न कर भेजी जा रही है।

अतः अनुरोध है कि वर्णित स्थलों पर आगामी विधान सभा निर्वाचन 2020 के महेनजर मतदाताओं के मतदान केन्द्र तक आवागमन हेतु पहुँच पथ के निर्माण व मरम्मति हेतु आवश्यक कार्रवाई करने का कृप्य करेंगे।

अनुलग्नक : यथावर्णित।

विश्वासभाजन,

निर्वाची पदाधिकारी

-सह-

अनुमंडल पदाधिकारी
त्रिवेणीगंज।

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:-

3.Name of Road:-

A. For Road

1.Damage Location/Chainage :- In 1st and 2nd km

2.Damage Length :- 370 M

3.Nature of Damage :- Road wash out

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- In 1st and 2nd KM

2.Damage Length :- 370 M

3.Nature of Damage :- Road wash out

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

AR
20/10/20

Signature of JE/AE/EE

22/10/20
AR

Signature
27/11/21

(Name of Inspector)

DETAILS OF ESTIMATE FOR REPAIR / MOTARABLE WORK

Abstract of Cost

Division:- RWD triveniganj

Sub division:- Chhatapur

BLOCK :- CHHATAPUR

PANCHAYAT :- Bhimpur

Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per specification & direction of Engineer-in.Charge	672.00cum	Cum	626.89	421270.08
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	446.5 cum	Cum	2145.02	957697.80
					1378967.88

Add 12% GST on item no 4, 5

Add 1% Labour cess total item

Total

1378967.88

165476.15

13789.68

1558233.71

Rs 1558233.00

[Signature]
26/10/21

Junior Engineer
Chhatapur

[Signature]
22/10

S D O
Rural Works Sub division
Chhatapur

[Signature]
26/11/20

Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division Triveniganj

Technically approved for Rs 15,58,233 F
(Fifteen Lac fifty eight thousand two hundred thirty three) only

[Signature]
07/01/21
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

SE

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK

ROAD AT RD.....

Bhimpur kewla middle school WN 3, 5 &7

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur

PANCHAYAT :-


Bhimpur

Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge				672.00cum
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I				446.5 cum


22/10/20
Junior Engineer
Chhatapur


22/10
S D O
Rural Works Sub division
Chhatapur


26/11/20
Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division Triveniganj

MEASUREMENT SHEET

Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge

1

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
	30	6.00	0.30	54.0cum
	15	5.00	0.30	22.5cum
	27	5.00	0.30	40.5cum
	35	5.00	0.30	52.5cum
	40	5.00	0.30	60.0cum
	40	5.00	0.30	60.0cum
	10	4.00	0.30	12.0cum
	10	4.00	0.30	12.0cum
	20	5.00	0.60	60.0cum
	20	5.00	0.60	60.0cum
	27	5.00	0.30	40.5cum
	20	5.00	0.60	60.0cum
	20	5.00	0.60	60.0cum
	25	5.00	0.30	37.5cum
	27	5.00	0.30	40.5cum
				672.0cum

Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I

2

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
	30	5.50	0.30	49.5cum
	15	4.50	0.30	20.3cum
	27	4.50	0.30	36.5cum
	35	4.50	0.15	23.6cum
	40	4.50	0.30	54.0cum
	40	4.50	0.30	54.0cum
	10	3.50	0.30	10.5cum
	10	3.50	0.30	10.5cum
	20	4.50	0.15	13.5cum
	20	4.50	0.15	13.5cum
	27	4.50	0.30	36.5cum
	20	4.50	0.30	27.0cum
	20	4.50	0.30	27.0cum
	25	4.50	0.30	33.8cum
	27	4.50	0.30	36.5cum
				446.5cum

Junior Engineer
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj
EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ