

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

ESTIMATED	COST	Rs	1124528.	00			
NAME OF RO	DAD :-	Lak	shminiya uı	rdu madhyav	vidyal ma	atdan kendra to w r	ıo-2 road
DIVISION	:-	RWD,	WORKS DIVIS	ION , TRIVENI	GANJ		
-							
CIRCLE	:-	RWD,	WORKS CIRC	LE MADHEPU	RA		
£							
Block		CHHA	CADUD	SUPAUL			

REPORT

An estimate amountini 1124528.00 has been framed to meet the actual cost of expenditure towards motarable

work of Lakshminiya urdu madhyavidyal matdan kendra to w no-2 road in between
In between 0.00st Km & 0.500 km
Of Chhatapur Block to resume normal traffic facilities for the year 2020-21.

This year's unpredictable rain fall in the Kosi basin broke the rural roads, which increased the problems of the villagers. In this rain, the life of people who were in trouble, were surrounded by water from all sides, it was necessary to resume normal traffic facilities. So that the voters and officials reach their respective booth smoothly As directed by SDO, Triveniganj vide his letter no. 271 dt 14.10. 2020

Measurement of the work had been recorded duly and attached along with the estimate. Local sand, brick bats, hume pipe and bamboos has been used to restore the traffic and accordingly estimate has been framed on basis of up-to-date SOR.

Hence requested for technical approval of the estimate.

Junior Engineer

s∕D O

Rural Works Sub division Chhatapur Executive Engineer Rural Works division

Rural Works Department

Vork Division, Trivenigani

Inspection Report for El

. B. For Bridge

1. Damage Location/Chainage:- 0.00 TO 0.500km

2.Damage Length

3.Nature of Damage

- 211M - Ruad wash out and side culting

4. Details of Restoration Works:-

(iv.)Restored Length:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length:

Signature of JE/AE/EE

Signature

(Name of Inspector)

Executive Engineer Rural Works Department Mark Division, Trivenigani

Signature (Name of lasperstor)

संशा में

कार्यपालक अभिवता

ग्रामीण कार्य विभाग कार्य प्रमत्तल, जिवेणीगंज।

विवेचीगज, विनात- 14-10- 2020

विषय :

बिहार विधान सभा आम निर्वाचन 2020 के मद्देनजर मतदान केन्द्र तक पहुँच पथ के निर्माण के सबंध में।

महाशय.

उपर्युक्त विषयक संदर्भ में कहना है कि बिहार विधान सभा आम निर्वाचन 2020 के महेनज़र कुल चार श्रीतों से मतदान केन्द्र तक पहुँच पथ के निर्माण एवं भरम्मति से जुढ़े जन शिकायत आवेदन पत्र प्राप्त हुआ है, जिसका विवरण इस प्रकार है —

250	आवेदक का नाम व पता	शिकायत का विषय वस्त्	अभ्यवित
1		The second secon	
	आशीषकाना झा व १० अन्य ग्रामीण जनता ग्राम+पंशायत-म्यूदनी प्रचंड- शतापुर	मपुबनी पंचायत अंतर्गत मेहता टीला प्रक्ष विक मधुबनी में वार्ड न0-91112 एवं साठविक मधुबनी में वार्ड गठ-13 एय सठविक्रडोडरा में वार्ड गठ-3.45 में मतदाता के आवागमन हेतु कटावप्रता सहक का प्रतिहने वो सबंध में।	
2	विधायत बल्ला प्रसाद-भारतपुर विधायत बल्ला प्रसाद-भारतपुर	बलुआ पंचायत अतर्गत मावित बलुआ में वार्ड नाम-४ एवं छ को ओडने वाली सहक की मरम्मति के संबंध में।	
3	पंज्यत-भीमपुर प्रवार-फालपुर	उठमठिक भीमपुर एक मठिक भीमपुर मतदान केन्द्र पर आने हेतु भीमपुर में वार्ड मठ-3,5,9,10,11,12,13 से जुड़े संख्या की गरम्मति के सबध में।	
	ललन कुमार महत्व एवं १७ अन्य, ग्राम प्रवासता संस्मीनियां प्रखंड-छातापुर	रप्नदन मार्गित एवं उर्दू मार्गिक लक्ष्मीनियाँ मतदान केन्द्र पर जाने जाने देतु बार्द सं0-07 11 12 महार टीका एवं लक्ष्मीनियाँ वार्ट न0-0502 से जुड़े सहक की मरम्मति एवं निर्माण के संबंध में।	

क्रम स0- 01 से 04 पर अंकित परिवाद पत्र का विषय-वस्तु मतवान केन्द्रों पर पहुँच पद्य एवं आवागमन की असुविधा के दृष्टिगत चुनाव बहिष्कार करने के विरुद्ध वर्णित रखलों पर मतदाताओं के आवागमन हेतु सडक निर्माण एवं मरम्मति कार्य कराने व मतदाता को सुविधा मुहैया कराये जाने से संबंधित है। आवेदन पत्र की छायाप्रति संलग्न कर भेजी जा रही है।

अतः अनुरोध है कि वर्णित स्थलों पर आगामी विद्यान समा निर्वाचन 2020 के महेनजर मतदाताओं के मतदान केन्द्र तक आवागमन हेतु पहुँच पथ के निर्माण व मरम्मति हेतु आवश्यक कार्रवाई करने का कर करेंगे।

अनुलग्नकः यथावर्गितः

विष्वासमाजनः
निर्वाधी पेदांधिकः
-सहअनुमंडल पदाधिक
जिवेणीगंज।

DETAILE OF ESTIMATE FOR REPIR / MOTARABLE WORK

Abstract of Cost

Division:- RWD trivenigani Sub division:-Chhatapur

BLOCK :- CHHATAPUR

PANCHAYAT :- Lakshminiya

Yr. 2020-21

\$I. No./	Item of works	Quantity	Unit	Rate	Amount
item no.					
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge	460.35cum	Cum	626.89	288588.81
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	329.4 cum	Cum	2145.02	706569.59
					995158.40

995158.40

119419.01

9951.58

1124528.99 1124528.00

Rs

Add 12% GST on item no 4, 5 Add 1% Labour cess total item

Total

Chhatapur

Rural Works Sub division Chhatapur

Executive Engineer Rural Works division

Exerciseniganiqueer Rural Works Department Work Division, Trivenigani

Techenically approved for Re 11,24,528200 (Rupees Eleven Lae twenty four thousand five hundred werns) Estarts

अधीक्षण अभिवंता ग्रामीण कार्य विभाग कार्य अंचल, मधेपुरा

SE

DETAILE OF ESTIMATE FOR REPIR / MOTARABLE WORK

ROAD AT RD......

Lakshminiya urdu madhyavidyal matdan kendra to w no-2 road

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj Sub division:-Chhatapur

BLOCK :- CHHATAPUR

PANCHAYAT :-

Lakshminiya

Yr. 2020-21

Sl. No./					
item no.	Item of works	L	В	Н	Quantity
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge				460.35cum
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I				329.4 cum

Junior Enginee Chhatapur

S D O Rural Works Sub division Chhatapur Executive Engineer Rural Works division Triveniganj

Executive Engineer Rural Works Department Work Division, Trivenigani

MEASUREMENT SHEET

Filling of Local Sand Obtain from River Bed , Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge

	Length	width	depth	Quantity
	in M	in M	in (Av.) M	cum
Ch				
	16	4.50	0.30	21.6cum
	45	4.50	0.60	121.5cum
	35	4.50	0.30	47.3cum
	30	4.50	0.60	81.0cum
	45	4.50	0.40	81.0cum
	40	4.50	0.60	108.0cum
				460.4cum

Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of 2 E/I

	Length	width	depth	Quantity	
Ch	in M	in M	in (Av.) M	cum	
2	16	4.00	0.60	38.4cum	
	45	4.00	0.30	54.0cum	
11	35	4.00	0.45	63.0cum	
	30	4.00	0.60	72.0cum	
	45	4.00	0.30	54.0cum	
	40	4.00	0.30	48.0cum	
				329.4cum	

Junior Engineer Chhatapur

Rural Works Sub division Chhatapur

Executive Engineer Rural Works division

Triveniganj nes Rural Works Department

Mork Division, Frivenigani