

(47)

31

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

ESTIMATED COST Rs 798784.00

NAME OF ROAD :-

Balua panchayat untargt middle
school, Balua me W NO-4 to W NO-6 road

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

REPORT


An estimate amounting 798784.00 has been framed to meet the actual cost of expenditure towards motarable work of Balua panchayat untargt middle school, Balua me W NO-4 to W NO-6 road in between In between 0 Km & 2 km Balua of Chhatapur Block to resume normal traffic facilities for the year 2020-21.


This year's unpredictable rain fall in the Kosi basin broke the rural roads, which increased the problems of the villagers. In this rain, the life of people who were in trouble, were surrounded by water from all sides, it was necessary to resume normal traffic facilities. So that the voters and officials reach their respective booth smoothly As directed by SDO, Triveniganj vide his letter no. 271 dt 14.10. 2020

Measurement of the work had been recorded duly and attached along with the estimate. Local sand, brick bats, hume pipe and bamboos has been used to restore the traffic and accordingly estimate has been framed on basis of up-to-date SOR.

Hence requested for technical approval of the estimate.


20/10/20
Junior Engineer


29/10
S D O
Rural Works Sub division
Chhatapur


26/11/20
Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Triveniganj

Inspection Report for Flood Damage Work

Date:-.....

1. Name of PIUs:-

2. Name of Block:- CHHATAPUR

3. Name of Road:- Balua Panchayat Urterogt middle school, Balua me

A. For Road W. No - 4 and 6 Road. Under work. Motorable

1. Damage Location/Chainage :- In. 0.00 to 2 Km

2. Damage Length :- 271m

3. Nature of Damage :- Road wash out and side cutting

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- In 0.0 Km to 2 Km

2. Damage Length :- 271m

3. Nature of Damage :- Road wash out and side cutting

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :


20/10/20

Signature of JE/AE/EE


27/11/21

Signature

(Name of Inspector)

सेवा में

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग कार्य प्रमंडल, त्रिवेणीगंज।

त्रिवेणीगंज, दिनांक- 14.10.2020

विषय : बिहार विधान सभा आम निर्वाचन 2020 के महेनजर मतदान केंद्र तक पहुँच पथ के निर्माण के संबंध में।

महाराज,

उपर्युक्त विषयक संदर्भ में कहना है कि बिहार विधान सभा आम निर्वाचन 2020 के महेनजर कुल चार श्रोतों से मतदान केंद्र तक पहुँच पथ के निर्माण एवं मरम्मति से जुड़े जन शिकायत आवेदन पत्र प्राप्त हुआ है, जिसका विवरण इस प्रकार है :-

क्र०	आवेदक का नाम व पता	शिकायत का विषय वस्तु	अभ्युक्ति
1	2	3	4
1	आशीषकान्त झा व 10 अन्य ग्रामीण जनता, ग्राम-पंचायत-मधुबनी, प्रखंड- छातापुर	मधुबनी पंचायत अंतर्गत मेहता टोला ग्राम वि० मधुबनी में वार्ड नं०-9,11,12 एवं संचिठि मधुबनी में वार्ड नं०-13 एवं संचिठिबोहरा में वार्ड नं०-3,4,5 में मतदाता के आवागमन हेतु कटावधरात सड़क को जोड़ने के संबंध में।	
2	जयद्वेष साह एवं 06 अन्य ग्राम पंचायत मलुआ प्रखंड-छातापुर	बलुआ पंचायत अंतर्गत मांवि० बलुआ में वार्ड नं०-4 एवं 6 को जोड़ने वाली सड़क की मरम्मति के संबंध में।	
3	रजनीत कुमार सिंह एवं 10 अन्य, ग्राम पंचायत-भीमपुर प्रखंड-छातापुर	उममोवि० भीमपुर एवं मांवि० भीमपुर मतदान केंद्र पर जाने हेतु भीमपुर में वार्ड नं०-3,5,9,10,11,12,13 से जुड़े सड़क की मरम्मति के संबंध में।	
4	लालन कुमार मंडल एवं 07 अन्य, ग्राम पंचायत- लक्ष्मीनिर्वा प्रखंड-छातापुर	रघुनंदन मांवि० एवं उर्दू मांवि० लक्ष्मीनिर्वा मतदान केंद्र पर जाने जाने हेतु वार्ड नं०-07, 11, 12 मंडल टोला एवं लक्ष्मीनिर्वा वार्ड नं०-01,02 से जुड़े सड़क की मरम्मति एवं निर्माण के संबंध में।	

क्रम सं०- 01 से 04 पर अंकित परिवाद पत्र का विषय-वस्तु मतदान केंद्रों पर पहुँच पथ एवं आवागमन की असुविधा के दृष्टिगत चुनाव बहिष्कार करने के विरुद्ध वर्णित स्थलों पर मतदाताओं के आवागमन हेतु सड़क निर्माण एवं मरम्मति कार्य कराने व मतदाता को सुविधा मुहैया कराये जाने से संबंधित है। आवेदन पत्र की छायाप्रति संलग्न कर भेजी जा रही है।

अतः अनुरोध है कि वर्णित स्थलों पर आगामी विधान सभा निर्वाचन 2020 के महेनजर मतदाताओं के मतदान केंद्र तक आवागमन हेतु पहुँच पथ के निर्माण व मरम्मति हेतु आवश्यक कार्रवाई करने का कृपया करेंगे।

अनुलग्नक : द्वावर्णित।

विश्वासभाजन,

निर्वाची पदाधिकारी

-सह-

अनुमंडल पदाधिकारी

त्रिवेणीगंज।

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK

Abstract of Cost

Division:- RWD triveniganj
Sub division:-Chhatapur

BLOCK :- CHHATAPUR
PANCHAYAT :- Balua

Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge	530.70cum	Cum	626.89	332690.52
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	174.5 cum	Cum	2145.02	374198.74
					706889.26

Add 12% GST on item no 4, 5
Add 1% Labour cess total item
Total

706889.26

84826.71

7068.89

798784.87

Rs 798784.00

Junior Engineer
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj
Rural Works Department
Work Division, Triveniganj

Technically approved for Rs 7,98,784.00
(Rupees Seven Lac Ninety eight Thousand Seven hundred
Eighty four only)

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

SE

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK

ROAD AT RD.....

Balua panchayat untargt middle
school,Balua me W NO-4 to W NO-6 road

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj
Sub division:-ChhatapurBLOCK :- CHHATAPUR
PANCHAYAT :- Balua
Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge				530.70cum
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I				174.5 cum


20/11/20
Junior Engineer
Chhatapur
22/11/20
S D O
Rural Works Sub division
Chhatapur
26/11/20
Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works division
Triveniganj

MEASUREMENT SHEET

1

Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
1St km	7	4.00	0.30	8.4cum
	32	5.00	0.30	48.0cum
	15	5.00	0.30	22.5cum
	15	6.00	0.60	54.0cum
	10	5.00	0.60	30.0cum
	5	4.00	0.60	12.0cum
	5	4.00	0.60	12.0cum
	25	5.00	0.30	37.5cum
	30	4.50	0.30	40.5cum
2nd Km	30	6.00	0.30	54.0cum
	30	5.00	0.30	45.0cum
	30	4.00	0.60	72.0cum
	27	4.00	0.60	64.8cum
	10	5.00	0.60	30.0cum
				530.7cum

2

Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
1St km	7	3.50	0.30	7.4cum
	32	4.50	0.15	21.6cum
	15	4.50	0.15	10.1cum
	15	5.50	0.15	12.4cum
	10	4.50	0.30	13.5cum
	5	3.50	0.15	2.6cum
	5	3.50	0.30	5.3cum
	25	4.50	0.15	16.9cum
2nd Km	30	5.50	0.20	33.0cum
	30	4.50	0.15	20.3cum
	30	3.50	0.30	31.5cum
				174.5cum

Junior Engineer
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj
EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ