

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

ESTIMATED COST Rs ~~15,10,24,324~~ 16,12,100/-

NAME OF ROAD :- JADIA CHARNE ROAD (Near Bridge)

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

प्रतिवेदन

पथ का नाम :-

कार्य का नाम :-

जालिम से चरने पथ /
जालिम से चरने पथ के 9.1 फुल के पास, पहुँच पथ 37
में बाड़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाड़ से क्षतिग्रस्त 9.1 फुल

में बाड़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है

जिसकी प्राक्कलित लागत 2649,200/- 16.12.100 है।

उक्त पथ का निर्माण योनांतगत हुआ है एवं योजना अनुरक्षण

अवधि में पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार लोकल बालू एवं देने के बाद

यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट

रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, 01.....।

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

DETAILE OF ESTIMATE FOR RESTORATION OF JADIA CHARNE ROAD (Near Bridge)

Abstract of Cost

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:- Chhatapur

JADIA CHARNE ROAD (Near Bridge)

Length of Breach 263.00M *1/10 road - 11.4 km* Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1/15.5 (WRD) morth 2504	Providing and laying pitching on slope laid over prepared filter media including boulder apron laid dry in front of toe of embankment as per drawing and technical Specification	89.94cum	per Cum	<i>3391.40</i> 679.00	<i>305023</i> 61067.86
2	Supply of Local Sand obtained from river bed watering and ramming, all comp. job as perspe. & dirc. of E/I	139.39cum	Per cum	522.67	<i>72855</i> 72857.06
3	Construction of granular sub base by providing well graded material spreading in uniform layer with motor grader on prepared surface, mixing mix in place method with rotavator at OMC, and compacting with three wheel 80-100KN static roller.... As per technical spe. & dir. of E/I	428.25cum	Per cum	2400.00	1027800.00
					<i>1161724.92</i>

Add 12% GST on item no 5,6&7

Add 1% Labour cess total item

S. Fee $(355.68 \times 89.94 + 141.85 \times 139.39 + (428.3 \times .6 \times 604.91 + 428.23 \times .4 \times 175.8) \times .1$

Total

139406.99

11617.25

23732.52

Rs 151024.24

Say Rs 151024

1405678

168681

14057

23733

1612149

Junior E
Chhataj

SDO
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj

T.A. for Rs 1612100 *(Rs. sixteen lakh twelve thousand, one hundred only)*
07/04/21
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

DETAILE OF ESTIMATE FOR RESTORATION OF JADIA CHARNE ROAD (Near Bridge)

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur

Ohm Prakash house to Shah tola

Length of Breach 263.00M

Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Providing and laying pitching on slope laid over prepared filter media including boulder apron laid dry in front of toe of embankment as per drawing and technical Specification U/S	(20.2+11)	4.85	.16+.18+.28+.29+.25+.22+.30+.19/8 .18+.18+.27+.22+29+.26+.2	35.4 cum
	D/S	(20+11)	4.60		36.0 cum
	Apron	62.00	1.00	0.30	18.6 cum
					89.94 cum
2	Supply of Local sand below boulder	31.2	4.85	0.45	68.1 cum
		31	4.6	0.5	71.3 cum
					139.4 cum
3	Supply and laying of GSB grade II	60.0m	3.75+5.1+19.7/3	0.75	428.3cum

J.E

S D O

Rural Works Sub division
Chhatapur

Executive Engineer

Rural Works division
Triveniganj

Inspection Report for Flood Damage Work

Date:.....

1.Name of PIUs:-

2.Name of Block:- *Chhatapur*

3.Name of Road:- *Jadiya chornei Road.*

A. For Road

1.Damage Location/Chainage :-

2.Damage Length :- *102 m.*

3.Nature of Damage

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

completed

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :- *partially damage*

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

local sand, stone, boulders.

(ii.)Equipments/Tools being used in Restoration works:-

Tractor, trolley, etc.

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

Sul 20/10
Signature of JE/AE/EE

25/1/21
Signature

(Name of Inspector)