

41

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:- CONSTRUCTION OF ROAD LALIT GRAM  
CHAPIN TO TULSI PATTI ROAD

DIVISION:- R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:- R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:- CHHATAPUR

### ESTIMATED COST

~~3406307.00~~

Rs 34,06,307/-

प्रतिवेदन

पथ का नाम :- Construction of Road Lalit Groom Chapin to Teesipati Road

कार्य का नाम :- 1 पथ की मरम्मत = 4 Km

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त पथ 250m

में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत 438/982-00 है।


उक्त पथ का निर्माण M.M.S.T. योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में .....।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।


प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

  
11-10-20

कनीय अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रशाखा, .....।

  
26/10/20

सहायक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अवर प्रमण्डल, .....।

  
26/10/20

कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, .....  
Executive Engineer  
Rural Works Department  
Work Division, Trivenigani

## Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- CHHATAPUR

3.Name of Road:- CONSTRUCTION OF ROAD LALITGRAM CHHAPIN TO TULSI PATI ROAD.

### A. For Road

1.Damage Location/Chainage :- 3rd KM, Road Length = 6 KM

2.Damage Length :- 250m wash out

3.Nature of Damage :- Road w/ In maintenance

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-, L/sand, Brick bats, H.P. 100mm

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

### B. For Bridge

1. Damage Location/Chainage:- 3rd KM

2.Damage Length :- 250m washout

3.Nature of Damage :- Road w/ In maintenance

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

Signature of JE/AE/EE

*[Signature]*  
20/11/20

Signature

*[Signature]*  
29/01/21

(Name of Inspector)

*[Signature]*  
11-10-20

# Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads Damaged during flood in 2020 in SUPAUL District

**Name of Road:**

**CONSTRUCTION OF ROAD LALIT GRAM CHAPIN TO TULSI PATTI ROAD**

**Block:** CHHATAPUR

**District:** SUPAUL

**Divison :** RWD, Works Division, TRIVENIGANJ

**Circle:** RWD, Work Circle, Madhepura

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	2389.33	522.67	1248832.85
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	855.00	1751.13	1497216.15
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	45.00	3377.00	151965.00
	<b>TOTAL AMOUNT =</b>				<b>2898014.00</b>
	<b>ADD 12.00 %GST=</b>				<b>347761.68</b>
	<b>ADD 1% L.CESS=</b>				<b>28980.14</b>
	<b>SEIGNIORAGE FEE=</b>				<b>131551.00</b>
	<b>SAY TOTAL AMOUNT =</b>				<b>3406306.82</b>

**3406307.00**

*RR*  
11/10/20  
JE

RWD SUB DIVISION-CHHATAPUR

*RR*  
11/10  
AE

RWD SUB DIV.  
CHHATAPUR

*RR*  
11/10  
EE

EXECUTIVE ENGINEER  
RWD WORKS DIV. TRIVENIGANJ  
TRIVENIGANJ

*Technically Approved for Rs 34,06,307/-  
(Thirty four Lac six thousand three hundred seven only)*

*11/10/21*

अधीक्षक अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंचल, मधेपुरा

SE  
MADHEPURA



## Detailed Estimate


**Name of Road:**

### CONSTRUCTION OF ROAD LALIT GRAM CHAPIN TO TULSI PATTI ROAD

Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
		1	200.00	(5+5.5+5+6)/4	(2+3.5+1.5)/3	2389.33
					TOTAL=	2389.33
					Total Qty. =	2389.33
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	BELOW WATER LEVEL	1	50.00	(8.00+9.00)/2	0.90	382.50
	TOP LEVEL	1	150.00	(5.00+5.50)/2	0.60	472.50
					Total Qty. =	855.00
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
	1ST CUTTING	6	3.00	2.50		45.00
					Total Qty. =	45.00

  
JE 11/10/20

RWD SUB DIV- CHHATAPUR

  
AE 11/10

RWD SUB DIV. CHHATAPUR

  
EE 26/10/20

EXECUTIVE ENGINEER  
RWD WORKS DIV. TRIVENIGANJ  
TRIVENIGANJ