

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

ESTIMATED COST Rs 1766100.00

NAME OF ROAD :-

31 NO. ROAD TO DARHARIYA SIMA PMGSY VIA PARIYADHAR

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

प्रतिवेदन
 पथ का नाम :- 3/140 पथ से इटेरील सीमा का परिवर्तन
 कार्य का नाम :- पथ का चौड़ाई - 3.856 km
 में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 0.50 km.
 बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है
 जिसकी प्राक्कलित लागत 2,14,400 1/1/166 pot
 उक्त पथ का निर्माण योजनागत हुआ है एवं योजना अनुरक्षण
 अवधि में पथ के कटे (क्षतिग्रस्त)
 भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
 यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
 रूप से प्राक्कलन में दर्शाया गया है।
 प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

<i>[Signature]</i> कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य प्रशाखा,।	<i>[Signature]</i> सहायक अभियंता, ग्रामीण कार्य विभाग, कार्य अवर प्रमण्डल,।	<i>[Signature]</i> कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमण्डल,।
---	---	---

Inspection Report for Flood Damage Work

Date:-

1. Name of PIUs:-

EE RWD Works Div. T. B. Gangajay

2. Name of Block:-

Chhatapuri.

3. Name of Road:-

31 No road to Dhararia sima 2m654.
via Pariyadhar.

A. For Road

Length - 3.54km

1. Damage Location/Chainage :-

2. Damage Length :-

0.05050km

3. Nature of Damage :-

w/ontd road

4. Details of Restoration Works:-

ec bag, 4/5000 1/2000, 1/2000.

(i.) Material being used in Restoration Works:-

ec bag, 4/5000 1/2000.

(ii.) Equipments/Tools being used in Restoration works:-

Tractor - Tolly, SCB.

(iii.) Procedure taken up in Restoration works:-

completed.

(iv.) Restored Length :-

0.05050km

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads Damaged during flood in 2020 in SUPAUL District

Name of Road:

31 NO. ROAD TO DARHARIYA SIMA PMGSY VIA PARIYADHAR

Block: CHHATAPUR

District: SUPAUL

Division : RWD, Works Division, TRIVENIGANJ

Length - 3.5 km

Circle: RWD, Work Circle, Madhepura

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	722.77	522.67	377770.00
2	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Per 100 Bags	212.55	3113.40	661753.00
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	247.97	1751.13	434225.52
4	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	15.00	3280.50	49207.50
	TOTAL AMOUNT =				1522956.00
	ADD 1.00 %LABOUR CESS=				15230.00
	ADD 12.00 %GST=				182755.00
	TOTAL AMOUNT =				1720941.00

S Fee

45189.00

Total Amount =

1766130.00

Say Rs =

1766100.00

JE 20/10/20

AE 20/10/20

EE 26/11/20

RWD SUB DIVISION-CHHATAPUR

RWD SUB DIV.
CHHATAPUR

RWD WORKS DIV. TRIVENIGANJ

TA for Rs 17,66,100/- (Rs. seventeen lac sixty six thousand and hundred) only.

11/12/20
अधीक्षणे अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

SE
MADHEPURA

ame of Road:

31 NO. ROAD TO DARHARIYA SIMA PMGSY VIA PARIYADHAR

	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	1ST LAYER	1	50.50	(7.60+8.50+6+4.5)/4	(1.6+2.6+3.5+3.7+4.5+3.45+2.5+1.7)/8	988.58
	Less- HP- / Brick bat Qty	2	3	2.5	1.189 = 17.84 + 247.97 = 265.81	
					NET Total Qty =	722.77
2	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.					
	L/S	1	30.00	(3.5+3.40+2.55)/3	3.50	330.75
	R/S	1	26.00	(3.25+3.90+3.75)/3	2.90	273.95
					TOTAL=	604.70
					Total No. of EC Bags =(676.25X35.315)	21255.21
					SAY NO OF BAGE=	21255
					NO OF BAGS/100=	212.55
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
		1	6.25	(8.5+6)/2	1.50	67.97
		1	45.00	.00	1.00	180.00
					Total Qty. =	247.97
4	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
		2	3.00	2.50		15.00
					Total Qty. =	15.00

[Signature]
JE

[Signature]
AE

[Signature]
EE

RWD SUB DIV- CHHATAPUR

RWD SUB DIV. CHHATAPUR

RWD WORKS DIV. TRIVENIGANJ