

18 48

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- HOUSE OF ENDAL ROY TO RAM TOLA

DIVISION:- R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:- R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:- CHHATAPUR

ESTIMATED COST

2688224.00

प्रतिवेदन

पथ का नाम :- House of Indal Rai to Ram tols

कार्य का नाम :-

पथ की लम्बाई - 1.5 Km

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त पथ 160m 240m

में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है

जिसकी प्राक्कलित लागत 36620.72 = ००

उक्त पथ का निर्माण G.T.S. (Pipe) योनान्तर्गत हुआ है एवं योजना अनुश्रवण

अवधि में।

पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद

यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट

रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

APR
10-11-20
Sd/-
10/11/20
APR

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।

APR
10/11/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।

APR
10/11/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,
Rural Works Department
Work Division Trivenigani

Inspection Report for Flood Damage Work

Date:-.....

1. Name of PIUs:-

2. Name of Block:- CHHATAPUR

3. Name of Road:- HOUSE OF INDAL RAY TO RAM TOLA

A. For Road

1. Damage Location/Chainage :- In 1st km (400m), Length of Road 1.5km

2. Damage Length :- 160m + 60 240m

3. Nature of Damage :- Road w/ Const (Departmental work)
Wash out

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- 400m

2. Damage Length :- 240m

3. Nature of Damage :- Road work (Departmental) GTS 147

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

AR
10-11-20
JE/ehz

Sul
05/11/20

28/11/21

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in 2020 in SUPAUL District

Name of Road:

HOUSE OF ENDAL ROY TO RAM TOLA

Block: CHHATAPUR

District: SUPAUL

Division : RWD, Works Division, TRIVENIGANJ

Circle: RWD, Work Circle, Madhepura

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	2412.00	522.67	1260680.04
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	504.00	1751.13	882569.52
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	45.00	3377.00	151965.00
	TOTAL AMOUNT =				2295214.56
	ADD 12.00 %GST=				275425.75
	ADD 1% L.CESS=				22952.15
	S. FEE				94632.00
	SAY TOTAL AMOUNT =				2688224.45

2688224.00

[Signature]
JE 10/11/20

RWD SUB DIVISION-CHHATAPUR

[Signature]
AE

AS

[Signature]
EE

EXECUTIVE ENGINEER
RWD WORKS DIV. TRIVENIGANJ
TRIVENIGANJ

SE
MADHEPURA

Technically approved for Rs 26,88,224/-
[Twenty six Lac Eighty Eight Thousand and two
hundred twenty four] Only

[Signature]
07/04/21
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

Detailed Estimate

Name of Road:

HOUSE OF ENDAL ROY TO RAM TOLA

Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
		1	200.00	$(8+6)/2$	1.50	2100.00
		1	40.00	$(7+9)/2$	1.20	312.00
					TOTAL=	2412.00
					Total Qty =	2412.00
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
		1	12.00	6.00	0.90	64.80
		1	180.00	5.50	0.30	297.00
		1	8.00	6.00	0.90	43.20
		1	60.00	5.50	0.30	99.00
					Total Qty. =	504.00
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
		6	3.00	2.50		45.00
					Total Qty. =	45.00


JE


AE


EE

RWD SUB DIV- CHHATAPUR

AS

RWD WORKS DIV. TRIVENIGANJ

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ