

GOVT. OF BIHAR



Year 2020-21

NAME OF ROAD :- Pariyahi NaharPul 49RD to Nawnirmit dhara par kr
Jadia Balua path via Chauhan Tola ,Mandal,Nonia tola

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

ESTIMATED COST Rs ~~16339.00~~ 1,70,675/-

प्रतिवेदन

पथ का नाम :-

कार्य का नाम :-

परीगाँव/नहा (88) 49 RD से रोजीवापेट चालू पथ का निर्माण - 8.3.2020
वागा - चौहान रोड, मंडल रोड, नोमिया रोड
में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त 0.065 km
में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है
जिसकी प्राक्कलित लागत 170,675/- है।
उक्त पथ का निर्माण योनांतगत हुआ है एवं योजना अनुरक्षण
अवधि में पथ के कटे (क्षतिग्रस्त)
भाग में आवश्यकता अनुसार Hume Pipe Bamboo, लोकल बालू एवं Brick-Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।
प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

26/11/20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,

Sul
26/11/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,

26/11/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:- EE RW & work Riv. Tribemgarh

2.Name of Block:- Chhotapuri

3.Name of Road:- P.N. Se. No. C.T. No. TOLA TAL

A. For Road

Length - 3.125 km

1.Damage Location/Chainage:- 1.86 km

2.Damage Length :- 0.0065 km in both side.

3.Nature of Damage :- partially cutting of road

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- Local sand

(ii.)Equipments/Tools being used in Restoration works:- Engr 10, 500.

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :- 0.0065 km.

B. For Bridge

1. Damage Location/Chainage:-

2.Damage Length :-

3.Nature of Damage :-

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

Local Sand

Signature of JE/AE/EE

[Signature]
20/10/20

Signature

[Signature]
25/11/21

(Name of Inspector)

DETAILE OF ESTIMATE FOR

Pariyahi NaharPul 49RD to Nawnirmit dhara par kr Jadia Balua
path via Chauhan Tola ,Mandal,Nonia tola

Division:- RWD triveniganj
Sub division:-Chhatapur
Length of Breach

Abstract of Cost

BLOCK :- CHHATAPUR
PANCHAYAT :-

Sl. No	Item of works	Quantity	Unit	Rate	Amount
1	Filling of local sand obtainedfro river bed watering & ramming all compt.job as spe.& direction of E/I	282.2m	per m	522.67	147498.13
					147498.13

Add 12% GST on item no 5,6&7

17699.78

Add 1% Labour cess total item

1474.98

Total

166672.88

Add 1% contingenc

1666.73

Rs 168339.00

④ 4003 = 170,675.00

22/11/20

Juni
Chh

S D O

Rural Works Sub division
Chhatapur

22/11

Executive Engineer
Rural Works division
Triveniganj

T.A. for Rs. 170,675/- (Rs. One lac, seven thousand six hundred seventy five only)

22/10/21

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

DETAIL OF ESTIMATE FOR RESTORATION OF
Pariyahi NaharPul 49RD to Nawnirmit dhara par kr Jadia Balua path via Chauhan Tola
,Mandal,Nonia tola

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur

Length of Breach

Yr. 2020-21

Sl. No	Item of works	No	L	B	H	Quantity
1	Filling of local sand obtainedfro river bed watering & ramming all compt.job as spe.& direction of E/I	2	15.00	(1.50+2)/2	(1+1.5)/2	65.63cum
		2	12.00	(1.20+2)/2	(1+1.8)/2	53.76cum
		2	10.50	(1.75+2)/2	(1+2.1)/2	61.03cum
		2	13.50	(1.10+1.75)/2	(1.2+1.5)/2	51.94cum
		2	14.50	(1.00+1.5)/2	(1+1.75)/2	49.84cum
						282.20cum

df 20/10/20
Juni

S D O 20/10
S D O
Rural Works Sub division
Chhatapur

Dr 20/10
Executive Engineer
Rural Works division
Triveniganj