

GOVT. OF BIHAR



Year 2020-21

NAME OF ROAD :- Gwalpara Bocha Chauk MMGSY Sadak To Charne Jane wali PMGSY Sadak Tak

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

ESTIMATED COST Rs ~~291478.00~~ 2,98,400/-

प्रतिवेदन

पथ का नाम :-

कार्य का नाम :-

Goolpara Bocha choul massy sadak to charmejanewali massy
Sadak tak.

जें बाड़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त
0.216km में बाड़ क्षतिग्रस्त मरम्माति मद से यातायात चालू करने हेतु तैयार किया गया है
जिसकी प्राक्कलित लागत 2,98,400/- है।
उक्त पथ का निर्माण योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में 25/1/20 पथ के कटे (क्षतिग्रस्त)
भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।
प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

1/26/11/20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, 1/.....।

26/11/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,।

26/11/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,।

DETAILE OF ESTIMATE FOR

Gwalpara Bocha Chauk MMGSY Sadak To Charne Jane
wali PMGSY Sadak Tak

Division:- RWD triveniganj
Sub division:- Chhatapur
Length of Breach

Abstract of Cost

BLOCK :- CHHATAPUR
PANCHAYAT :-

No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of local sand obtainedfro river bed watering & ramming all compt.job as spe.& direction of E/I	488.6m	per m	522.67	255391.59
					255391.59

Add 12% GST on item no 5,6&7

30646.99

Add 1% Labour cess total item

2553.92

Total

288592.50

Add 1% contingenc

2885.92

Rs 291478.00

Junior
Chhat:

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj

75. for Rs. 2,98,000/- (Two lac Ninety Eight
thousand) only.

11/07/04/21
अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

**DETAIL OF ESTIMATE FOR RESTORATION OF
Gwalpara Bocha Chauk MMGSY Sadak To Charne Jane
wali PMGSY Sadak Tak**

Division:- RWD triveniganj
Sub division:- Chhatapur
Length of Breach

BLOCK :- CHHATAPUR

Sl. No./ item	Item of works	Yr. 2020-21				Quantity
		No	L	B	H	
1	Filling of local sand obtainedfro river bed watering & ramming all compt.job as spe.& direction of E/I					
		2	22.50	(1.50+2.1)/2	(1+1.1)/2	85.05cum
		2	20.00	(1.20+2)/2	(1+1.8)/2	89.60cum
		2	18.50	(1.75+2.2)/2	(1+2.1)/2	113.27cum
		2	15.00	(1.10+1.75)/2	(1.2+1.5)/2	57.71cum
		2	12.00	(1.00+1.5)/2	(1+1.75)/2	41.25cum
		2	20	(1.60+2.1)/2	(1+1.75)/2	101.75cum
						488.63CUM

22/10/20
Junior

[Signature]
S D O
Rural Works Sub division
Chhatapur

[Signature]
Executive Engineer
Rural Works division
Triveniganj

Inspection Report for Flood Damage Work

Date:-.....

1. Name of PIUs:-

EE RWD. W. Div. Tirumangal

2. Name of Block:-

CHHATHUR

3. Name of Road:-

G.B.C.M.S TO

CHARNEJANE BALI PM. SARAK TAK.

A. For Road

1. Damage Location/Chainage

Length of road - 2.216 km

2. Damage Length

0.216 km.

3. Nature of Damage

Partially cutting of road.

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

Local sand.

(ii.) Equipments/Tools being used in Restoration works:-

JCB, Tractor-Trailers.

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :-

0.216 km

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length

3. Nature of Damage

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

Signature of JE/AE/EE
20/10/20
AR

Signature
20/10/20

Signature

(Name of Inspector)

20/10/20
DE