

(28) 42

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- (L056)T01 CHAINPUR TO TANGARI PART-B A And B

DIVISION:- R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:- R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:- CHHATAPUR

ESTIMATED COST

1471861.00

3184671.00

प्रतिवेदन

पथ का नाम :- (LO-56) TO CHAHPUR TO TANHARI PART A

कार्य का नाम :-

पथ की लम्बाई में 3.6 km बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त पथ 200m

में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. 2906608 है।

उक्त पथ का निर्माण P.M.S.Y. योनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में ।

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


20-11-20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, Etahpur


20/11/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, Etahpur


20/11/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- GHHATAPUR

3.Name of Road:- (LOS6) -TO1 CHAINPUR TO TANGARI PART- A

A. For Road Road Length = 3.6 Km

1.Damage Location/Chainage :- 2nd Km , two cutting =

2.Damage Length :- 100m + 100 = 200m

3.Nature of Damage :- wash out

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:- 4 sand, Back bats 1000 gram HP,

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- 2nd Km

2.Damage Length :- 100m + 100 = 200m (two cutting)

3.Nature of Damage :- wash out

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

ABSTRACT OF COST

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK

ROAD AT ROAD-

(LO56) TO1 CHAINPUR TO TANGARI

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj


BLOCK :- CHHATAPUR

Sub division:-Chhatapur

Yr. 2020-21

Sl. No./ item no.	Item of works		
1	PART -A		2906608.00 1662820.00
	PART-B		3226847.00 1521851.00
2			
	TOTAL=		6133455.00 3184671.00


20/10/20
Junior Engineer
Chhatapur


SDO 20/10/20
Rural Works Sub division
Chhatapur


Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Technically approved for Rs 31,84,671/-
(Rupees thirtyone Lac Eighty four Thousand six hundred
Seventy one only)

SE ! 07/04/21
MADHEPURA

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in 2020 in SUPAUL District

Name of Road:

(L056)T01 CHAINPUR TO TANGARI PART-A

Block: CHHATAPUR

District: SUPAUL

Divison : RWD, Works Division, TRIVENIGANJ

Circle: RWD, Work Circle, Madhepura

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1530.00	522.67	799685.10
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	241.80	1751.13	423423.23
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	60.00	3377.00	202620.00
	TOTAL AMOUNT =				1425728.33
	ADD 12.00 %GST=				171087.40
	ADD 1% L.CESS=				14257.28
	SEIGNIORAGE FEE				51747.00
	SAY TOTAL AMOUNT =				1662820.02


1662820.00


JE

RWD SUB DIVISION-CHHATAPUR


AE

RWD SUB DIV.
CHHATAPUR


EE

RWD WORKS DIV. TRIVENIGANJ

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

SE
MADHEPURA

Detailed Estimate

Name of Road:

(L056)T01 CHAINPUR TO TANGARI PART-A

Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	BELOW WATER LEVEL	1	100.00	(9.00+8.00)/2	1.80	1530.00
					TOTAL=	1530.00
					Total Qty =	1530.00
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	BELOW WATER LEVEL	1	12.00	(9.00+8.00)/2	0.90	91.80
	TOP LEVEL	1	100.00	5.00	0.30	150.00
					Total Qty. =	241.80
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
	1ST CUTTING	8	3.00	2.50		60.00
					Total Qty. =	60.00


JE


AE


EE

RWD SUB DIV- CHHATAPUR

RWD SUB DIV. CHHATAPUR

RWD WORKS DIV. TRIVENIGANJ

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in 2020 in SUPAUL District

Name of Road:

(L056)T01 CHAINPUR TO TANGARI PART-B

Block: CHHATAPUR

District: SUPAUL

Divison : RWD, Works Division, TRIVENIGANJ

Circle: RWD, Work Circle, Madhepura

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1350.00	522.67	705604.50
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	254.10	1751.13	444962.13
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	45.00	3377.00	151965.00
	TOTAL AMOUNT =				1302531.63
	ADD 12.00 %GST=				156303.80
	ADD 1% L.CESS=				13025.32
	SEIGNIORAGE FEE				49990.00
	SAY TOTAL AMOUNT =				1521850.75

1521851.00


20/11/20
JE

RWD SUB DIVISION-CHHATAPUR


20/11/20
AE

RWD SUB DIV.
CHHATAPUR


20/11/20
EE

RWD WORKS DIV. TRIVENIGANJ
EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

SE
MADHEPURA

Detailed Estimate

Name of Road:

(L056)T01 CHAINPUR TO TANGARI PART-B

Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	BELOW WATER LEVEL	1	100.00	(7.00+8.00)/2	1.80	1350.00
					TOTAL=	1350.00
					Total Qty =	1350.00
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	BELOW WATER LEVEL	1	12.00	(9.00+7.50)/2	0.90	89.10
	TOP LEVEL	1	100.00	5.50	0.30	165.00
						254.10
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
	1ST CUTTING	6	3.00	2.50		45.00
					Total Qty. =	45.00

[Signature]
20/11/20
JE

[Signature]
20/11/20
AE

[Signature]
20/11/20
EE

RWD SUB DIV- CHHATAPUR

RWD SUB DIV. CHHATAPUR RWD WORKS DIV. TRIVENIGANJ

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ