RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:-

SINGH TOLA SE TO BHAWANIPUR THATDA RAM TOLA TO JIT MOHAN SATHAN

DIVISION:-

R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:-

CHHATAPUR

ESTIMATED COST

1708598.00

प्रतिवेदन

पथ का नाम :- Skingh Tola se to Bhawani pero Thatala Ramtola to and का नाम :- Jih mahant Sathan
में बाढ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त प्रथ 60/07
में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है
जिसकी प्राक्कलित लागत रि.श. 15770 59
जिसकी प्राक्कलित लागत Rg. 1574059 है। उक्त पथ का निर्माण MMG.S.Y योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में। पथ के कटे (क्षतिग्रस्त)
भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।
प्राक्कलन मदो का दर वर्त्तमान अनुसुचित दर के अनुरूप है।

(Xe) 20

कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य प्रशाखा,। Supplie

सहायक अभियंता, ग्रामीण कार्य विभाग, कार्य अवर प्रमण्डल,। Bry 26 mil 20

कार्यपालक अभियंता, ग्रामीण कार्य विभाग,

Rural Works Department Work Division Trivenigani

Inspection Report for Flood Damage Work

The state of the s
Date:
1.Name of PIUs:-
2.Name of Block:- CHHATAPUR
3. Name of Road: - SINGH TOLA SE TO BHAWAHLPUR THATDA RAM TOLA TO
A. For Road DITMAHATSATHAN, Roed length- 4.2 KM
1.Damage Location/Chainage: 3rd KM
2.Damage Length :- 60M 90M
3. Nature of Damage :- Road work in Corft
4.Details of Restoration Works:-

B. For Bridge

(i.)Material being used in Restoration Works:-

(iii.)Procedure taken up in Restoration works:-

(ii.) Equipments/Tools being used in Restoration works:-

1. Damage Location/Chainage:- 3rd KM

2. Damage Length :- 60M 90 M

3. Nature of Damage :- Roed w/const-

4. Details of Restoration Works:-

(iv.)Restored Length :-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length:

100 m/20 Signature of JE/AE/EE

(Name of Inspector)

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in 2020 in SUPAUL District

Name of Road:

SINGH TOLA SE TO BHAWANIPUR THATDA RAM TOLA TO JIT MOHAN SATHAN

Block: CHHATAPUR

District: SUPAUL

Divison: RWD, Works Division, TRIVENIGANJ

Circle: RWD, Work Circle, Madhepura

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (R
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1575.00	522.67	823205.25
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
i		Cum	333.00	1751.13	583126.29
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	15.00	3377.00	50655.00
	TOTAL AMOUNT =				1456986.54
	ADD 12.00 %GST=				174838.38
	ADD 1% L.CESS=				14569.87
	S FEE				62203.00
	SAY TOTAL AMOUNT =				1708597.79
					1708598.00

JE JOIIING

RWD SUB DIVISION-CHHATAPUR

AE

RWD SUB DIV. CHHATAPUR EE

RWD WORKS DIV. TRIVENIGANJ

Techenically Approved for Ry 17,08,598/=
(Seventeen Lac Eight Thousand five hundred Hinty Eight) only

Noto114

318889 3184411

अधादाण कामायता ग्रामीण कार्न विभाग **कार्य अं**चल, मधेए

SE MADHÉPURA

Detailed Estimate

Name of Road:

SINGH TOLA SE TO BHAWANIPUR THATDA RAM TOLA TO JIT MOHAN SATHAN

SI No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	CH-3.00 KM	1	100.00	(7.50+6.00)/2	(2.0+3.00+2.0)/3	1575.00
					TOTAL=	1575.00
					Total Qty =	1575.00
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	CH-3.00 KM	1	100.00	6.00	0.30	180.00
		1	30.00	8.50	0.60	153.00
				<u> </u>	Total Qty. =	333.00
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
	CH-3.00 KM	2	3.00	2.50		15.00
					Total Qty. =	15.00

JE JE JII/OB

AE OF 1

EE Pring

RWD SUB DIV- CHHATAPUR

RWD SUB DIV. CHHATAPUR RWD WORKS DIV. TRIVENIGAN

RWD WORKS DIVISION TRIVENIGANJ