

55
43

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- PART-A PARIYAH NAHAR KE BALUA UDHAMPUR PATH TO
BALUA JADIYA SHW SADAK TAK VIA LALIT GRAM OP
RAILWAY STATION TENGARI VILLAGE TAK.

DIVISION:- R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:- R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:- CHHATAPUR

ESTIMATED COST

RS 2822364.00

प्रतिवेदन

पथ का नाम :- Periyah Nahor Ke Balua udhampur Path to Balua Jodiga
कार्य का नाम :- SHW Sadak via Lalitgaram Railway Station, toriya village
में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य। पथ की लम्बाई = 1.5 km

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त ~~पथ 360 + 65 = 425m~~

में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है

जिसकी प्राक्कलित लागत ~~Rs. 3098157.00~~ है।

उक्त पथ का निर्माण निविदा प्रक्रिया में योजनावर्तित हुआ है एवं योजना अनुरक्षण


अवधि में। पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद


यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट

रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


11/2/2021

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,


01/04/21

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,


11/2/21

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
Executive Engineer
Rural Works Department
Work Division,

Inspection Report for Flood Damage Work

Date:-.....

1. Name of PIUs:-

2. Name of Block:- CHHATAPUR

3. Name of Road:- Pariyahi Nahar Ke Balua Udhampura Path Ke Balua Jadiga

A. For Road

1. Damage Location/Chainage :- 1st KM

2. Damage Length :- 425m

3. Nature of Damage :- Road wash out

4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- 1st KM

2. Damage Length :- 425m

3. Nature of Damage :- Road wash out


4. Details of Restoration Works:-

(i.) Material being used in Restoration Works:-

(ii.) Equipments/Tools being used in Restoration works:-

(iii.) Procedure taken up in Restoration works:-

(iv.) Restored Length :

Signature of JE/AE/EE  1/2/2021

Signature  28/11

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in 2020 in SUPAUL District

Name of Road:
Block: CHHATAPUR

District: SUPAUL

Division : RWD, Works Division, TRIVENIGANJ

Circle: RWD, Work Circle, Madhepura

PART-A					
Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-				
		Cum	1500.00	522.67	784005.00
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	159.00	1751.13	278429.67
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	22.50	3280.40	73809.00
TOTAL AMOUNT =					1136243.67
ADD 12.00 %GST=					136349.24
ADD 1% L.CESS=					11362.44
S FEE					42434.7
SAY TOTAL AMOUNT =					1326390.05
1326390.00					


PART-B					
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1733.33	522.67	905961.33
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	159.00	1751.13	278429.67
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	30.00	3280.40	98412.00
TOTAL AMOUNT =					1282803.00
ADD 12.00 %GST=					153936.36
ADD 1% L.CESS=					12828.03
SEIGNIORAGE FEE=					46406.50
SAY TOTAL AMOUNT =					1495973.89
1495974.00					

PART-A+ PART-B=

2822364.00


JE
RWD SUB DIVISION-CHHATAPUR


AE
RWD SUB DIV. CHHATAPUR


EE
RWD WORKS DIV. TRIVENIGANJ

SE
MADHEPURA

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

अधीक्षक 27/04/21
ग्रामीण कार्य विभाग
कार्य अंचल, नयेपुरा
Technically approved for Rs 28,22,364/-
Twenty Eight Lac twenty two Thousand
Three hundred sixty four only

Detailed Estimate

Name of Road:

**PART-A PARIYAH I NAHAR KE BALUA UDHAMPUR PATH TO BALUA JADIYA SHW SADAK TAK VIA
LALIT GRAM OP RAILWAY STATION TENGARI VILLAGE TAK.**

PART-A						
Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
		1	100.00	5.00	(2.5+3.5+3.0)/3	1500.00
					TOTAL=	1500.00
					Total Qty =	1500.00
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	BELOW WATER LEVEL	1	10.00	8.00	0.30	24.00
	TOP LEVEL	1	100.00	4.50	0.30	135.00
					Total Qty. =	159.00
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
		3	3.00	2.50		22.50
					Total Qty. =	22.50
PART-B						
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
		1	100.00	5.00	(3.2+4.0+3.2)/3	1733.33
					TOTAL=	1733.33
					Total Qty =	1733.33
2.00	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	BELOW WATER LEVEL	1	10.00	8.00	0.30	24.00
	TOP LEVEL	1	100.00	4.50	0.30	135.00
					Total Qty. =	159.00
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
		4	3.00	2.50		30.00
					Total Qty. =	30.00

JE/2/21

AE

EE