


33 34

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

NH-57 TO NONIYA TO TOLA

ESTIMATED COST Rs 1412637.00

NAME OF ROAD :- (NH-57 TO NONIYA TO TOLA) middle School 1 Bhimpur1 to WN 10 ,11&14 Road

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

REPORT

An estimate amounting 1412637.00 has been framed to meet the actual cost of expenditure towards motarable work of middle School 1 Bhimpur1 to WN 10 ,11&14 Road in between In between 0 Km to .500 km & 2nd km Bhimpur of Chhatapur Block to resume normal traffic facilities for the year 2020-21.

This year's unpredictable rain fall in the Kosi basin broke the rural roads, which increased the problems of the villagers. In this rain, the life of people who were in trouble , were surrounded by water from all sides, it was necessary to resume normal traffic facilities . So that the voters and officials reach their respective booth smoothly As directed by SDO, Triveniganj vide his letter no. 271 dt 14.10. 2020

Measurement of the work had been recorded duly and attached along with the estimate. Local sand, brick bats, hume pipe and bamboos has been used to restore the traffic and accordingly estimate has been framed on basis of up-to-date SOR .

Hence requested for technical approval of the estimate .


20/11/20
Junior Engineer


29/10
S D O
Rural Works Sub division
Chhatapur


24/11/20
Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- CHHATA PUR

3.Name of Road:- NH-57- TO. NONIYA TOLA, UNDR, WORK, MIDDLE SCHOOL

A. For Road

BHIMPUR TO W.No 10, 11, AND 14. Road length-5km

1.Damage Location/Chainage :- In 1st. and 3rd km

2.Damage Length :- 240 m

3.Nature of Damage :- Road wash out one side cutting

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- In 1st and 3rd km

2.Damage Length :- 240m

3.Nature of Damage :- Road wash and side cutting

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :


22/10

Signature of JE/AE/EE


27/11/21

Signature

(Name of Inspector)

सेवा में

कार्यपालक अनियंता

ग्रामीण कार्य विभाग कार्य प्रमंडल, त्रिवेणीगंज।

त्रिवेणीगंज, दिनांक- 14.10.2020

विषय : बिहार विधान सभा आम निर्वाचन 2020 के महेनजर मतदान केन्द्र तक पहुँच पथ के निर्माण के संबंध में।

महोदय,

उपर्युक्त विषयक संदर्भ में कहना है कि बिहार विधान सभा आम निर्वाचन 2020 के महेनजर कुल चार श्रोतों से मतदान केन्द्र तक पहुँच पथ के निर्माण एवं मरम्मति से जुड़े जन शिकायत आवेदन पत्र प्राप्त हुआ है, जिसका विवरण इस प्रकार है :-

क्र०	आवेदक का नाम व पता	शिकायत का विषय वस्तु	अभ्युक्ति
1	2	3	4
1	आशीषकान्त झा व 10 अन्य ग्रामीण जनता ग्राम+पंचायत-मधुबनी, प्रखंड- छातापुर	मधुबनी पंचायत अंतर्गत मेहता टोला प्रांत कि मधुबनी में वार्ड नं०-9,11,12 एवं संवि० मधुबनी में वार्ड नं०-13 एवं संवि०कोडर में वार्ड नं०-3,4,5 में मतदाता के आवागमन हेतु कटावप्रस्त सड़क को जोड़ने के संबंध में।	
2	जयकृष्ण साह एवं 06 अन्य ग्राम पंचायत बलुआ प्रखंड-छातापुर	बलुआ पंचायत अंतर्गत मांकि बलुआ में वार्ड नं०-4 एवं 8 को जोड़ने वाली सड़क की मरम्मति के संबंध में।	
3	रजित कुमार सिंह एवं 10 अन्य, छा० पंचायत-भीमपुर प्रखंड-छातापुर	छा०मांकि भीमपुर एवं मांकि भीमपुर मतदान केन्द्र पर जाने हेतु भीमपुर में वार्ड नं०-3,5,9,10,11,12,13 से जुड़े सड़क की मरम्मति के संबंध में।	
4	लालन कुमार मंडल एवं 07 अन्य, ग्राम पंचायत- लक्ष्मीनिर्वा प्रखंड-छातापुर	खुनदन मांकि एवं उदु मांकि लक्ष्मीनिर्वा मतदान केन्द्र पर जाने जाने हेतु वार्ड नं०-07, 11, 12 मंडल टोला एवं लक्ष्मीनिर्वा वार्ड नं०-01,02 से जुड़े सड़क की मरम्मति एवं निर्माण के संबंध में।	

क्रम सं०- 01 से 04 पर अंकित परिवाद पत्र का विषय-वस्तु मतदान केन्द्रों पर पहुँच पथ एवं आवागमन की असुविधा के दृष्टिगत चुनाव बहिष्कार करने के विरुद्ध वर्णित स्थलों पर मतदाताओं के आवागमन हेतु सड़क निर्माण एवं मरम्मति कार्य कराने व मतदाता को सुविधा मुहैया कराये जाने से संबंधित है। आवेदन पत्र की छायाप्रति संलग्न कर भेजी जा रही है।

अतः अनुरोध है कि वर्णित स्थलों पर आगामी विधान सभा निर्वाचन 2020 के महेनजर मतदाताओं के मतदान केन्द्र तक आवागमन हेतु पहुँच पथ के निर्माण व मरम्मति हेतु आवश्यक कार्रवाई करने का कृपया करेंगे।

अनुलग्नक : यथावर्णित।

विश्वासभाजन,

निर्वाची पदाधिकारी

-सह-

अनुमंडल पदाधिकारी
त्रिवेणीगंज।

DETAIL OF ESTIMATE FOR REPAIR /MOTARABLE WORK

ROAD AT RD.....

(NH-57 TO NONIYA TO TOLA) middle School 1 Bhimpur1 to WN 10,11&14
Road

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj

BLOCK :- CHHATAPUR


Sub division:-Chhatapur

PANCHAYAT :-

Bhimpur

Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge				620.70cum
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I				401.4 cum


Junior Engineer
Chhatapur
S D O
Rural Works Sub division
Chhatapur
Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division: Triveniganj

DETAIL OF ESTIMATE FOR REPAIR /MOTARABLE WORK

Abstract of Cost

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur

PANCHAYAT :- Bhimpur

Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge	620.70cum	Cum	626.89	389110.62
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	401.4 cum	Cum	2145.02	861011.03
					1250121.65

Add 12% GST on item no 4, 5

Add 1% Labour cess total item

Total

1250121.65

150014.60

12501.22

1412637.47

Rs 1412637.00

AK
20/10/20

Junior Engineer
Chhatapur

Sub
20/10

S D O
Rural Works Sub division
Chhatapur

Am
20/10/20

Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Technically Approved for Rs 14,12,637.00

(Fourteen Lac twelve thousand six hundred thirty seven only)

H
07/04/21

अधीक्षक
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

SE

MEASUREMENT SHEET

1

Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge

Ch	Length in M	width in M	depth in(Av.) M	Quantity cum
	15	6.00	0.30	27.0cum
	6	5.00	0.90	27.0cum
	10	5.00	0.90	45.0cum
	19	4.00	0.90	68.4cum
	29	4.00	0.60	69.6cum
	7	4.00	0.60	16.8cum
	15	4.00	0.30	18.0cum
	20	5.00	0.30	30.0cum
	20	5.00	0.30	30.0cum
	10	4.50	0.30	13.5cum
	30	4.50	0.30	40.5cum
	17	4.50	0.60	45.9cum
	40	4.50	0.60	108.0cum
	30	4.50	0.60	81.0cum
				620.7cum

2

Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I

Ch	Length in M	width in M	depth in(Av.) M	Quantity cum
	15	5.50	0.30	24.8cum
	6	4.50	0.15	4.1cum
	10	4.50	0.60	27.0cum
	19	3.50	0.15	10.0cum
	29	3.50	0.15	15.2cum
	7	3.50	0.60	14.7cum
	15	3.50	0.60	31.5cum
	20	4.50	0.30	27.0cum
	20	4.50	0.30	27.0cum
	10	4.00	0.60	24.0cum
	30	4.00	0.60	72.0cum
	17	4.00	0.15	10.2cum
	40	4.00	0.60	96.0cum
	30	4.00	0.15	18.0cum
				401.4cum

Junior Engineer
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division, Triveniganj