

33 40

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- HOUSE OF HIRALAL MUKHAYA SHW TO
YADAV TOLA.

DIVISION:- R.W.D, WORKS DIVISION, TRIVENIGANJ

CIRCLE:- R.W.D, WORK CIRCLE, MADHEPURA

BLOCK:- CHHATAPUR

ESTIMATED COST

2393250.00

प्रतिवेदन

पथ का नाम :- *House of Hiralal Mukhiya SH To Yadav Tola*

कार्य का नाम :- *Length of Road- 1.6 Km*

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 10.06.2020 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त *पथ 1.6 Km*

में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत *Rs 2917640* है।

उक्त पथ का निर्माण *निविदा प्रक्रिया में* योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में *बढ़ी* पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

AR
20/11/20

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,

AR
20/11/20

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल,

AR
20/11/20

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल,
Executive Engineer
Rural Works Department
Work Division Trivenigani

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- CHHATAPUR

3.Name of Road:- House of Hiralal Meekhuig a SHW TO Jadar Tolg

A. For Road

Road length-2KM

1.Damage Location/Chainage :- In 1st 1km

2.Damage Length :- 145m 190m

3.Nature of Damage :- wash out

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- In 1st 1km

2.Damage Length :- 145m 190m

3.Nature of Damage :- wash out

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

APD
24/11/20
Sul
06/11

Signature of JE/AE/EE

Signature
28/11/21

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in 2020 in SUPAUL District

Name of Road:

HOUSE OF HIRALAL MUKHAYA SHW TO YADAV TOLA.

Block: CHHATAPUR

District: SUPAUL

Division : RWD, Works Division, TRIVENIGANJ

Circle: RWD, Work Circle, Madhepura

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	2351.25	522.13	1227658.16
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	403.80	1751.13	707106.29
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	32.50	3377.00	109752.50
	TOTAL AMOUNT =				2044516.96
	ADD 12.00 %GST=				245342.03
	ADD 1% L.CESS=				20445.17
	Spec				82946.00
	SAY TOTAL AMOUNT =				2393250.16

2393250.00

Ar
20/11/20
JE

RWD SUB DIVISION-CHHATAPUR

SP
20/11/20
AE

RWD SUB DIV.
CHHATAPUR

km
20/11/20
EE

RWD WORKS DIV. TRIVENIGANJ
EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

Technically approved for Rs 23,93,250=00
(Rupees twenty three Lac ninety three thousand two hundred
fifty only)

AK
07/04/21

SE
MADHEPURA

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

Detailed Estimate

Name of Road:

HOUSE OF HIRALAL MUKHAYA SHW TO YADAV TOLA.

Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	1ST CUTTING	1	40.00	(6.00+5.00)/2	(2.00+2.50)/2	495.00
	2ND CUTTING	1	150.00	(6.00+5.00)/2	(2.00+2.50)/2	1856.25
					TOTAL=	2351.25
					Total Qty. =	2351.25
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.					
	1ST CUTTING	1	10.00	(8.00+8.5)/2	0.90	74.25
	TOP LAYER	1	40.00	5.00	0.30	60.00
	2ND CUTTING	1	6.00	(8.00+8.5)/2	0.90	44.55
	TOP LAYER	1	150.00	5.00	0.30	225.00
					Total Qty. =	403.80
3	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.					
	1ST CUTTING	3	3.00	2.50		22.50
	2RD CUTTING	2	2.00	2.50		10.00
					Total Qty. =	32.50


JE 20/10/24

RWD SUB DIV- CHHATAPUR


AE

RWD SUB DIV. CHHATAPUR RWD WORKS DIV. TRIVENIGANJ


EE

EXECUTIVE ENGINEER
RWD WORKS DIV. TRIVENIGANJ