

34
29

GOVT. OF BIHAR



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

ESTIMATED COST Rs 3376439.00

NAME OF ROAD :-

(SHATUT BHAWAN TO BRAHAMAN TOLA DODRA) Lakshminiya
panchayat untergat raghunandan middle school, w no-7 road

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

REPORT


An estimate amounting 1551466.00 has been framed to meet the actual cost of expenditure towards motarable work of Lakshminiya panchayat untergat raghunandan middle school, w no-11 & w no-12 road in between In between 1st Km & 3rd km Lakshminiya of Chhatapur Block to resume normal traffic facilities for the year 2020-21.

This year's unpredictable rain fall in the Kosi basin broke the rural roads, which increased the problems of the villagers. In this rain, the life of people who were in trouble, were surrounded by water from all sides, it was necessary to resume normal traffic facilities. So that the voters and officials reach their respective booth smoothly As directed by SDO, Triveniganj vide his letter no. 271 dt 14.10. 2020

Measurement of the work had been recorded duly and attached along with the estimate. Local sand, brick bats, hume pipe and bamboos has been used to restore the traffic and accordingly estimate has been framed on basis of up-to-date SOR.

Hence requested for technical approval of the estimate.


20/10/20
Junior Engineer


22/10
S D O
Rural Works Sub division
Chhatapur


26/11/20
Executive Engineer
Rural Works division
Triveniganj
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- CHHATA PUR

3.Name of Road:- Shatut Bhawan to Boahaman to Dodra. Under-Road
Lakshminiya Panchayat untergat Raghunandan middle school
W.No- 11, and 12.

A. For Road

1.Damage Location/Chainage:- In 1st and 3rd km, and Road length = 3 km

2.Damage Length :- $515m + 435m = 950m$

3.Nature of Damage :- Road wash out and side cutting

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- In 1st and 3rd km

2.Damage Length :- $515m + 435m = 950m$

3.Nature of Damage :- Road wash out and side cutting


4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-


(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :


29/11/21

Signature of JE/AE/EE


28/11/21

Signature

(Name of Inspector)

सेवा में

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग कार्य प्रमंडल, त्रिवेणीगंज।

त्रिवेणीगंज, दिनांक- 14.10.2020

विषय : बिहार विधान सभा आम निर्वाचन 2020 के महेनजर मतदान केन्द्र तक पहुँच पथ के निर्माण के संबंध में।

महाराज,

उपर्युक्त विषयक संदर्भ में कहना है कि बिहार विधान सभा आम निर्वाचन 2020 के महेनजर कुल चार स्रोतों से मतदान केन्द्र तक पहुँच पथ के निर्माण एवं मरम्मति से जुड़े जन शिकायत आवेदन पत्र प्राप्त हुआ है, जिसका विवरण इस प्रकार है :-

क्र०	आवेदक का नाम व पता	शिकायत का विषय वस्तु	अभ्युक्ति
1	2	3	4
1	आशीषकान्त झा व 10 अन्य ग्रामीण जनता, ग्राम-पंचायत-मधुबनी, प्रखंड- छातापुर	मधुबनी पंचायत अंतर्गत मेहता टोला ग्राम कि मधुबनी में वार्ड नं०-2,11,12 एवं सड़क नं०-13 एवं सड़क नं०-3,4,5 में मतदाता के आवागमन हेतु कटावप्रस्त सड़क को जोड़ने के संबंध में।	
2	जयकृष्ण साह एवं 06 अन्य ग्राम पंचायत बलुआ प्रखंड-छातापुर	बलुआ पंचायत अंतर्गत मठवि बलुआ में वार्ड नं०-4 एवं 6 को जोड़ने वाली सड़क की मरम्मति के संबंध में।	
3	रजित कुमार सिंह एवं 10 अन्य, ग्राम पंचायत-भीमपुर प्रखंड-छातापुर	उमठवि भीमपुर एवं मठवि भीमपुर मतदान केन्द्र पर जाने हेतु भीमपुर में वार्ड नं०-3,5,9,10,11,12,13 से जुड़े सड़क की मरम्मति के संबंध में।	
4	ललन कुमार मंडल एवं 07 अन्य, ग्राम पंचायत-लक्ष्मीनिर्वा प्रखंड-छातापुर	रघुनंदन मठवि एवं उदू मठवि लक्ष्मीनिर्वा मतदान केन्द्र पर जाने जाने हेतु वार्ड नं०-07, 11, 12 मंडल टोला एवं लक्ष्मीनिर्वा वार्ड नं०-01,02 से जुड़े सड़क की मरम्मति एवं निर्माण के संबंध में।	

क्रम सं०- 01 से 04 पर अर्जित परिवाद पत्र का विषय-वस्तु मतदान केन्द्रों पर पहुँच पथ एवं आवागमन की असुविधा के दृष्टिगत चुनाव बहिष्कार करने के विरुद्ध वर्णित स्थलों पर मतदाताओं के आवागमन हेतु सड़क निर्माण एवं मरम्मति कार्य कराने व मतदाता को सुविधा मुहैया कराये जाने से संबंधित है। आवेदन पत्र की छायाप्रति संलग्न कर भेजी जा रही है।

अतः अनुरोध है कि वर्णित स्थलों पर आगामी विधान सभा निर्वाचन 2020 के महेनजर मतदाताओं के मतदान केन्द्र तक आवागमन हेतु पहुँच पथ के निर्माण व मरम्मति हेतु आवश्यक कार्रवाई करने का कष्ट करेंगे।

अनुलग्नक : 04 वर्णित।

विवेकासभाजन

निर्वाची पदाधिकारी

-सह-

अनुमंडल पदाधिकारी

त्रिवेणीगंज।

ABSTRACT OF COST

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK

ROAD AT ROAD-

SHATUT BHAWAN TO BRAHAMAN TOLA DODRA(Lakshminiya
panchayat untergat raghunandan middle school, w no-7 road)

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj


BLOCK :- CHHATAPUR


Sub division:-Chhatapur

Yr. 2020-21

Sl. No./ item no.	Item of works		
1	PART -A		1767756.00
	PART-B		1608683.00
2			
	TOTAL=		3376439.00


20/11/20
Junior Engineer
Chhatapur


S D O
Rural Works Sub division
Chhatapur


Executive Engineer
Rural Works division
Triveniganj

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

Technically approved for Rs 33,76,439/-
(Thirty three Lac Seventy six Thousand four hundred Thirty nine) only

SE
MADHEPURA 

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK**A**

ROAD AT RD.....

(SHATUT BHAWAN TO BRAHAMAN TOLA DODRA) Lakshminiya panchayat

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur


PANCHAYAT :-


Lakshminiya

Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Filling of Local Sand Obtain from River Bed				639.75cum
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all				515.3 cum


Junior Engineer
Chhatapur


S D O
Rural Works Sub division
Chhatapur


Executive Engineer
Rural Works division
Triveniganj
EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK 'A' **Abstract of Cost**

Division:- RWD triveniganj
Sub division:-Chhatapur

BLOCK :- CHHATAPUR
PANCHAYAT :- Lakshminiya
Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge	639.75cum	Cum	626.89	401052.88
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	515.3 cum	Cum	2145.02	1105221.56
					1506274.43

Add 12% GST on item no 4, 5
Add 1% Labour cess total item
SEIGNIORAGE FEE
ADD
Total

1506274.43
180752.93
15062.74
65666.00

1767756.11

Rs 1767756.00

Junior Engineer
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj

EXECUTIVE ENGINEER
RWD WORKS
TRIVENIGANJ

MEASUREMENT SHEET

Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per

1

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
	30	4.25	0.30	38.3cum
	30	5.00	0.30	45.0cum
	30	5.00	0.30	45.0cum
	10	4.50	0.30	13.5cum
	30	6.00	0.30	54.0cum
	30	5.00	0.30	45.0cum
	30	3.50	0.30	31.5cum
	30	4.00	0.60	72.0cum
	30	4.00	0.30	36.0cum
	30	4.00	0.40	48.0cum
	30	5.00	0.30	45.0cum
	30	5.00	0.30	45.0cum
	40	4.50	0.30	54.0cum
	30	4.00	0.30	36.0cum
	30	3.50	0.30	31.5cum
				639.8cum

2

Supply and carriage of brikk bats up to 8 km from breach

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
	30	3.75	0.30	33.8cum
	30	4.50	0.30	40.5cum
	30	4.50	0.30	40.5cum
	10	4.00	0.30	12.0cum
	30	5.50	0.30	49.5cum
	30	4.50	0.30	40.5cum
	30	3.00	0.30	27.0cum
	30	3.50	0.30	31.5cum
	30	3.50	0.30	31.5cum
	30	3.50	0.20	21.0cum
	30	4.50	0.30	40.5cum
	30	4.50	0.30	40.5cum
	40	4.00	0.30	48.0cum
	30	3.50	0.30	31.5cum
	30	3.00	0.30	27.0cum
				515.3cum

Junior Engineer
Chhatapur

S D O
Rural Works Sub division
Chhatapur

Executive Engineer
Rural Works division
Triveniganj
EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK**Abstract of Cost B**

Division:- RWD triveniganj
Sub division:-Chhatapur

BLOCK :- CHHATAPUR
PANCHAYAT :- Lakshminiya

Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge	771.00cum	Cum	626.89	483332.19
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	414.8 cum	Cum	2145.02	889647.05
					1372979.24

1372979.24

Add 12% GST on item no 4, 5

164757.51

Add 1% Labour cess total item

13729.79

SEIGNIORAGE FEE

57217.00

ADD

Total

1608683.54


Rs 1608683.00


20/10/20

Junior Engineer
Chhatapur

S D O

Rural Works Sub division
Chhatapur


Executive Engineer

Rural Works division

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

DETAILS OF ESTIMATE FOR REPAIR /MOTARABLE WORK

ROAD AT RD.....

(SHATUT BHAWAN TO BRAHAMAN TOLA DODRA)Lakshminiya panchayat untergat

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj

BLOCK :- CHHATAPUR

Sub division:-Chhatapur

PANCHAYAT :-

Lakshminiya

Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Filling of Local Sand Obtain from River Bed				771.00cum
2	Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all				414.8 cum

Junior Engineer
Chhatapur

S D O

Rural Works Sub division
Chhatapur

Executive Engineer

Rural Works division

Triveniganj

EXECUTIVE ENGINEER
RWD WORKS DIVISION
TRIVENIGANJ

MEASUREMENT SHEET

'B'

1

Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification &


Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
	30	3.50	0.60	63.0cum
	30	4.00	0.40	48.0cum
	30	5.00	0.40	60.0cum
	30	4.00	0.30	36.0cum
	30	4.00	0.30	36.0cum
	30	5.00	0.30	45.0cum
	30	3.50	0.30	31.5cum
	30	4.00	0.40	48.0cum
	30	4.00	0.30	36.0cum
	30	3.50	0.30	31.5cum
	30	4.00	0.40	48.0cum
	30	3.50	0.40	42.0cum
	30	4.00	0.30	36.0cum
	30	5.00	0.40	60.0cum
	30	4.00	0.50	60.0cum
	30	5.00	0.30	45.0cum
	30	5.00	0.30	45.0cum
				771.0cum


2

Supply and carriage of brikk bats up to 8 km from breach and placing in

Ch	Length in M	width in M	depth in (Av.) M	Quantity cum
	30	3.00	0.15	13.5cum
	30	3.50	0.20	21.0cum
	30	4.50	0.30	40.5cum
	30	3.50	0.15	15.8cum
	30	3.50	0.30	31.5cum
	30	4.50	0.30	40.5cum
	30	3.00	0.20	18.0cum
	30	3.50	0.15	15.8cum
	30	3.50	0.30	31.5cum
	30	3.00	0.15	13.5cum
	30	3.50	0.30	31.5cum
	30	3.00	0.15	13.5cum
	30	3.50	0.30	31.5cum
	30	4.50	0.30	40.5cum
	30	3.50	0.15	15.8cum
	30	4.50	0.15	20.3cum
	30	4.50	0.15	20.3cum
				414.8cum


20/10/20
Junior Engineer
Chhatapur


20/10
S D O
Rural Works Sub division
Chhatapur


20/10/20
Executive Engineer
Rural Works division
Triveniganj

EXECUTIVE ENGINEER
RWD WORKS
TRIVENIGANJ