


35  
28

# GOVT. OF BIHAR



## ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

Year 2020-21

ESTIMATED COST Rs 1578619.00

NH-57

NAME OF ROAD :- (KABRISTHAN TO MUSHARI TOLA) Madhubani patanchayt Primary school WN 9,11 & 12 Road

DIVISION :- RWD ,WORKS DIVISION , TRIVENIGANJ

CIRCLE :- RWD , WORKS CIRCLE MADHEPURA

Block :- CHHATAPUR SUPAUL

## REPORT

An estimate amounting to ~~1578619.00~~ has been framed to meet the actual cost of expenditure towards motarable


work of **Madhubani patanchayt Primary school WN 9,11 & 12 Road**  
in between ~~In between~~ 0 Km to 1 ST KM & 2nd km & 3rd km Madhubani  
of Chhatapur Block to resume normal traffic facilities for the year 2020-21.


This year's unpredictable rain fall in the Kosi basin broke the rural roads, which increased the problems of the villagers. In this rain, the life of people who were in trouble, were surrounded by water from all sides, it was necessary to resume normal traffic facilities. So that the voters and officials reach their respective booth smoothly As directed by SDO, Triveniganj vide his letter no. 271 dt 14.10. 2020

Measurement of the work had been recorded duly and attached along with the estimate. Local sand, brick bats, hume pipe and bamboos has been used to restore the traffic and accordingly estimate has been framed on basis of up-to-date SOR.

Hence requested for technical approval of the estimate.

  
20/10/20  
Junior Engineer

  
22/10/20  
S D O  
Rural Works Sub division  
Chhatapur

  
22/10/20  
Executive Engineer  
Rural Works division  
Triveniganj  
Executive Engineer  
Rural Works Department  
Work Division, Triveniganj

## Inspection Report for Flood Damage Work

Date:-.....

1.Name of PIUs:-

2.Name of Block:- CHHATAPUR

3.Name of Road:- Madhubni Panchayat Primary school. W. No-9, 11, and 12

Road, under- Motorable work

A. For Road

1.Damage Location/Chainage :- In 1st and 2nd Km

2.Damage Length :- 315m

3.Nature of Damage :- Road wash out and side cutting

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-

(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :-

B. For Bridge

1. Damage Location/Chainage:- In 1st and 2nd Km

2.Damage Length :- 315m

3.Nature of Damage :- Road wash out and side cutting.

4.Details of Restoration Works:-

(i.)Material being used in Restoration Works:-


(ii.)Equipments/Tools being used in Restoration works:-

(iii.)Procedure taken up in Restoration works:-

(iv.)Restored Length :

  
20/10/20

Signature of JE/AE/EE

  
27/11/21

Signature

(Name of Inspector)

सेवा में

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग कार्य प्रमंडल, त्रिवेणीगंज।

त्रिवेणीगंज, दिनांक 14.10.2020

विषय : बिहार विधान सभा आम निर्वाचन 2020 के मद्देनजर मतदान केन्द्र तक पहुँच पथ के निर्माण के संबंध में।

महाराज,

उपर्युक्त विषयक संदर्भ में कहना है कि बिहार विधान सभा आम निर्वाचन 2020 के मद्देनजर कुल चार स्रोतों से मतदान केन्द्र तक पहुँच पथ के निर्माण एवं मरम्मति से जुड़े जन शिकायत आवेदन पत्र प्राप्त हुआ है, जिसका विवरण इस प्रकार है :-

क्र०	आवेदक का नाम व पता	शिकायत का विषय वस्तु	अभ्युक्ति
1	2	3	4
1	आशीषकान्त झा व 10 अन्य ग्रामीण जनता ग्राम+पंचायत-मधुबनी, प्रखंड- छातापुर	मधुबनी पंचायत अंतर्गत मेहता टोला ग्राम वि० मधुबनी में वार्ड न०-9,11,12 एवं संचिडि मधुबनी में वार्ड न०-13 एवं संचिडिदोहरा में वार्ड न०-3,4,5 में मतदाता के आवागमन हेतु कटारपरत सड़क को जोड़ने के संबंध में।	
2	जयकृष्ण साह एवं 06 अन्य ग्राम पंचायत बलुआ प्रखंड-छातापुर	बलुआ पंचायत अंतर्गत मावि० बलुआ में वार्ड न०-4 एवं 8 को जोड़ने वाली सड़क की मरम्मति के संबंध में।	
3	रजित कुमार सिंह एवं 10 अन्य, ग्राम पंचायत-भीमपुर प्रखंड-छातापुर	उमरवि० भीमपुर एवं मावि० भीमपुर मतदान केन्द्र पर जाने हेतु भीमपुर में वार्ड न०-3,5,9,10,11,12,13 से जुड़े सड़क की मरम्मति के संबंध में।	
4	लालन कुमार मंडल एवं 07 अन्य, ग्राम पंचायत- लक्ष्मीनिर्या प्रखंड-छातापुर	रघुनंदन मावि० एवं उदू मावि० लक्ष्मीनिर्या मतदान केन्द्र पर जाने जाने हेतु वार्ड न०-07 11 12 मंडल टोला एवं लक्ष्मीनिर्या वार्ड न०-01,02 से जुड़े सड़क की मरम्मति एवं निर्माण के संबंध में।	

क्रम सं०- 01 से 04 पर अंकित परिवाद पत्र का विषय-वस्तु मतदान केन्द्रों पर पहुँच पथ एवं आवागमन की असुविधा के दृष्टिगत चुनाव बहिष्कार करने के विरुद्ध वर्णित स्थलों पर मतदाताओं के आवागमन हेतु सड़क निर्माण एवं मरम्मति कार्य कराने व मतदाता को सुविधा मुहैया कराये जाने से संबंधित है। आवेदन पत्र की छायाप्रति संलग्न कर भेजी जा रही है।

अतः अनुरोध है कि वर्णित स्थलों पर आगामी विधान सभा निर्वाचन 2020 के मद्देनजर मतदाताओं के मतदान केन्द्र तक आवागमन हेतु पहुँच पथ के निर्माण व मरम्मति हेतु आवश्यक कार्रवाई करने का कृप्य करेंगे।

अनुलग्नक : यथावर्णित।

विश्वासभाजन,

निर्वाची पदाधिकारी

-सह-

अनुमंडल पदाधिकारी  
त्रिवेणीगंज।



# **DETAIL OF ESTIMATE FOR REPIR /MOTARABLE WORK**

## **Abstract of Cost**

Division:- RWD triveniganj  
Sub division:-Chhatapur

BLOCK :- CHHATAPUR  
PANCHAYAT :- Madhubani

Yr. 2020-21

Sl. No./ item no.	Item of works	Quantity	Unit	Rate	Amount
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge	903.00cum	Cum	626.89	566081.67
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I	387.4 cum	Cum	2145.02	830927.12
					1397008.79

Add 12% GST on item no 4, 5  
Add 1% Labour cess total item  
Total

1397008.79  
167641.06  
13970.09  
1578619.94  
Rs 1578619.00

*AP*  
20/10/20  
Junior Engineer  
Chhatapur

*SDO*  
20/10/20  
S D O  
Rural Works Sub division  
Chhatapur

*dy*  
26/10/20  
Executive Engineer  
Rural Works division  
Triveniganj  
Executive Engineer  
Rural Works Department  
Triveniganj

Technically approved for Rs 15,78,619/-  
(Rupees fifteen Lac Seventy Eight Thousand Six hundred  
nineteen only)

*11/07/21*  
अधीक्षण अभियंता  
ग्रामीण कार्य विभाग  
कार्य अंचल, मधेपुरा

SE

**DETAILE OF ESTIMATE FOR REPIR /MOTARABLE WORK**

ROAD AT RD.....

(KABRISTHAN TO MUSHARI TOLA) Madhubani patanchayt Primary school WN  
9,11 & 12 Road

AS PER ACTUAL WORK DONE

Division:- RWD triveniganj

BLOCK :- CHHATAPUR


Sub division:-Chhatapur


PANCHAYAT :-


Madhubani

Yr. 2020-21

Sl. No./ item no.	Item of works	L	B	H	Quantity
1	Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per spacification & direction of Engineer-in.Charge				903.00cum
2	Supply and carriage of bribk bats up to 8 km from breach and placing in breach and laying of bats all complete job. as perspecification and direction of E/I				387.4 cum

  
20/10/20  
Junior Engineer  
Chhatapur

  
20/10/20  
S D O  
Rural Works Sub division  
Chhatapur

  
20/10/20  
Executive Engineer  
Rural Works division  
Triveniganj  
Executive Engineer  
Rural Works Department  
Rural Division Triveniganj

# MEASUREMENT SHEET

Filling of Local Sand Obtain from River Bed ,Watering & ramming all Complete as per specification & direction of Engineer-in.Charge

1

Ch	Length in M	width in M	depth in (Av.)M	Quantity cum
1st KM	20	5.00	0.90	90.0cum
	20	5.00	0.90	90.0cum
	30	5.00	0.90	135.0cum
	15	5.00	1.20	90.0cum
	5	6.00	0.30	9.0cum
	10	6.00	0.30	18.0cum
	15	5.00	0.30	22.5cum
2nd KM	10	5.00	0.30	15.0cum
	15	5.00	0.60	45.0cum
	15	5.00	0.60	45.0cum
	15	5.00	0.30	22.5cum
	15	5.00	0.60	45.0cum
	20	5.00	0.60	60.0cum
	15	5.00	0.30	22.5cum
	30	5.00	0.30	45.0cum
	15	4.00	0.60	36.0cum
	25	5.00	0.30	37.5cum
	15	4.00	0.30	18.0cum
	15	5.00	0.60	45.0cum
	10	4.00	0.30	12.0cum
				903.0cum

2

Supply and carriage of brikk bats up to 8 km from breach and placing in breach and laying of bats all complete job.specification and direction of E/I

	Length in M	width in M	depth in (Av.)M	Quantity cum
1st KM	20	4.50	0.30	27.0cum
	20	4.50	0.30	27.0cum
	30	4.50	0.30	40.5cum
	15	4.50	0.15	10.1cum
	5	5.50	0.30	8.3cum
	10	5.50	0.30	16.5cum
2nd KM	15	4.50	0.30	20.3cum
	10	4.50	0.30	13.5cum
	15	4.50	0.15	10.1cum
	15	4.50	0.15	10.1cum
	15	4.50	0.30	20.3cum
	15	4.50	0.30	20.3cum
	20	4.50	0.30	27.0cum
	15	4.50	0.30	20.3cum
	30	4.50	0.15	20.3cum
	15	3.50	0.30	15.8cum
	25	4.50	0.30	33.8cum
	15	3.50	0.30	15.8cum
	15	4.50	0.30	20.3cum
	10	3.50	0.30	10.5cum
				387.4cum

AK  
20/10/20  
Junior Engineer  
Chhatapur

S D O  
Rural Works Sub division  
Chhatapur

Executive Engineer  
Rural Works division  
Triveniganj  
Rural Works Division, Patna