

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Chapra

DIVISION – R.W.D. works Division , Marhaura

Name of Work - Motrable of Road from Kanya Vidyalaya of Amnaur
Taraiya Road to Parshurampur Gandak Dam via
Gosi Amnaur

Block - Amnaur

Estimated cost - Rs 2526976.00

Year : 2020-21

प्रतिवेदन

कार्य का नाम :- *Motable of Road from Kanya Vidyalaya of Amnour to Road to Panchsheelam Gurdole from Via Gosi Amnour*
शीर्ष :- FDR
प्राक्कलित राशि :- 2526976/-
प्रखण्ड का नाम :- अमनौर जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल मढ़ौरा के दिशा-निर्देशन में कुल रु0 2526976/- के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bats, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।

[Signature]
25/11/20
J.B. Amnour

[Signature]
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मढ़ौरा।
25/11/20

Inspection Report for Flood damage work

Date:

1. Name of PIUs- E.E. R.W.D (W) Morela

2. Name of Block/Road- Amangur - Motorole of Roul Jann Karaya

A. For Road
Vidyalay of Amangur Tanya Road to Pashuram
Gandhi Dam Yai Gassi Amangur

1. Damage Location/Chainage : - 2.20, 2.40, 2.60, 2.75.

2. Damage Length : 267.40 M.

3. Nature of Damage : Road cutting due to flood.

4. Details of Restoration :

i Material being used in Restoration

: Stone ball, sand filling.

ii Equipment/Tools being used in Restoration works: Roller, Tractor, J.C.B, Bulky

iii Procedure taken up in Restoration works

: Dumping, laying, Rolling

iv Restored Length

: 267.40

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

E. Akhilesh Kumar
(Name of Inspector)

EE

RWD (W) Division
SONEFOR.


ABSTRACT OF COST


Name of Work - Motrable of Road from Kanya Vidyalaya of Amnaur -Taraiya Road to Parshurampur Gandak Dam via Gosi Amnaur


Block - Amnaur

S.L No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work	Rs 2236262.00
B	Add 12 % GST on (A)	Rs 268351.00
C	Add 1 % L. Cess on (A)	Rs 22363.00
	Total Cost	Rs 2526976.00

Rs 25,26,976.00


J.E
RWD
Amnaur


A.E
R.W.D
Amnaur


E.E
R.W.D
Marhaura

T/A for 25.26.976.00 (Rupees twenty five lac twenty six thousand nine hundred seventy six only)


अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा

Name of work :-

Detailed Estimate

Motorable of Road from Kanya Vidyalaya of Amnaur -Taraiya Road to Parshurampur Gandak Dam via Gosi Amnaur

SI No	Item	No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	4.00	4.00	0.45	7.20			
		1	5.50	4.00	0.76	16.72			
		2	16.00	4.52	1.05	151.87			
		1	13.00	4.45	1.13	65.37			
		1	6.40	3.75	1.00	24.00			
		3	10.00	4.00	0.70	84.00			
		3	24.00	4.12	1.42	421.23			
		2	20.00	4.10	0.80	131.20			
		1	13.30	3.90	0.60	31.12			
		1	17.40	4.24	0.80	59.02			
		1	13.00	4.13	1.20	64.43			
		1	15.00	4.00	0.40	24.00			
		1	13.00	4.32	0.30	16.85			
		1	14.60	4.00	0.75	43.80			
		Total						1140.81	cum
2	Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	4.00	4.00	0.10	1.60			
		1	5.50	4.00	0.10	2.20			
		2	16.00	4.52	0.10	14.46			
		1	13.00	4.45	0.10	5.79			
		1	6.40	3.75	0.10	2.40			
		3	10.00	4.00	0.10	12.00			
		3	24.00	4.12	0.10	29.66			
		2	20.00	4.10	0.10	16.40			
		1	13.30	3.90	0.10	5.19			
		1	17.40	4.24	0.10	7.38			
		1	13.00	4.13	0.10	5.37			
		1	15.00	4.00	0.10	6.00			
		1	13.00	4.32	0.10	5.62			
		1	14.60	4.00	0.10	5.84			
		Total						119.91	cum
TOTAL								2236262.00	

J.E
RWD
Amnaur

A.E
R.W.D
Amnaur

E.E
R.W.D
Marhaura