

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Chapra

DIVISION – R.W.D. works Division, Marhaura

Name of Work - Motrable of Road from AMNOR MADHORA PATH
TO DAKSHIN DHARMPUR TAK

Block - Marhaura

Estimated cost - Rs 303720.00

Year : 2020-21

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs - *E.C. P.W.D (W) Marhara*

2. Name of Block/Road - *Marhara*

A. For Road *Amra Marhara to Dakshin Pharampur tal.*

1. Damage Location/Chainage : *1250, 1630, 1780*

2. Damage Length : *60 M*

3. Nature of Damage : *cut in road*

4. Details of Restoration Works :

- Material being used in Restoration works : *Brick Bala, L/Sand*
- Equipments/Tools being used in Restoration works: *Tractor, Trally, roller etc.*
- Procedure taken up in Restoration works : *laying, spreading etc*
- Restored Length : *60 M*

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

- Material being used in Restoration works :
- Equipments/Tools being used in Restoration works:
- Procedure taken up in Restoration works :
- Restored Length :

C. Requirement of new CD/Bridge

- Name of Road :
- Location/Chainage :
- Type of CD work/Length required :

- Upload one Photograph of damaged portion if available
- Attach minimum two photograph (during restoration & after restoration) photographs should be Geotags and at least one photo be captured in selfie mode.

15/11/20
Signature of JE/AE/EE

16/12/20
Signature

(Name of Inspector)

प्रतिवेदन

कार्य का नाम :- आगौर मढ़ौरा पथ के दिशा ६१२१५२ तऽ

शीर्ष :- FDR

प्राक्कलित राशि:- 303720 =

प्रखण्ड का नाम:- Marhaura


जिला-सारण।


प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा०का०वि०, कार्य प्रमंडल मढ़ौरा के दिशा-निर्देशन में कुल रु० 303720 के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bats, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मढ़ौरा।


15/11/20


16.11.20

ABSTRACT OF COST

Name of Work - Motrable of Road from AMNOR MADHORA PATH TO DAKSHIN
DHARMPUR TAK

Block - Marhaura

S.L No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work	Rs 268779.00
B	Add 12 % GST on (A)	Rs 32253.00
C	Add 1 % L. Cess on (A)	Rs 2688.00
	Total Cost	Rs 303720.00

J.E
RWD
Marhaura
15/11/20

A.E
R.W.D
Marhaura
16/11/20

E.E
R.W.D
Marhaura
16/11/20
Say - 3,03,720=00

T/A for Rs. 3,03,720=00 (Rupees Three lac three thousand
seven hundred twenty) only.

SE
22-12-20
RWD (M) Circle
Chapra.

Name of work :-

Detailed Estimate

Motable of Road from AMNOR MADHORA PATH TO DAKSHIN DHARMPUR
TAK

		TAK							
SI No	Item	No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	25.00	2.90	1.00	72.50			
		1	20.00	3.00	0.45	27.00			
		1	15.00	3.10	0.79	36.74			
		Total						136.24	cum
2	Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	25.00	2.90	0.10	7.25			
		1	20.00	3.00	0.10	6.00			
		1	15.00	3.10	0.10	4.65			
		Total						17.90	cum
TOTAL									268779.00

J.E
RWD
Marhaura

A.E
R.W.D
Marhaura

E.E
R.W.D
Marhaura