

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road:- Champapur REO road to Barharwa Lakhansen	Length-4.10 Km
Estimated Cost- Rs.:- 1,75,400.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- चम्पापुर आर.ई.ओ.रोड से बड़हरना लखनसेन

प्रखंड का नाम :- दाका

पथ की लम्बाई :- 4.10 कि.मी.


शीर्ष :- 3054 F.D.R.

प्राक्कलित राशि :- ₹ 1,75,400.00

अनुरक्षण अवधि :- अन्दर

प्रस्तुत प्राक्कलन चम्पापुर आर.ई.ओ.रोड से बड़हरना लखनसेन में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो0...1,75,400.00 रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है। प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020
सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका



07/09/2020
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, दाका


**Rate for Restoration work of Road from Champapur REO road to Barharwa
Lakhansen for the year 2020-21 in Dhaka Block.**

Length:- 4.10 Km

SL N.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bats) CH:-3363 to 3370M $7.00 \times 5.50 + 6.50 / 2 \times 1.80 + 2.50 + 1.80 / 3 = 85.40 M^3$ Total = 85.40 M ³	M ³	85.40	2053.84	1,75,398.00
			Total=	Rs.	1,75,398.00
				Say Rs.	1,75,400.00


I-3-2020
JE.


07/09/2020
AE.


07/09/2020
EE.

bal Farto T.A.T/S is accorded for Rs. 1,75,400.00
(..... crore..... One lac..... Seventy Five thousand.....
..... Four hundred.....) only.


S.E. (R.W.D.)
works Circle
Motihari
29-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Champapur R.E.O Road to Barharwa
Lakhansen.

(A) For Road

1. Damage Location Chainage:-

2. Damage Length:- 7.0 m

3. Name of Damage:- Road cutting due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Brick bats
- (ii) Equipments Tools being used in restoration works:-
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 7.0 m.


24/12/2020
Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul