



मुख्यमंत्री ग्राम संपर्क योजना (NDB)

सड़क का नाम-रामपुर NH-107 से खुशरुपट्टी पथ निर्माण ।
पथ की लम्बाई :- 2.380 कि.मी.
प्राक्कलित राशि-173.012 (लाख)
5 वर्षीय अनुसंधान राशि-17.676 (लाख)
कार्य प्रारंभ की तिथि- 13-07-2020
कार्य समाप्ति की तिथि- 12-01-2022
एग्रीमेन्ट नं.-112 SED/MMGSY/2020-21

संवेदक	कार्यकारी एजेंसी
मनोज कुमार	कार्यपालक अभियंता,
भगवानपुर (तहसील)	ग्रामीण कार्य विभाग,
	कार्य प्रमंडल, मधेपुरा

Latitude: 25.889007
Longitude: 86.964009
Elevation: 36.93±8 m
Accuracy: 5.4 m
Time: 02-08-2021 15:42
Note: NH 107 se khushru Patte



Latitude: 25.892559
Longitude: 86.96463
Elevation: 45.94±15 m
Accuracy: 21.4 m
Time: 02-08-2021 18:15
Note: NH 107 se khushru Patte

Powered by NoteCam



409 26-06-2020-1600.4-1000/मानोज कुमार पिता श्री सुशान्त कुमार यादव का
बिहार BIHAR भगवानपुर थाना औरंगाबाद जिला बस्ती AF 744895

Agreement No-.....112.....SBD/2020-21

Date of Start - 13.07.2020

Date of Completion - 12.01.2022

0.0 % Below from S/R

Agreement

This agreement made theday of 2021, between Rural Works Department (Govt. of Bihar) Works Division Madhepura (Hereinafter called "the Employer") of the one part, and Manoj Kumar, At- Bhagwanpur, Baijnathpur, Dist- Saharsa (Bihar). (Hereinafter called "the contractor" of the other part) Whereas the employer is desirous that the Contractor execute the construction and five year maintenance of road under MMGSY (NDB), Package No.- MMGSY-NDB-BRRP-76-Madhepura; (Tender-ID-82257) (Bid ID-372227) for Construction & Five Year Maintenance Work of:-

Sl. No.	Name of Road	Length (Km)	Construction Cost (Rs)	Maintenance Cost (Rs)
1	Singheshwar Supaul Path mein Dr C K Prasad ke Ghar To Bhuna Tola Via Yadav Tola & Nai Tola	1.390	10825081.00	1009438.00
2	Road No. 19 Vishwakarma Mandir To Singhpur Sharma Tola (NDB)	1.965	12626688.00	1479359.00
3	Piprahi Jiwachpur Vishwabank Road Mahua Tola Chandeshwari Dealer House To Mushari Tola	2.285	16465520.00	1714801.00
4	Chitti Lakshminiya Path To Budh Tola	1.345	8568916.00	1002155.00
5	PWD Road Middle School Rahata To Bhawanipur	2.875	22440904.00	2121595.00
6	Rampur NH 107 To Khusropatti	2.380	17301358.00	1767637.00
7	Shiv Jee Das ke Ghar To Sharma Tola hote hue MBC Nahar (NDB)	0.690	4864262.00	516158.00
8	Navsrijit Madhya Vidyalay To Kajara Kamat Tola Hote hue MMGSY Path	0.750	6092791.00	562609.00
Total:-		13.680	99185524.00	10173752.00

(hereinafter called "the Works") and the employer has accepted the Bid by the Contractor for the execution and completion of such Works and the Routine maintenance of the work for 5 years of the contract price and remedying of any defects therein at a cost of Rupees 10,93,59,276.00 (Rupees Ten Crore Ninety Three lakh Fifty Nine Thousand Two Hundred Seventy Six Only)

11/7/2022

EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
MADHEPURA

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS :

1. In this agreement, words and expressions shall have the same meaning as are respectively assigned to them in the conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of the agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz :
 - i. Letter of Acceptance ;
 - ii. Notice to proceed with the works;
 - iii. Contractor's Bid;
 - iv. Contract Data;
 - v. Special Conditions of contract and general conditions of contract;
 - vi. Specification;
 - vii. Drawings;
 - viii. Bill of Quantities; and
 - ix. Any other document listed in the contract data as forming part of the contract.

In witness whereof the parties thereto have caused this agreement to be executed the day and year first before written.

The Common Seal of was

hereunto affixed in the presence of :

Signed, Sealed and Delivered by the said

Mamaj Kumar, Rajkumar Lakshy,

..... in presence of .

Binding Signature of Employer

Binding Signature of Contractor 11/17/2021

25/3/21
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION
MADHEPURA
28/3/21
28/3/2021

1 1st on A/c bill

Name of Work—
Situation of Work—
Agency by which work is executed—
Date of Measurement—
No. and date of agreement

(These four lines should be repeated at the commencement of the measurement relating to each work)

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
Name of work—	construction of				
Road from Rampur North to Panchpuri					
Agency—	Maharaj Kumar				
Agreement—	112 SBO/2020-21				
Date of start—	13/07/2020				
Date of completion—	12/01/2022				
	M.D— 15/04/21				

Details Measurement of 2x2 (Box culvert)					
Item (1)	Earthwork in excavation for foundation of structure				
Box culvert—	1x	6.00	3.50	0.70	= 14.70 M ³
Cut off wall—	2x	3.50	1.30	1.80	= 16.38 M ³
Return wall—	4x	3.32	3.41	1.80	= 81.51 M ³
					112.59 M ³
Item (2)	providing P.C.C (M ₂₀) in cut off wall				
	2x	2.50	0.300	1.50	= 2.25 M ³
Item (3)	providing P.C.C (M ₂₀) in cut off Box culvert and Return wall.				
Box culvert—	1x	6.00	2.50	0.15	= 2.25
Return wall—	4x	3.32	2.41	0.20	= 6.40

Continuation

8.65

ABSTRACT OF COST

Selling out Pillars

V.T.M.B.P.No (4)

7. 102 no (19) - 2.381m

Ans $14285.88/\text{ton} - 34000 = 0$

clearing and grubbing

Food Land

V.T.M.B.P.No-4

ferro (15) — 1.67 ha

Q. 49174.86/ke - 82122 = ∞

Earthwork in excavation

for synthesis of structure

N/T. M.B.P.No-(1)

$$iter\ no(1) = 112.59 m^2$$

Scanned with CamScanner

Continuation