



Abstract of cost for Restoration work of Ojha Tola to Mahuawa Road after flood 2020.

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	188.16	1546.00	290895.36
	(b) Rubbish	cum	47.04	742.00	34903.68
Total					325799.04
Add 1% labour Cess					3257.99
Add 12% GST					39095.88
Grand Total					368152.92
Say Rs					368150.00



J.E.


A.E.


S. S. F.

यह प्रमाणित किया जाता है कि कार्य अंश में पूर्ण हो चुका है और
आवक (कार्यपात्रक अभियंता वीनामही) के बीच में विवाद
254/28-1-21

Technically Approved for Rs 368150.00 (Rupees Three
lakh Sixty eight thousand One hundred Fifty) only


S. S. F.
R. W. S. F. (S) Circle
Bilaspur

**Detailed Estimate of Restoration work of road from Ojha Tola to Mahuawa Road
after flood 2020**

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.						
	from chainage in M	to chainage in M	length in M	width in M	depth in M		Quantity in CUM
1	60	340.00	280.00	2.8	0.3		235.20
							235.20
(a)	Brick Bats 80%						188.16
(b)	Local Sand/ Rubbish 20%						47.04

J.E.

[Signature]
05.04.021
A.E.

6'4, 21