

**GENERAL ABSTRACT OF COST FOR EMERGENT REPAIR FOR RESTORATION
OF TRAFFIC**

NAME OF ROAD : NH-2 TO AWARIYA ROAD KALI STHAN TO JAGJIWAN HIGH
SCHOOL MACHAKIYA
DISTRICT KAIMUR (BHABHUA)
BLOCK DURGAWATI
DIVISION MOHANIA
LENGTH OF ROAD (in Km) 0.010
CD STRUCTURES

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	RESTORATION COST	
1	Brick Bat Filling	1.377
2	Drainage	0.000
3	Information Board	0.050
	SUB TOTAL OF Restoration	1.427
	LABOUR CESS 1% of cost	0.014
	GST 12 % of cost	0.171
	SEIGNIORAGE FEE @ 10 % on Minor Mines	0.106
	TOTAL OF Restoration	1.719
Part B	Conigency 1 % on Restoration cost	0.017
	TOTAL COST OF PROJECT IN LACS =	1.736

JE
RWD

AE
RWD


EE
RWD

NAME OF Road:- NH-2 TO AWARIYA ROAD KALI STHAN TO JAGJIWAN HIGH SCHOOL MACHAKIYA

Sl. No.	SDB SL.NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1			Brick BAT Filling								
			Emergent Repair by Filling Brick Bats in Flood damaged Stretch of the Road for making it Motorableas per S/D of E/I								
			Road	cum	1	5.00	7.500	1.250	(av)	46.88	
			Flank	cum	1	20.00	2.000	1.000	(av)	40.00	
			Net Qty							86.88	1,37,705.00
2			Providing Sign Board							TOTAL =	1,37,705.00
									1	5000	5000
										D) SUB TOTAL OF Board =	5,000.00
										TOTAL COST OF PAVEMENT IN RS. (A+B+C+D+E+F)=	1,42,705.00



JE
RWD



AE
RWD

Inspection Report for Flood Damage Work

Date

1 Name of PIUs

Executive Engineer, RWD, Mohania.

2 Name of Block/Road

B/O - Dargawati.

A For Road

1 Damage Location/Chainage

0.095 to 0.125 km.

2 Damage Length

25 m

3 Nature of Damage

crust cutting - 5m, & flow cutting -

4 Details of Restoration Works

i Material being used in Restoration Works

Baric B of

ii Equipments/Tools being used in Restoration Works

Tractor, JCB

iii Procedure Taken up in Restoration Works

Depositing.

iv Restored Length

25 m.

B For Bridge

NA

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works

NA

i Material being used in Restoration Works

ii Equipments/Tools being used in Restoration Works

iii Procedure Taken up in Restoration Works

iv Restored Length

Signature of JE/AE/EE

20/11/24
JE

20/11/24
AA

20/11/21
Executive Engineer
Rural Works Department
Work Division, Mohania

Signature
Executive Engineer
(Name of Inspector)
Rural Works Department
Works Division Bhabhua