

योजना का नाम - शाहपुर से पांडेपुर पथ का मोटरबुल कार्य का प्राक्कलन वर्ष 2021-2022

मद - FDR प्रखण्ड - शाहपुर

कुल लम्बाई - 3.2 कि०मी०

प्राक्कलित राशी - 3.933 लाख

प्रतिवेदन

प्रस्तुत प्राक्कलन जिसकी अनुमानित लागत मात्र 3.933 लाख है, उपरोक्त कार्य हेतु तैयार किया गया है।

यह पथ NH-84 आरा बक्सर (उच्च विधालय शाहपुर के निकट) से प्रारम्भ होकर पांडेपुर तक जाती है। पथ के आधे कि०मी० पर एक उच्चस्तरीय पल अवस्थित है। जिसका पहुँच पथ अतिवृष्टि एवं बाढ़ के कारण क्षतिग्रस्त हो गया था। पहुँच पथ की सुरक्षा एवं पथांश भाग को मोटरबुल कराया गया है।

प्राक्कलन में प्रयुक्त दर वर्तमान अनुसूचित दर के अनुकूल है। कार्य हित में प्रशासनिक एवं तकनीकी स्वीकृति अपेक्षित है।

कनीय अभियंता

शाहपुर


24/11/2021
सहायक अभियंता

कार्य अभि०शाहपुर


24/11/21
कार्यपालक अभियंता

कार्य प्रमण्डल जगदीशपुर

GENERAL ABSTRACT OF COST

NAME OF ROAD : L035 SHAHPUR L027 TO PANDEPUR
 DISTRICT : BHOJPUR
 DIVISION : SAHPUR
 DIVISION : JAGDISHPUR

SL. No.	DESCRIPTION	AMOUNT(LAKHS)
PART -A	INITIAL RECTIFICATION INCLUDING SURFAC RENEWAL	
1	BRICKS BATS	3.198 3.478
		0.417 0.380
	ADD 12% GST ON RECTIFICATION COST	
	ADD 1 %LABOUR CESS ON RECTIFICATION COST	0.038 0.031
	TOTAL COST OF CONST. IN LACS	3.933 3.609
	TOTAL COST OF PROJECT IN LACS	3.933 3.609

JE
RWD

AE
RWD

EE
RWD

शहजपुर जिला
ग्राम पंचायत
9/5

कार्यपालक अधिकारी
ग्रामीण कार्य विभाग
कार्य प्रमंडल-डुमरांव

Technical, approved for Rs. 3.609 lacs (Rupees
Three lacs Sixty thousand nine
hundred) only.

Superintending Engineer
Rural Works Department
Works Circle - APO

FDR 2021-21

GENERAL ABSTRACT OF COST

Block :- SAHPUR

District :- BHOJPUR

Length :- 3.20 km

Name of Road :- L035 SHAHPUR L027 TO PANDEPUR

SL. No.	Item of Work	Amount
A 3.933	TOTAL COST OF CONSTRUCTION :	3.198 3.933
TOTAL	:	3.933 3.198 / 200

Junior Engineer

[Signature]
24/11/2024
Asstt. Engineer
Engineer

[Signature]
24/11/24
Executive

SE
RWD

technical, approved for Rs. 3.198 / per (Rupees)
Three lac one thousand
Eight hundred only.

Superintending Engineer,
Rural Works Department
Works Circle ARA

[Signature]
21/12

Name of the Road :-			L035 SHAHPUR L027 TO PANDEPUR		BLOCK		SAHPUR				
Length(Km):-			3.20 KM		DISTRICT		BHOJPUR				
SL No.	SDB SL. NO.	MORD Ref. No.	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1.	6.1	604	Brick Bats								
			Providing and laying of Brick bat obtained from chimney with machanical means with all spreading,grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge .								
			Net Qty. Required	Cum					185.4	1876.39	347882
			TOTAL COST OF PAVEMENT IN RS.=								347882

1725.11
319835.00
319835.00

24/11/2021

JE
RWD

AE
RWD

24/11/21
EE
RWD