



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

ESTIMATE FOR EMERGENT REPAIR FOR RESTORATION OF TRAFFIC

Bihar (बिहार) Map



F.D.R-2021-22. (Temporary)

Name of the Road :-

IKK- To Tetai Begla Road,

DISTRICT

:

Jehanabad

DIVISION

:

Jehanabad

BLOCK

:

Tetaniabad

TOTAL COST OF RESTORATION

:

1.24

Lac

Submitted By:

Executive Engineer

RWD WORKS DIVISION

Jehanabad

GENERAL ABSTRACT OF COST

NAME OF ROAD :

Irki to Tetai Bigha Road.

DISTRICT

Jehanabad

BLOCK

Jehanabad

DIVISION

Jehanabad

LENGTH OF ROAD (in Km)

CD STRUCTURES

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	RESTORATION COST	
1	Brick Bat Filling	1497.73
2	Hume Pipe 1000mm Dia	47.30 x 2323.22/21 = 5000.00
3	Sand Bag with Sand	11.424
	SUB TOTAL OF Restoration	1556.454
	LABOUR CESS 1% of cost	15.56454
	GST 12 % of cost	186.77448
	SEIGNIORAGE FEE @ 10 % on Minor Mines	155.6454
	TOTAL OF Restoration	1814.43882
	TOTAL COST OF PROJECT IN LACS =	1,81,44,388.82

70747

70947

709

85142

5602

85772

23/10/21
JE
RWD

23/10/21
AE
RWD

30.10.2021
EE
RWD

by
0.858

Technically approved for Rs. 0.858
Rupees. Zero Crore. Zero
Eighty Five thousand Eight hundred

Certified
S.E.
RWD (W) Circle
Jehanabad

Sd/-
S.E.
RWD (W) Circle
Jehanabad

B.F. Rs. 0.858 lacs.

provisionally Technically Sanctioned for Rs. 0.858 lakh
Rupees Zero Crore two lakh Eighty five
thousand four Eight Hundred - only.

~~Contd. of~~
S.E.
R.W.D. (M) Circle
Aurangabad

sd/
S.E.
R.W.D. (M) Circle
Aurangabad

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र।

1. निरीक्षी पदाधिकारी का नाम एवं पदनाम :- सी. व. पुष्प. प्रसाद, कार्यपत्र नि, गायन नि, बावन
2. निरीक्षण की तिथि :- 27/11/21
3. पथ का नाम (शीर्ष के साथ) :- Irki To Tetai Bigha Road
4. पथ की लम्बाई :- 3.00 K.m
5. कार्य प्रमंडल का नाम :- Jehanabad,
6. प्रखंड का नाम :- Jehanabad,
7. पथ की स्थिति :- (पूर्ण/On going) पूर्ण
8. पथ अनुरक्षण अवधि में है :- (Yes/No) नहीं
9. क्षतिग्रस्त भाग की लम्बाई :- 8.50 M.

10. क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी :-
(लम्बाई x उँचाई x गहराई)

$$(1) \quad 4.40 \times \left(\frac{2.50 + 3.00 + 2.80}{3} \right) \times \left(\frac{1.40 + 1.50 + 1.20}{3} \right) = 17.20 m^3$$

$$(2) \quad 4.10 \times \left(\frac{2.90 + 3.50 + 4.00}{3} \right) \times \left(\frac{2.50 + 1.90 + 1.80}{3} \right) = 30.10 m^3$$

11. Temporary Restoration में किस-किस :-
समाग्रियों का उपयोग किया गया है,
उसका विवरणी

$$\text{Total qty} = 47.30 m^3$$

Brick Bats.

12. अभियुक्ति :-

निरीक्षी पदाधिकारी का हस्ताक्षर
पदनाम सहित