

Date :- 21/11/2021

1. Name of PIUs :- Er Bijo Kumar

2. Name of Block/Road :- Rahw/ Toi To Sikanarpur

A. For Road

1. Damage Location/Chainage :- ch 0.40 to

2. Damage Length :- 35.20 mtr.

3. Nature of Damage :- crust and flank

4. Details of Restoration Works :-

i. Material being used in Restoration Works:- Brick Bats and G.S.B

ii. Equipments/ Tools being used in Restoration Works:- J.C.B, Roller and tractor.

iii. Procedure taken up in Restoration Works:- Departmental

iv. Restored Length:- 35.20 Mtr.

B. For Bridge

1. Damage Location/Chainage:-

2. Damage Length:-

3. Nature of Damage:-

4. Details of Restoration Works:-

i. Material being used in Restoration Work:-

ii. Equipments/ Tools being used in Restoration Works:-

iii. Procedure taken up in Restoration Works:-

iv. Restored Length:-

NA.

C. Requirement Of New CD/Bridge

i. Name of Road:-


ii. Location Chainage:-


iii. Type of CD Work/Length Required

Upload one photograph of damage portion if available

Attach minimum two photograph (during restoration & after restoration) photographs

Should be Geotags and at least one photo be captured in selfie mode


21.11.21
Signature of JE/AE/EE


21.11.21
Signature of verifying officer

पथ का नाम :- एल0-53-टी01 से सिकन्दरपुर

प्राक्कलित राशि :- 1.216 लाख

1.060 प्रतिवेदन 1.060

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 1.216 लाख है ग्रामीण कार्य विभाग, कार्य प्रमंडल, बिहारशरीफ अन्तर्गत रहुई प्रखंड में वर्ष-2021 में आयी बाढ़ के कारण क्षतिग्रस्त पथ के भरमति हेतु तैयार किया गया है।

उपर्युक्त पथ का निर्माण PMGSY योजनान्तर्गत किया गया है। वर्ष-2021 में पंचाने नदी में आई बाढ़ के कारण पथ के उपर से पानी का बहाव शुरू हो गया एवं पानी बहाव के कारण मिट्टी का कटाव हुआ एवं पथ 35.2 मीटर लंबाई में कटाव हो गया फलतः आवागमन बाधित हो गया एवं ग्रामीणों का अन्य जगह से संपर्क टुट गया।

विभागीय निर्देशानुसार कटे हुए भाग को ईट के टुकड़ों से भरने के उपरान्त आवागमन को चालू किया गया। पूर्ण रूप से कटे हुए भाग में ब्रिक बैट एवं GSB द्वारा पथ मरम्मत किया गया। प्रस्तुत प्राक्कलन में कराए गए कार्य में ब्रिक बैट एवं GSB का उपयोग किया गया। कार्य के उपरान्त स्थल निरीक्षण के क्रम में उच्चाधिकारियों द्वारा जाँच करा लिया गया है। प्राक्कलन में लिया गया दर अंचल कार्यालय द्वारा पत्रांक-458 दिनांक-19.06.2021 द्वारा अनुमोदित दर से लिया गया है। सिर्फ दुलाई का दर नहीं रहने के कारण इसे वर्तमान अनुसूचित दर पर तैयार किया गया है।

इस योजना की राशि FDR (3054) में भारित होगा। यथाशीघ्र प्राक्कलन की स्वीकृति अपेक्षित है।

Ksirell
29.10.21

कनीय अभियंता,
कार्य प्रशाखा, रहुई

29/10/21

सहायक अभियंता
कार्य अवर प्रमंडल, रहुई

29/10/21

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बिहारशरीफ

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD: Lohit P.O. to Salsandipore (VR 22)

DISTRICT: NALANDA

BLOCK: Rajauli

THESION: Biharchand

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	BRICK BATS	73344
2	CSB	1117.5
Total		121500.5
TOTAL COST IN LACS -		1.060
TOTAL COST OF PROJECT IN LACS -		1.060

Asin
29.10.21
RWD

29/11/21
RWD

gm
11/11/21
RWD

Sanctioned
Technically approved for Rs. 1,21,400.50
(Rupees one lac Twenty one thousand Four Hundred only)
Condition and direction laid down in attached technical notes with DPR is to be followed Strictly

5d -

S. E.

RWD

Work Circle Nalanda

certified copy

अधीक्षण आभयनना
ग्रामीण कार्य विभाग
कार्य अंचल (नालन्दा)

7.11/12/2021

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD : L053-T01 to Sikandarpur (VR22)

DISTRICT : NALANDA
BLOCK : Rahui
DIVISION : Biharsharif

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	BRICK BATS	111705 = 93344.00 108901.000
5	GSB	12687.548
	Total	121588.548
	TOTAL COST IN LACS =	1.060 1.216
	TOTAL COST OF PROJECT IN LACS =	1.060 1.216

Kein
29.10.21
JE
RWD

AE
29/10/21
AE
RWD

am
1/11/21
EE
RWD

Sanctioned
Technically approved for Rs. 1,24,400.00
(Rupees one lac Twenty Four
Thousand Four Hundred only)
Condition and direction laid down in attached
technical notes with DPR is be followed Strictly

Sd —
S. E.
RWD
Work Circle Nalanda

Certified copy
Amman
7/12/2021

अधोक्षण आभयन्ता
ग्रामीण कार्य विभाग
कार्य अंचल (नालन्दा)
9.6/12/2021

Estimate for Motorable of Road from LOSS

Name of Road L053-T01 to Sikandarpur (VR22)									
Sl. No.	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
SUB HEAD : EARTHWORK, BRICKS BATS, SAND FILLING									
1	Construction of Bricks Bats Supplying Brick bats with carriage at site including labour cess, GST and seigniorance fee (excluding over head and CP)								
		cum					46.334	1,168.20	54127.00
							54.056		63148.00
							46.334	506.138	23451.00
							54.056		27360.00
2	Carriage for Brick bats including labour cess & GST (excluding over head and CP)	No					49.114	321.00	15766.00
3	Supplying unskilled labour for Brick bats and laying 600 mm dia for spreading and levelling brick bats including labour cess & GST (excluding over head and CP)	No					57.299		18393.00
						AC) SUB TOTAL OF CRUST =		4,00,904.00	
								93344.00	
Sub Head : PAVEMENT LAYERS - GSB & WBM ITEMS									
4	Supplying GSB with carriage at site including labour cess, GST and seigniorance fee (excluding over head and CP)								
		Cum					7.588	1,672.16	12,687.55
						B) SUB TOTAL OF CRUST =		12,687.55	
						TOTAL COST OF PAVEMENT IN RS. (A+B+C+D+E+F)=		4,24,588.55	
								106031.55	

Kamal

29.10.21

JE

By 29/10/21

AE

11/11/21

EE

RWD