

30 31

## Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalgarh-2

2 Name of Block/Road : Baikunthpur / Samratigra Paschim Tol Se Samratigra  
Purab Tol Bandh Tale

### A For Road

1 Damage Location / Chainage : 0.00 m To 500 m

2 Damage Length : 156.00 m

3 Nature of Damage : Heavy Rain / Flood.

### 4 Details of Restoration Works:

i. Material being used in Restoration Works : Brick Bats

ii Equipments / Tools being used in Restoration Works : JCB, Tractor, Polo, Shovel, Rely

iii Procedure taken up in Restoration Works : YES.

iv Restored Length : 156.00 m

### B For Bridge

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

### 4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

Signature  
24/11/2020  
JE

Signature  
24.11.2020  
AE

Signature  
24/11/20  
EE

Signature  
24/11/21  
Executive Engineer  
R.W.D. W.D.  
Hathua



# ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR  
DISTRICT :- GOPALGANJ  
BLOCK :- BAIKUNTHPUR

Sanvaliya Paschim Tola Se Sanvaliya Purab Tola Bandh Tak

ESTIMATED COST - RS.

974600.00

SUBMITTED BY :-  
EXECUTIVE ENGINEER  
RWD (W) DIVISION  
GOPALGANJ-2

## Report

Name of Work :- Motorable work of Sanvaliya Paschim Tola Se  
Sanvaliya Purab Tola Bandh Tak

Estimated Cost :- 974600.00


Total length of Road :- 0.500 km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

  
10/11/2020  
J.E.

  
10.11.2020  
A.E.

  
24/11/20  
E.E.



**Detailed Estimate For Motorable Work in Road from Sanvaliya Paschim Tola Se  
Sanvaliya Purab Tola Bandh Tak damaged due to Heavy rain/flood for year 2020-  
2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in atches including all cost of bour & material with all complete job.								
CH - 00 M to 500 M	1	22.00	3.00	0.60	39.60	M3		
	1	17.00	1.00	1.50	25.50	M3		
	1	14.00	4.00	1.00	56.00	M3		
	1	20.00	1.50	1.20	36.00	M3		
	1	2.00	1.50	0.80	2.40	M3		
	1	3.00	1.00	0.60	1.80	M3		
	1	5.00	1.40	0.45	3.15	M3		
	1	14.00	1.00	1.50	21.00	M3		
	1	30.00	2.40	1.20	86.40	M3		
	1	15.00	2.50	3.00	112.50	M3		
	1	5.00	1.40	0.80	5.60	M3		
	1	9.00	0.70	1.20	7.56	M3		
		156.00						
Less for H.P.	0	1.23	1.23	0.95	0.00	M3		
					397.51	M3	2427.65	958338.20
								965015.15
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	4159.56	0.00
								958338.20
								965015.15
Add 1 % Contingency								7588.20
								9650.15
							Total	974665.30
							Say	974600.00

968426.20  
Say Rs 9.68426 L

*[Signature]*  
10/11/20  
J.E.

*[Signature]*  
10.11.2020  
A.E.

*[Signature]*  
24/11/20  
E.E.

*(Faint bleed-through from the reverse side of the page)*

3.2.2