

Government of Bihar

Under Flood Damage Repair

Estimate for Restoration of Traffic

DISTRICT :	West Champaran	BLOCK : Nautan
NAME OF ROAD :	TARCOLWA TO MANAGAPUR ROAD UNDER FLOOD DAMAGE REPAIR	

TOTL LENGHT		5.68	KMS	COST PER KM
COST OF PAYMENT (RS.)		2.673	Lacs	
NO. OF DD WORK		0.00	Nos	
COST OF CDS (RS)		0.00	Lacs	
TOTAL COST OF ROAD (RS)		2.673	Lacs	
MAINTANANCE COST (RS)		0.	Lacs	

SUBMITTED B

**The Executive Engineer,
Works Division, Bettiah**

TECHNICAL REPORT


Name of Road :- Tarcolwa to mangalpur
Name of Block :- Nautan
Name of Division :- R.W.D. Works Division Bettiah
Name of District :- West Champaran
Estimated Cost :- 2.673 Lacs
Restoration Length :- 100.0 M


This Estimate is prepared for Restoration of Tarcolwa to mangalpur
.....road under FDR as per the instruction of Secretary, Rural Works Department, Patna vide
ज्ञापक:- मु0अ0 -4 (मु0) विविध (कार्य) 23 -40 /16-2254 पटना, दिनांक 30.06.2020. Road remains effected
from flooded about 01 to 02 weeks and heavy amount of water passed through it.


Honorable Chief Minister/Secretary, Rural Works Department, Bihar, Patna/D.M., West Champaran
Bettiah/Concerned MP/MLA has instructed to maintain the traffic and movement of public etc. at the
earliest so that public of this area may get connected and for the same Departmental instruction has also
been issued to fill the gap made by flooded immediately.

The area surrounding is submerged in water and hence provision of Brown Bag
.....has been made to
maintain the road damage due to flood/heavy rainfall as per availability of material from available place by
tractor. Presently there is no Contractor is employed for Construction and Maintenance of this road hence
the work has been carried out Departmentally and due to this, provision of Contractor profit is not
mentioned in the estimate.

In view of above, it is requested to approve the estimate amounting to Rs. 2.673 Lacs please
Submitted for Technical Approval please.


31.9.20
Junior Engineer,
Nautan


Assistant Engineer,
Nautan


30.9.20
Executive Engineer
R.W.D.(W) Division, Bettiah

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक - मु0अ0-4 (मु0) विविध (कार्य)-23-40/16 - 2254

पटना, दिनांक 30/6/2020

प्रेषक,

पंकज कुमार पाल,
सचिव

सेवा में,

सभी कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
बिहार, पटना।

विषय-

संभावित अतिवृष्टि/बाढ़ के कारण क्षतिग्रस्त पथों के आपातकालीन मरम्मत के संबंध में।


महाराज,

उपर्युक्त विषय के संबंध में कहना है कि राज्य में मानसून अति सक्रिय है जिसके कारण बाढ़ प्रवण जिलों में पथों के क्षतिग्रस्त होने की संभावना है। अतः निदेश दिया जाता है कि वर्तमान मानसून के दौरान अतिवृष्टि/बाढ़ से क्षतिग्रस्त पथों को मोटरेबुल बनाने का कार्य तत्परता से प्राथमिकता में किया जाय जिससे कि पथों में यातायात कम से कम समय तक बाधित रहे। इस क्रम में यह भी निदेश है कि जिला प्रशासन के साथ वर्षा-अवधि के दौरान लगातार समन्वय रखी जाय एवं उनसे प्राप्त पथों की मरम्मत का कार्य प्राथमिकता में कराया जाय।

ऐसे पथ जिनकी अनुसूचना नीति के अन्तर्गत मरम्मत कार्य की निविदा प्रक्रिया में है उनको भी मोटरेबुल बनाए रखना विभाग का दायित्व है। इन्हें मोटरेबुल बनाए रखने में यदि प्राक्कलन में प्राक्धानित मदों का उपयोग किया जाना आवश्यक हो तो वैसे स्थिति में एकरारनामा करने के समय इन मदों की उतनी मात्रा परिमाण विपत्र में से घटा दिया जाए।

क्षेत्रीय पदाधिकारी वर्षा-अवधि के दौरान बिना जिलाधिकारी अथवा अधोहस्ताक्षरी की अनुमति के मुख्यालय नहीं छोड़ेंगे।


विश्वासभाजन


(पंकज कुमार पाल)
सचिव

पत्रांक- मु0अ0-4 (मु0) विविध (कार्य) 23-40/16 - 2254

पटना, दिनांक 30/06/2020

प्रतिलिपि:- सभी प्रमंडल आयुक्त/जिलाधिकारी/सभी मुख्य अभियंता/सभी अधीक्षण अभियंता,
ग्रामीण कार्य विभाग, बिहार, पटना को सूचनार्थ एवं आवश्यक कारवाई हेतु प्रेषित।


सचिव
30/06/2020

Estimate for Repair of Restoration of Road (Damaged by Flood-2020)
for Motorability in Tarcolwa to Managapur Road

Id : 2245

Lengh - 5.68 KM

Item No	Name of Item	Unit	No.	Lengh	Width	Height	Qty.	Rate	Amount
	Poviding & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design. Specification and direction of E/I	cum	As per Appendix I				1350.0M ³	1662.37	2,24,420.00
	Total Road Work								2,24,420.00
	Add GST @ 12%								26,930.00
	Add Labour Cess @ 1%								2244.00
	Add Seignarage Fee @ 10% of basic material rate								13,729.00
	Total Cost of Work								2,67,323.00


Say Rs. 2,67,300.00


30.5.20

Junior Engineer
Rural Works Department
Works Section Nautan


30/5/20

Assistant Engineer
Rural Works Department
Works Sub Division Nautan



30.5.20

Executive Engineer
Rural Works Department
Works Division Bettiah

**Estimate for Repair of Restoration of Road (Damaged by Flood-2020)
for Motorability in Tarcolwa to Managapur Road**

Measurement for surfacing the Breach with Brick Bat

Total only 135.0M³


Assistant Engineer
Rural Works Department
Works Sub Division Nautan

Aug 4
 30.9.20
 Executive Engineer
 Rural Works Department
 Works Division Bettiah