



## प्रतिवेदन

कार्य का नाम Restoration work of Road from Sirganeshdutt  
Nagar adarsh Kirana store to chauru mule path,  
पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में  
यातायात बंद करने हेतु आपातकालीन मरम्मत कार्य।

प्रस्तावित - Mr. Sharan,  
वित्तीय वर्ष 2020-2021  
आवकालेय राशि - Rs. 345100.00

प्रस्तुत प्रावकलन जिसकी प्रावकलित राशि 345100.00 है, Sirganeshdutt  
Nagar adarsh Kirana store Mr. Sharan, chauru mule path में यातायात बंद करने हेतु आपातकालीन मरम्मत के  
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटन के पत्रांक 2521 दिनांक 05.08.2020 द्वारा  
दिए गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Bridges Batts भरकर पथ को बंद  
करने का प्रावधान किया गया है। प्रावकलन वर्तमान बंद अनुसूचित दर पर तैयार किया गया है। इसकी  
समस्त स्वीकृति अपेक्षित है।

Shankar,  
12/12/2020  
अभियंता

San  
21/12/20  
सहायक अभियंता

San  
16.12.20  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रबंधन मजदूर  
पृष्ठ-1

# Inspection Report for Flood Damage Work

Date

- 1 Name of PFI's - E.E.R.W.D, MU2, EAST-1  
2 Name of Block/Road - Mushahari / Sirgansh But nagas  
adarsh kirana Store to chainpur. Mulch bekh  
A For Road

- 1 Damage Location/Chainage - Many place.  
2 Damage Length - 1 KM  
3 Nature of Damage  
4 Details of Restoration Works-

- i Material being used in Restoration Works-  
ii Equipments/Tools being used in Restoration Works-  
iii Procedure Taken up in Restoration Works-  
iv Restored Length

B. For Bridge

- 1 Damage Location/Chainage  
2 Damage Length  
3 Nature of Damage  
4 Details of Restoration Works-

- i Material being used in Restoration Works-  
ii Equipments/Tools being used in Restoration Works-  
iii Procedure Taken up in Restoration Works-  
iv Restored Length

*Signature*  
16/12/2020

Signature of JE/ AE/ EE

*Signature*

(Name of Inspector)

**NAME OF WORK:- Restoration work of Road from sirganeshdutt nagar  
adarsh kiraña store to chainpur mukh path tak**

Total Length :-

0.80

Restoration Length :- 0.4

**ABSTRACT OF COST**

| I.<br>D.                                                                                                                                                                                                               | Unit | Rates    | Quantity   | Amount            |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|------------|-------------------|
| <b>Providing and Laying of Brick Bats:</b><br>Placing tractor at loading point loading with front end loader<br>dumpong, turning for return trip exluding time for haulage and<br>return trip                          | Cum  | 1,768.60 | 168.62     | 298,221.00        |
| Providing, cutting and fixing of 62 mm to 75 mm dia bamboo<br>piles in size with making shoes and driving etc. complete job as<br>per specification and direction E/I.                                                 | Rm   | 49.40    | -          | -                 |
| Providing including labour for filling empty cement bag with<br>local sand, stiching the bag and placing including supply of sutali<br>etc. all complete as per approved design, specification and<br>direction of E/I | Nos  | 36.20    | -          | -                 |
| <b>Total Amount</b>                                                                                                                                                                                                    |      |          | <b>Rs.</b> | <b>298,221.00</b> |
| Add for GST @ 12%                                                                                                                                                                                                      |      |          | <b>Rs.</b> | <b>35,787.00</b>  |
| Add for Labour Cess @ 1%                                                                                                                                                                                               |      |          | <b>Rs.</b> | <b>2,982.00</b>   |
| Add for Seigniorage Fee                                                                                                                                                                                                |      |          | <b>Rs.</b> | <b>17,149.00</b>  |
| <b>Gross Total Amount</b>                                                                                                                                                                                              |      |          | <b>Rs.</b> | <b>354,139.00</b> |
| Say                                                                                                                                                                                                                    |      |          | <b>Rs.</b> | <b>354,100.00</b> |

*Signature*  
J.E. 12/12/2020

A.E. 12/12/20  
RWD, Sub-Division, mushahari

*Signature*  
16.12.20  
Executive Engineer  
RWD(W) Div. Muzaffarpur East 1

Technically Approved for Rs 3.54 Lacs (Rupees  
Three Lacs. fifty four thousand one hundred) only

*Signature*  
31.12.20  
Superintending Engineer  
B.W.D, WORKS CIRCLE

**MUZAFFARPUR**