## RURAL WORKS DEPARTMENT



## **GOVERNMENT OF BIHAR**

NAME OF ROAD:-

RESTORATION OF ROAD FROM FULKAHA BAZAR TO

**KOSHIKAPUR NEPAL BOARDER** 

**DIVISION:-**

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

**BLOCK:-**

**NARPATGANJ** 

**ESTIMATED COST** 

1107922.00

Inspection Report for flood damage work
1. Name of PIUs- RWD, Works dir. Forkesgang - Arana
1. Ivaille of 11032 Kings
2. Name of Block/Road-Narpatgenig / Restor! of Row from Fulkaha to' Koshkapur Nepal Bordor.  A. For Road
Koshkapur Nepal Bordor.
A.For Road
1. Damage Location/Chainage: 2. Damage Lengh: -35 M.
3. Nature of Damage : One of Culture due to 1- loos
i Material being used in Restoration - Local Sand, EC Bags, 132
i Material being used in Restoration - Local Sand, EC Bags, 152 miles Compressed ii Equipment Tools being used in Restoration works: Roller, Tractor, Je B, Pike Compressed iii Procedure taken up in Restoration works  Mathene etc.
ii Equipment Tools being used in Restoration works: Roller, Tractor, JeB, The Compression Fraction of Restoration works iv Restored Length  Restored Length  Restoration works  Here, Tractor, JeB, The Compression works in Restoration works in Restoration works in Restoration works
of Restoration
B. For Bridge
1.Damage Location/Chainage: 2. Damage Lengh
3. Nature of Damage
4. Details of Restoration :
i Material being used in Restoration ii Equipment/Tools being used in Restoration works:
iii Procedure taken up in Restoration works
iv Restored Length
Songe De look
CANAL TO ITAL
Signature of JE/AE/EE  Note: The signature of JE/AE/EE

(Name of Inspector)

## **Abstract of Cost**

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

## RESTORATION OF ROAD FROM FULKAHA BAZAR TO KOSHIKAPUR NEPAL BOARDER

**Block: FORBESGANJ** 

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	694.17	627.77	435778.09
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	630.00	75.86	47790.92
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	210.00	40.06	8412.72
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	9916.45	37.35	370346.96
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

3		Cum	47.25	1851.91	87502.92
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	7.50	5251.25	39384.34
	TOTAL AMOUNT =			989216.00	
	ADD 12.00 %GST=				118706.00
					1107922.00
	SAY TOTAL AMOUNT =				1107522.00

RWD WORKS DIV.

**FORBESGANJ** 

RWD WORKS DIV. FORBESGANJ

**RWD WORKS** DIV. FORBESGANJ

Technically Approved for RS-11, 07, 922=00 (Rubees Eleven Lats Seven thousand nine numbered thenty two) conty

Superintending Engineer Rural Works Department Works Circle, Kishanganj