

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM HANUMAN NAGAR
THAKURBARI TO MUSLIM TOLA VIA BHAGWATI
YADAV MILKI DUMARIYA MAHADALIT BASTI P.S.
MILKI DUMARIYA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

6365528.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD. Works dev. Forbesganj - Arania

2. Name of Block/Road- Narpatganj / Rest. of road from Hanuman

Nagar Thakur Bari to Muslim Tola via Bhagwati

A. For Road

Yadav Milk Dumariya Mahadalit Basti P.S. Milk Dumariya.

1. Damage Location/Chainage :

2. Damage Length

: - 43M + Flank damage

3. Nature of Damage

: Flank damage in D/S and Road cutting due to flood

4. Details of Restoration

i Material being used in Restoration EC, Bag, Local sand, B/Bats, Bamboo etc.

ii Equipment/Tools being used in Restoration works: JCB, Roller, Tractor, Pile Compactor

iii Procedure taken up in Restoration works

: as per specification and Process of Restoration work.

iv Restored Length

→ 43M + Flank Cutting.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A.

18/12/20

Signature of JE/AE/EE

18/12/20

18/12/20
EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

**RESTORATION OF ROAD FROM HANUMAN NAGAR THAKURBARI TO MUSLIM TOLA VIA BHAGWATI
YADAV MILKI DUMARIYA MAHADALIT BASTI P.S. MILKI DUMARIYA**

Block: NARPATGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1631.00	627.77	1023895.41
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	3540.00	75.86	268539.45
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1770.00	40.06	70907.22
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	110689.57	37.35	4133892.39
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	58.05	1851.91	107503.58
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	15.00	5251.25	78768.69
	TOTAL AMOUNT =				5683507.00
	ADD 12.00 %GST=				682021.00
	SAY TOTAL AMOUNT =				6365528.00

18/12/2020
JE
RWD WORKS
DIV.
FORBESGANJ

AE
20/12/2020
RWD WORKS DIV. FORBESGANJ

RWD WORKS
DIV. FORBESGANJ

Technically approved for Rs. 63,65,528.00 (Rupees sixty three
lacs sixty five thousand five hundred twenty eight) only

24/12/20
Superintending Engineer
Rural Works Department
Works Circle, Kishanganj