

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

RESTORATION OF ROAD FROM PHULKAHA BAZAR
NAME OF ROAD:- TO AMRORI VIA KUM KUM DEVI +2 SCHOOL SIDE OF
JAGDISH YADAV HOUSE CUTTING-1

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

1556061.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD, works div. Forbesganj

2. Name of Block/Road- Narpatganj / Restoration of Road from Phulkaha

A. For Road Bazar to amrawri via Kumkum Devi + 2 School Side of Jagdish Yadav House

1. Damage Location/Chainage : along the road

2. Damage Length : 30m \pm 30m

3. Nature of Damage : washed out the Road and flanks damage due to flood

4. Details of Restoration :

i Material being used in Restoration local sand, sand bag, Bl/Bate, and Bamboo piling H.P.

ii Equipment/Tools being used in Restoration works: Tractor, JSB, Pile Compreser Machine, Roller

iii Procedure taken up in Restoration works : as per Process in filling Compacting

iv Restored Length : as per Specification of Restoration
30m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

R.A.

Signature of JE/AE/EE

Signature of JE/AE/EE

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

FALSE

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	763.00	627.77	478989.70
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1104.00	75.86	83747.90
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	276.00	40.06	11056.72
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	15936.25	37.35	595166.55
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				


		Cum	55.20	1851.91	102225.63
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	22.50	5251.25	118153.03
	TOTAL AMOUNT =				1389340.00
	ADD 12.00 %GST=				166721.00
	SAY TOTAL AMOUNT =				1556061.00

JE
RWD WORKS
DIV.
FORBESGANJ

AE
RWD WORKS DIV. FORBESGANJ

E.E.
RWD WORKS
DIV. FORBESGANJ

Technically approved for Rs 15,56,061.00 (Rupees Fifteen Lacs Fifty Six thousand Sixty one) only


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj