

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM PHATEHPUR BALUA
HATT PMGSY ROAD TO NAVAL JHA HOUSE TO
KRIPANAND HOUSE

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

731354.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD, works div. Forbesganj - Araria.

2. Name of Block/Road- Narpalganj / Restoⁿ of Road from Phatehpur Balua Hatt.
to Naval Jha House to Kripanand Thakur House.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : — 15 M + 250 M flank with Road washout.

3. Nature of Damage : Road cut due to flood water

4. Details of Restoration :

i Material being used in Restoration Local Sand Ed Bag, H.P. and B/Bats etc

ii Equipment/Tools being used in Restoration works: Tractor, JCB, Roller loder etc

iii Procedure taken up in Restoration works

iv Restored Length : as per specification and Prices
of Restoration works

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

— 265 M.

N.A.

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

**RESTORATION OF ROAD FROM PHATEHPUR BALUA HATT PMGSY ROAD TO NAVAL JHA HOUSE TO
KRIPANAND HOUSE**

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	304.83	627.77	191360.47
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	0.00	75.86	0.00
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	0.00	40.06	0.00
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	0.00	37.35	0.00
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	225.75	1870.43	422250.19

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	7.50	5251.25	39384.34
	TOTAL AMOUNT =				652995.00
	ADD 12.00 %GST=				78359.00
	SAY TOTAL AMOUNT =				731354.00

[Signature]
20/12/2020
JE
RWD WORKS
DIV.
FORBESGANJ

AE *[Signature]*
20/12/2020

RWD WORKS DIV. FORBESGANJ

[Signature]
RWD WORKS
DIV. FORBESGANJ

Technically approved for Rs. 7,31,354.00 (Rupees Seven Lacs thirty one thousand three hundred fifty four) only

[Signature]
20/12/2020

Superintending Engineer
Rural Works Department,
Works Circle, Kishanganj