

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM BATHNAHA BIRPUR  
ROAD 3.5 MILE CHOWK TO BHORHAR MAHADALIT  
TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

### ESTIMATED COST

1258833.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD works div. Forbesganj Araria

2. Name of Block/Road- Narpatganj / Rest. H. Road From Bathnaha Berpin  
Road 3.5 mile chowk. to Bhorhar Mahadalit Tola.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 29M+

3. Nature of Damage :

4. Details of Restoration :

ROAD cutting due to flood water high current.

i Material being used in Restoration Local sand, EC, bag, B/Bats H.P. Bamboo etc.

ii Equipment/Tools being used in Restoration works: JCB, Roller, Pile Compressor Machine

iii Procedure taken up in Restoration works : Tractor etc.

iv Restored Length : as per specifications and Process of Restoration work.

29M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A.

Signature of JE/AE/EE

Signature

(Name of Inspector)

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2020 in ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM BATHNAHA BIRPUR ROAD 3.5 MILE CHOWK TO BHORHAR  
MAHADALIT TOLA**

**Block:** NARPATGANJ

**District:** ARARIA

**Divison :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	711.33	627.77	446554.84
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	495.00	75.86	37550.01
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	165.00	40.06	6609.99
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	13984.74	37.35	522284.17
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	31.56	1851.91	58446.39

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	10.00	5251.25	52512.46
	TOTAL AMOUNT =				1123958.00
	ADD 12.00 %GST=				134875.00
	SAY TOTAL AMOUNT =				1258833.00

  
JE  
RWD WORKS  
DIV.  
FORBESGANJ

AE   
RWD WORKS DIV. FORBESGANJ

  
E.E.  
RWD WORKS  
DIV. FORBESGANJ

Technically approved for Rs. 12,58,833.00 (Rupees Twelve  
lacs fifty eight thousand eight hundred thirty three) only

  
Superintending Engineer

Superintending Engineer  
Rural Works Department  
Works Circle, Kishanganj