

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM HIRDAY RISHIDEV
NEAR PAN SHOP TO HOUSE OF MAHESH RISHIDEV

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

1968940.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- Narpatganj/Rest: of Road from Hirday Rishidev Near
Pan Shop to house of Mahesh Rishidev.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 50M.

3. Nature of Damage : Road cutting due to high Flood water current.

4. Details of Restoration :

i Material being used in Restoration Local Sand, EG bag, Bamboo, HP. etc. Brick/Bats.

ii Equipment/Tools being used in Restoration works: JCB, Tractor, Pile Compactor, motor etc
as per specification and Process of Restoration.

iii Procedure taken up in Restoration works

iv Restored Length

: 50M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A.

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM HIRDAY RISHIDEV NEAR PAN SHOP TO HOUSE OF MAHESH RISHIDEV

Block: NARPATGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1178.33	627.77	739724.15
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1806.00	75.86	137000.64
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	258.00	40.06	10335.63
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	11235.47	37.35	419607.85
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	116.10	1851.91	215007.17
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (IIPC), all complete job.				
		meter	45.00	5251.25	236306.06
	TOTAL AMOUNT =				1757982.00
	ADD 12.00 %GST=				210958.00
	SAY TOTAL AMOUNT =				1968940.00


18/12/2020

JE
RWD WORKS
DIV.
FORBESGANJ


20/12/2020

AE
RWD WORKS DIV. FORBESGANJ


E.E.

RWD WORKS
DIV. FORBESGANJ

Technically approved for Rs- 19,68,940.00 (Rupees Nineteen
Lacs Sixty eight thousand Nine hundred forty) only


20/12/20

Superintending Engineer
Rural Works Department
Works Circle, Kishanganj