

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM BAIJNATH JHA TOLA
POBDAHA TO BATHNAHA BIRPUR ROAD CUTTING-1

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

668115.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD- works div. Forbesganj - Araria

2. Name of Block/Road- Nampalgaon / Restor. of Road from Baijnath Jha Tola Pordaha to Balhaha Birpur Road

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 18 M

3. Nature of Damage : Road cutting due to flooded water.

4. Details of Restoration :

i Material being used in Restoration Local sand, EC bag, bamboo, Brick/Bats, H.P.

ii Equipment/Tools being used in Restoration works: JCB, Tractor, Roller, Pile compressor, etc.

iii Procedure taken up in Restoration works

iv Restored Length : as per specification of Process of Restoration.

→ 18 M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A.


Signature of JE/AE/EE


Signature of JE/AE/EE


Signature


Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

**RESTORATION OF ROAD FROM BAIJNATH JHA TOLA PORDAHA TO BATHNAHA BIRPUR ROAD
CUTTING-1**

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	363.60	627.77	228257.74
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	378.00	75.86	28674.55
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	108.00	40.06	4326.54
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	6366.24	37.35	237758.00
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	24.30	1851.91	45001.50


6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	10.00	5251.25	52512.46
	TOTAL AMOUNT =				596531.00
	ADD 12.00 %GST=				71584.00
	SAY TOTAL AMOUNT =				668115.00


JE
RWD WORKS
DIV.
FORBESGANI


AE
RWD WORKS DIV. FORBESGANI


E
RWD WORKS
DIV. FORBESGANI

668,115 = Rs (Rupees)
Technically approved for Rs Six Lacs Sixty eight thousand and one hundred fifteen only


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj