

प्रतिवेदन

कार्य का नाम: रत रत पी आमा नगर पथ पर लोचनपथ दे कामा
सरा सीजन विल पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- कुर्हानी
वित्तीय वर्ष - 2020-2021
प्राक्कलित राशि - Rs. 3.058 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 3.058 लाख है, हजार प्रमंडल मुजफ्फर
पुर्वी-1, प्रखंड- कुर्हानी में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है।

गोपाल
कनीय अभियंता

K. Anil
10/11/2020
सहायक अभियंता,
R.W.D. Works Sub Division
Kurhani

22-12-20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फर
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
2 Name of Block/Road- kudhani / MNP Agg Nagar path purshottampur
to Agg Nagar Harigan tola.

A For Road

- 1 Damage Location/Chainage At Many palaces
2 Damage Length 125.50 m
3 Nature of Damage Complete road blocked due to breached of
road due to flood water
4 Details of Restoration Works-
i Material being used in Restoration Works- Bricks bats
ii Equipments/Tools being used in Restoration Works- Static roller, tractor
iii Procedure Taken up in Restoration Works- Immediate repair for traffic
restoration
iv Restored Length 125.50 m

B For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

Scanned with CamScanner



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		MNP Aganagar path pursottampur to aga nagar harijan tola	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Kurhani	
TOTAL LENGTH OF ROAD		:	1.376 KM
CONSTRUCTION COST		:	3.058 Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

GENERAL ABSTRACT

Name of the Road :-

District

Block

Division

MNP Aganagar path pursottampur to aga nagar harijan tola
Muzaffarpur

Kurhani


Muzaffarpur East-1

Length of Road (in Km)

1.376 KM


Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal / Brick Bat	2.880
2	Sand Filling	0.000
3	Sand bag	0.000
4	1000 mm dia hume pipe	0.177
	GRAND SUB TOTAL	3.058
TOTAL COST OF PROJECT IN LACS =		3.058


JE
RWD


AE
RWD


EE
RWD

Technically Approved for Rs 3.058 Lacs (Rupees
Three Lacs five thousand Eight hundred / only


Superintending Engineer
B.W.D, WORKS CIRCLE
MUZAFFARPUR

Comparative Statement
Name of Road :- MNP Aganagar path purstampur to Aga Nagar Harjan tola

S.N	Item of Work	Unit	Quantity (in cum)	Rate Quoted By Hira Infrastructure Bhagwampur Muzaffarpur		Rate Quoted By Mandoj Kumar Bhagwampur, Nundar, Muzaffarpur		Rate Quoted By Pihu Construction Dhummagar, Dharfari, Deoria Kothi, Muzaffarpur	
				Rate (in Rs.)	Amount (in Rs.)	Rate (in Rs.)	Amount (in Rs.)	Rate (in Rs.)	Amount (in Rs.)
1	Providing and Laying of Brick Bats Labour for cosolisation in Jhama metal by Road Roller in proper grade camber and super elevation by and wet rolling including costs of running charge of roller driver and khalasi making and maintaining diversion light barrier -do-do-danger singal etc including cost of labour and materials all complete.	3	4	5	6	7	8	9	10
2	Providing and laying reinforced cement concrete pipe 1000mm dia as per designe single row.	m	5.00	3544.71	17723.55	3559.71	17798.55	3554.71	17773.55
Total Amount				L1	305746.00	L2	306104.46	L3	306079.46
Say									

C/S Prepared by

K. Awlota
30/08/20
A.E., R.W.D.
Kudahi

C/S Recommended by

AB
16/11
D.A.O.

C/S Recommended by

AB
16/11
E.E.

Work in

Lowest rate quoted by Hira Infrastructure and Amount is Rs. 305746/-
(As three bids are thousand seven hundred forty six) only hence this
quotation

Approved

AB
18/12/20

Superintending Engineer
RWD, Works Circle
Muzaffarpur

Name of the Road :- MNP Aganagar path pursottampur to aga nagar harijan tola							
Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal / Brick Bat				
			Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do - danger signal etc. Including cost of labour and Materials .all complete				
			Appendix - I				
			Cum	141.7			
				Total	141.65	2033.34	288026.70
		SOR ITEM 9.3	Providing and laying reinforced cement concrete pipe 1000mm dia as per designe single row.	m	5.00	3544.71	17723.55
2		11.20	Sand Filling				
			Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II				
			Cum	0.000			
				Total	0.00	454.53	0.00
Total Cost :-						305750.25	

305750.2531

[Signature]
10/11/20
Sr

K. Ravuluri
10/11/20
A.E., RWD
K. Ravuluri

[Signature]
22.11.20
Executive Engineer
R.W.D. Works Division
Muzaffarpur East-1