

कार्य का नाम:- शम्भुपुर लक्ष्मिनी से चरपुर सहायक लिट्टी रोड

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- कुर्हानी
वित्तीय वर्ष - 2020-21
प्राक्कलित राशि - Rs. 2.299 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि Rs. 2.299 लाख कार्य प्रारम्भ मुजफ्फरपुर पूर्वी-1, प्रखंड- कुर्हानी में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

[Signature]
कनीय अभियंता

K. Anshu
10/11/20
सहायक अभियंता,
A.E.
R.W.D. Works Sub Division
Kurhani

[Signature]
22.12.20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फरपुर
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER, R&D (W) DIV. Muzaffarpur East-1
2 Name of Block/Road- Kudhami/Rampur to Haripur Mahabadi tola.

A For Road

- 1 Damage Location/Chainage At Many palaces.
2 Damage Length 21M.
3 Nature of Damage Complete road blocked due to breached of road due to flood water.
4 Details of Restoration Works-
i Material being used in Restoration Works- Bricks bats
ii Equipments/Tools being used in Restoration Works- Statics, rollers, tractor of road due to flood water.
iii Procedure Taken up in Restoration Works- Immediate repairs for traffic restoration.
iv Restored Length 21M

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-
i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

Signature of JE/ AE/ EE

Signature
(Name of Inspector)

Scanned with CamScanner



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-	Rampur Ladwaria to Harpur Mahadalit Tola		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Kurhani		
TOTAL LENGTH OF ROAD	:	3.200	KM
CONSTRUCTION COST	:	2.299	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

GENERAL ABSTRACT

of the Road :-
District
Block
Division

Rampur Ladwaria to Harpur Mahadalit Tola
Muzaffarpur
Kurhani
Muzaffarpur East-1


Length of Road (in Km)


3.2 KM

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal / Brick Bat	2.299
2	Sand Filling	0.000
3	Sand bag	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	2.299
TOTAL COST OF PROJECT IN LACS =		2.299



10/11/2020

JE
RWD



10/11/20
AE
RWD


22-12-20
EE
RWD

Technically Approved for Rs 2.299 Lacs (Rupees
Two Lacs twenty nine thousand nine hundred) only


Superintending Engineer
B.W.D, WORKS CIRCLE
MUZAFFARPUR

certified copy


23/12/20
Superintending Engineer
B.W.D, WORKS CIRCLE
MUZAFFARPUR

Name of the Road :- Rampur Ladwaria to Harpur Mahadalit Tola						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE
						AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal / Brick Bat Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller driver and khalasi making and maintaining diversion light barrier - do - do - danger signal etc. Including cost of labour and Materials .all complete			
			Appendix - I	Cum	113.0	
				Total	113.05	2033.34
						229863.85
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9			
			Appendix - II	Cum	0.000	
				Total	0.00	454.53
						0.00
Total Cost :-						229863.85

[Signature]
10/11/20
I.R

K Anubhai
10/11/20
A.E

[Signature]
Executive Engineer
R.W.D. Works Division
Muzaffarpur East-I

Comparative Statement

Name of Road :- Rampur Ladwariya to Harpur Mahadait tola

S.N	Item of Work	Unit	Quantity (in cum)	Rate Quoted By Hira Infrastructure Bhagwanpur Muzaffarpur		Rate Quoted By Manoj Kumar Bhagwanpur, Nurfar, Muzaffarpur		Rate Quoted By Pihu Construction Dhumagar, Dharti, Deoria Kothi, Muzaffarpur	
				Rate (in Rs.)	Amount (in Rs.)	Rate (in Rs.)	Amount (in Rs.)	Rate (in Rs.)	Amount (in Rs.)
1	Providing and Laying of Brick Bats.	3	4	5	6	7	8	9	10
1	Labour for cosolisation in Jhama metal by Road Roller in proper grade camber and super elevation by and wet rolling including cos of running charge of roller driver and khalasi making and maintaining deviation light barrier -do-do-danger singal etc including cost of labour and materials all complete.	Cum	113.05	2030.30	229525.42	2036.30	230203.72	2039.30	230542.87
Total Amount				L1	229525.42	L2	230203.72	L3	230542.87
Say					229525.00		230204.00		230543.00

C/S Prepared by

C/S Recommended by

C/S Recommended by

D.A.O.

E.E.

K. Ananta
30/08/20
A.E., R.W.D.
Muzaffarpur

3908/2020
5/12/20
K. Ananta

Approved

Superintending Engineer

RWD, Works Circle

Muzaffarpur

lowest rate quoted by Hira Infrastructure and amount is Rs. 229525.00 (i.e. two lacs twenty nine thousand five hundred twenty five only) hence quotation