

प्रतिवेदन

कार्य का नाम: मुजफ्फरपुर मस्टा पत्रांक ५२ से दुबलिया

विशुद्ध पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।


प्रखण्ड- दुबली
वित्तीय वर्ष - २०२०-२०२१
प्राक्कलित राशि - Rs. २.२५४ लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि २.२५४ लाख है, कार्य प्रमुख मुजफ्फरपुर प्रखण्ड- दुबली में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।


कनीय अभियंता

K. Anil
10/11/2020
Assistant Engineer
R.W.D. Works Sub-Division
Kurhani, Muzaffarpur (Bihar)


22-12-20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुज०
पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER R&D (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Kudhani / Muzaffarpur Mahua path par pul to Subdhiya vishampur Kudhani


A For Road

- 1 Damage Location/Chainage At Many places.
- 2 Damage Length 327.90M
- 3 Nature of Damage Complete road blocked due to breached of road due to flood water.
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Bricks bats
 - ii Equipments/Tools being used in Restoration Works- Statics, rollers, trucks as road due to flood water
 - iii Procedure Taken up in Restoration Works- Immediate repairs for traffic restoration
 - iv Restored Length 327.90M

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

Signature of JE/ AE/ EE


Signature
(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :- Muzaffarpur Mahua path par pul to subdhiya vishanpur

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Kurhani

TOTAL LENGTH OF ROAD	:	1.270	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	7.248	Lac
-------------------	---	-------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

GENERAL ABSTRACT

Name of the Road :-

Muzaffarpur Mahua path par pul to subdhiya vishanpur

District

Muzaffarpur

Block

Kurhani

Division

Muzaffarpur East-1


Length of Road (in Km)


1.27 KM

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal / Brick Bat	7.248
2	Sand Filling	0.000
3	Sand bag	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	7.248
TOTAL COST OF PROJECT IN LACS =		7.248



10/11/2020


JE
RWD


10/11/2020
Assistant Engineer
R.W.D. Works Sub-Division
Kurhani, Muzaffarpur (Bihar)


22/12/20
EE
RWD

Technically approved for Rs 7.248 (Rupees Seven Lacs twenty four thousand eight hundred) only.


22/12/20
Superintending Engineer
R.W.D., WORKS CIRCLE
MUZAFFARPUR


31/12/20

Name of the Road :- Muzaffarpur Mahua path par pul to subdhiya vishanpur						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE
						AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal / Brick Bat Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and Khalasi making and maintaining diversion light barrier - do - do - danger signal etc. Including cost of labour and Materials .all complete Appendix - I			
				Cum	356.4	
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9 Appendix - II			
				Cum	0.000	
				Total	0.00	454.53
						0.00
Total Cost :-						724766.37


10/11/20

Assistant Engineer
R.W.D. Works Sub-Division
Kuhani, Muzaffarpur (Bihar)


23.11.20

Executive Engineer
R.W.D. Works Division
Muzaffarpur East-1

Comparative Statement

Name of Road :- Muzaffarpur Mathua path per put to Subhaya vishanpur

S.N	Item of Work	Unit	Quantity (in cum)	Rate Quoted By Raghvendra Kumar Hanuman Nagar, LIG, Kankarbagh, Patna		Rate Quoted By M/s Suranjan Kumar Baldeo Sahay Road Kadam Kuan Patna		Rate Quoted By Akash Kumar Bahadurpur Housing Colony, Kankarbagh Patna	
				Rate (in Rs.)	Amount (in Rs.)	Rate (in Rs.)	Amount (in Rs.)	Rate (in Rs.)	Amount (in Rs.)
1	Providing and Laying of Brick Bats: Labour for consolidation in dhama metal by Road Roller in proper grade camber and super elevation by and wet rolling including costs of running charge of roller driver and khilasi making and maintaining diversion light barrier -do-do-danger singal etc. including cost of labour and materials all complete.	Cum	356.44	2026.31	722257.94	2038.45	726585.12	2037.11	726107.49
Total Amount				L1	722258.00	L2	726585.00	L3	726107.00
Say									

C/S Prepared by

C/S Recommended by

C/S Recommended by

K. Anil K
30/08/20
A.E., R.W.D,
Kudhwa

D.A.O.

E.E.

Approved

Superintending Engineer
RWD, Works Circle
Muzaffarpur

Lowest rate quoted by Raghvendra Kumar and amount is 722258 =
(19. Seven lakh twenty two thousand two hundred and 58 only Hence
rate quotation