

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Chapra

DIVISION – R.W.D. works Division, Chapra-2

Name of Work - Restoration/Mottrable of Road from Isuapur. to
Tedha path (PMGSY) 1.92 KM

Block - Isuapur

Estimated cost - Rs 291442.00

Year : 2020-21

Inspection Report for flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- I Sagar - Restoration/ Motorable of Road from
Tonapur to Tasha Palu (PMUY-II) 1.92 km

A. For Road

1. Damage Location/Chainage : 115 to 235 m (near Thang)

2. Damage Length : 120 m

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works: Tractor, Road Roller

iii Procedure taken up in Restoration works :

iv Restored Length : 120 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

[Signature]
23/12/20
Signature of JE/AF/EE

[Signature]
23/12/2020
Signature
VIND D KUMAR
(Name of Inspector)
Executive Engineer
W.D. (W) Division Chabra-1

प्रतिवेदन

कार्य का नाम :- Restoration/Motable of Road from Isuapur to Tedha palh
शीर्ष :- FDR

प्राक्कलित राशि:- 2,91,442 = 00

प्रखण्ड का नाम:- Isuapur

जिला-सारण।

प्रस्तुत प्राक्कलन शीर्ष PMGSY/MMGSY/GTSNY/NABARD/MR-3054 अर्तगत निर्मित/निर्माणाधीन पथ के गत महीने में इस जिला में आये बाढ़/अतिवृष्टि के कारण क्षतिग्रस्त हुए पथों को चलने लायक (Motarable) बनाने हेतु विभागीय दिशा-निर्देशानुसार कार्यपालक अभियंता, ग्रा0का0वि0, कार्य प्रमंडल Chapra-2 के दिशा-निर्देशन में कुल रु02,91,442 = 00 के लिए तैयार किया गया है।

आवश्यकतानुसार तत्काल प्रभाव से पथों को चलने लायक बनाने हेतु प्राक्कलन में Bricks Bais, Sand Bag, Hume-Pipe इत्यादी का प्रावधान आवश्यक लम्बाई, चौड़ाई एवं मोटाई में प्राक्कलन के अनुसार प्रावधान किया गया है।

योजना एवं कार्य की महत्ता के साथ-साथ जनहित के लिए अतिउपयोगी प्राक्कलन को कार्यहित में स्वीकृति हेतु प्रस्तुत किया जा रहा है।


22/12/20


23/12/20
AC


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, Chapra-2।


ABSTRACT OF COST

Name of Work - Restoration/Mottrable of Road from Isuapur to Tedha path

Block - Isuapur

S.L No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work	Rs 257913.00
B	Add 12 % GST on (A)	Rs 30950.00
C	Add 1 % L. Cess on (A)	Rs 2579.00
	Total Cost	Rs 291442.00


R.W.D.
Chapra-2


A.E.
R.W.D.
Chapra-2


E.E.
R.W.D.
Chapra-2

T/A for Rs 291442 = 2 (Two lakh ninety one thousand four hundred and two rupees)
28-12-20


Detailed Estimate

ie of work :-

Restoration/Motrable of Road from Isuapur to Tedha path

SI No	Item	No	Length	Width	Avg.H/D	Qty	Unit	Rate	Amount
1	Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	120.00	3.75	0.28 0.245	123.75			
						Total	123.75	cum	1909.87
									236346.00
2	Fillling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	120.00	3.75	0.10	45.00			
						Total	45.00	cum	479.27
									21567.00
TOTAL									257913.00


R.W.D.
Chapra-2


A.E.
R.W.D.
Chapra-2


E.E.
R.W.D.
Chapra-2