

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalganj - 2

2 Name of Block/Road : Baidkuthpur / Rajulokpur Mulya Widyalaya Se  
Ganesh Pipra Pat.

A For Road

1 Damage Location / Chainage : 0.00 m to 700.00 m.

2 Damage Length : 151.00

3 Nature of Damage : Heavy Rain / Flood.

4 Details of Restoration Works:

i. Material being used in Restoration Works : Brick Batu

ii Equipments / Tools being used in Restoration Works : TCB, Tractor, Trolly, Bolah, Shovel etc.

iii Procedure taken up in Restoration Works : Yes

iv Restored Length : 151.00 m

B For Bridge

N/A.

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

*[Signature]*  
24/11/2020  
JE

*[Signature]*  
24-11-2020  
AE

*[Signature]*  
24/11/20  
EE

*[Signature]*  
Signature  
24/11/21  
(Executive Engineer)  
R.W.D. W.D.  
Hathua



# ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR  
DISTRICT :- GOPALGANJ  
BLOCK :- BAIKUNTHPUR

Fajulahpur Uchya Vidhyalay Se Gamahari Pipra Tak

ESTIMATED COST - RS. 1456800.00

**SUBMITTED BY :-**  
**EXECUTIVE ENGINEER**  
**RWD (W) DIVISION**  
**GOPALGANJ-2**

## Report

Name of Work :- Motorable work of Fajulahpur Uchya Vidhyalay  
Se Gamahari Pipra Tak

Estimated Cost :- 1456800.00


Total length of Road :- km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

  
23/10/2020  
J.E.

  
25.10.2020  
A.E.

  
25/10/20  
E.E.



**Detailed Estimate For Motorable Work in Road from Fajulahpur Uchya Vidhyalay Se Gamahari Pipra Tak damaged due to Heavy rain/flood for year 2020-2021**

Sr.	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
1	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 0 M to 700 M	1	30.00	1.00	0.30	9.00	M3		
		1	15.00	0.60	0.30	2.70	M3		
		1	15.00	0.50	0.40	3.00	M3		
		1	7.00	1.20	0.60	5.04	M3		
		1	2.00	1.50	0.80	2.40	M3		
		1	3.00	1.00	0.60	1.80	M3		
		1	5.00	1.40	0.45	3.15	M3		
		1	21.00	3.00	6.00	378.00	M3		
		1	12.00	1.10	1.20	15.84	M3		
		1	15.00	2.50	4.00	150.00	M3		
		1	5.00	1.40	0.80	5.60	M3		
		1	21.00	0.70	1.20	17.64	M3		
	Less for H.P.	0	1.23	1.23	0.95	0.00	M3	2412.11	1433203.2
						594.17	M3	2427.65	1442436.80
	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	2744.80 4159.56	0.00
									1433203.2
									1442436.80
	Add 1 % Contingency								14424.37
								Total	1456861.17
								Say	1456800.00

R 1447535.2  
Say Rs 14.475 L

*[Signature]*  
25/10/2020  
J.E.


*[Signature]*  
25.10.2020  
A.E.

*[Signature]*  
25/10/2020  
E.E.

Technically Approved For Rs 14.475 lac (Rupees fourteen lac  
forty seven thousand & five hundred) only

  
21/01/21

Superintending Engineer  
RWD Works Circle, Siwan

  
21/01/2021  
u