



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



of the Road :- Bagawn Chowk to Athar Road

RICT Muzaffarpur

SION Muzaffarpur East-1

CK Bandra

AL LENGTH OF ROAD	:	1.750	KM
-------------------	---	-------	----

STRUCTION COST	:	3.509	Lac
----------------	---	-------	-----

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

कार्य का नाम— बडगाँव चौक से आन्नर पथ

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड— बन्दरा

वित्तीय वर्ष— 2020-21

प्राक्कलित राशि— Rs. 3.509 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 3.509 लाख है, कार्य प्रमण्डल मुजफ्फरपुर खी-1, प्रखण्ड बन्दरा में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521, दिनांक 05.08.2020 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में ईट टुकड़ा स्थानीय बाधू भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी चटनोत्तर स्वीकृति अपेक्षित है।

Bumra
11.11.2020

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशासक बन्दरा

11.11.2020

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल बन्दरा

15.12.20

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमण्डल मुजफ्फरपुर

पूर्वी-1.

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- EXECUTIVE ENGINEER RWD (W) DIV. Muzaffarpur East-1
- 2 Name of Block/Road- Bancha / Badgaon down to other road.

A For Road

- 1 Damage Location/Chainage At many places
- 2 Damage Length 32.20 mtr.
- 3 Nature of Damage Complete traffic block due to Road Breach.
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works- Bricks Bat, local sand
 - ii Equipments/Tools being used in Restoration Works- JCB, tractor, Road Roller manual
 - iii Procedure Taken up in Restoration Works- Immediate Restoration of traffic
 - iv Restored Length 32.20 mtr.

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
 - i Material being used in Restoration Works-
 - ii Equipments/Tools being used in Restoration Works-
 - iii Procedure Taken up in Restoration Works-
 - iv Restored Length

N/A

Signature of JE/ AE/ EE


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of Road Bagawn Chowk to Athar Road

District Muzaffarpur

Block Bandra

Division Muzaffarpur East-1

Length of Road (in Km) 1.750 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Jhama metal	2.302
2	Sand Filling	1.207
3	H.P.	0.000
4	Bamboo Piles	0.000
	GRAND SUB TOTAL	3.509
TOTAL COST OF PROJECT IN LACS =		3.509

[Signature]
11.11.2020
JE
RWD

[Signature]
11.11.2020
AE
RWD

[Signature]
11.11.2020
EE
RWD

Technically approved for Rs. 350900=00 (Rs.
Three lacs fifty thousand nine hundred) only

[Signature]
22.12.20
SE, RWD
27/12/2020
Ward Circle, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Jhama metal Labour for consolidation in Jhama metal by Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller diver and khalasi making and maintaining diversion light barrier - do - do- danger signal etc. all complete .				
			Appendix - I	Cum	113.19		
				Total	113.19	2033.34	230153.75
2		11.20	Sand Filling Filling in foundation trenches as per drawing and technical specification Clause 305.3.9				
			Appendix - II	Cum	265.650		
				Total	265.65	454.53	120745.89
Total Cost :-							350899.64

11.11.2020
AE

11.12.20
E E

11.11.2020
JE